

**ENGINEERING INVESTIGATIONS AT
INACTIVE HAZARDOUS WASTE SITES IN THE
STATE OF NEW YORK
PHASE I INVESTIGATIONS**

**NYS DOT SPILL NO. 811902
VILLAGE OF PAWLING, DUTCHESS COUNTY, NEW YORK
SITE CODE: 314060**

Prepared for

**DIVISION OF SOLID AND HAZARDOUS WASTE
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
50 WOLF ROAD
ALBANY, NEW YORK 12233-0001**

Prepared by

**WEHRAN ENGINEERING, P.C.
666 EAST MAIN STREET
MIDDLETOWN, NEW YORK 10940**

WE Project No. 06281

February 1987

338912



1.0 EXECUTIVE SUMMARY

1.0 EXECUTIVE SUMMARY

The NYSDOT Spill No. 811902 site (New York Site Code 314060) is located along Route 22 in the Village of Pawling, Dutchess County, New York (Figure 1). The site consists of five parcels, approximately 20 acres in size. Groundwater in the vicinity of the site has been contaminated with petroleum hydrocarbons since the spring of 1982. Analytical data from samples taken at five private residences located in the vicinity indicate the presence of gasoline in each of the wells.

Subsequent hydrogeologic investigations by Empire Soils Investigations, Inc. and Thomson Associates identify the Amoco Station located along Route 22 in the Village of Pawling to be the major source of hydrocarbon contamination.

The preliminary Hazard Ranking System (HRS) scores for the NYSDOT Spill No. 811902 site are as follows: Migration Score (S_M) = 38.17; Direct Contact Score (S_{DC}) = 12.50; Fire and Explosion (S_{FE}) = 0. The migration score is attributable to a direct observed release to groundwater.

A Phase II work plan has not been suggested at the NYSDOT Spill No. 811902 site. The site is recommended for consideration by the NYSDEC Bureau of Remedial Action.

HRS WORKSHEETS

Facility Name: NYSDOT Spill No. 811902

Location: Route 22, Pawling, New York

EPA Region: II

Person(s) in Charge of the Facility:

Name of Reviewer: Stephen R. Petrisko **Date:** November 4, 1986

General Description of the Facility:

(For example: landfill, surface impoundment, pile, container; types of hazardous substances; location of the facility; contamination route of major concern; types of information needed for rating; agency action, etc.)

Gasoline contaminated water supply wells located in a commercial area along Route 22 in Pawling, New York. Chemicals present in wells include benzene, toluene, m-xylene, o-xylene, ethyl benzene, tetrachloroethylene, and dichlorobenzene.

Scores: $S_M = 38.17$ ($S_{gw} = 65.62$ $S_{sw} = 7.44$ $S_a = 0$)
 $S_{FE} = 0$
 $S_{DC} = 12.50$

GROUND WATER ROUTE WORK SHEET

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)
1 Observed Release	0 (45)	1	45	45	3.1
If observed release is given a score of 45, proceed to line 4 . If observed release is given a score of 0, proceed to line 2 .					
2 Route Characteristics					3.2
Depth to Aquifer of Concern	0 1 2 3	2		6	
Net Precipitation	0 1 2 3	1		3	
Permeability of the Unsaturated Zone	0 1 2 3	1		3	
Physical State	0 1 2 3	1		3	
Total Route Characteristics Score				15	
3 Containment	0 1 2 3	1		3	3.3
4 Waste Characteristics					3.4
Toxicity/Persistence	0 3 6 9 12 15 (18)	1	18	18	
Hazardous Waste Quantity	0 (1) 2 3 4 5 6 7 8	1	1	8	
Total Waste Characteristics Score			19	26	
5 Targets					3.5
Ground Water Use	0 1 2 (3)	3	9	9	
Distance to Nearest Well/Population Served	0 4 8 8 10 12 16 18 20 24 30 32 (35) 40	1	35	40	
Total Targets Score			44	49	
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			37,620	57,330	
7 Divide line 6 by 57,330 and multiply by 100 $S_{gw} = 65.62$					

SURFACE WATER ROUTE WORK SHEET

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)
[1] Observed Release	(0) 45	1	0	45	4.1
If observed release is given a value of 45, proceed to line [4] . If observed release is given a value of 0, proceed to line [2] .					
[2] Route Characteristics					4.2
Facility Slope and Intervening Terrain	0 1 2 (3)	1	3	3	
1-yr. 24-hr. Rainfall	0 1 (2) 3	1	2	3	
Distance to Nearest Surface Water	0 1 2 (3)	2	6	6	
Physical State	0 1 2 (3)	1	3	3	
Total Route Characteristics Score			14	15	
[3] Containment	0 1 2 (3)	1	3	3	4.3
[4] Waste Characteristics					4.4
Toxicity/Persistence	0 3 6 9 12 15 (18)	1	18	18	
Hazardous Waste Quantity	0 (1) 2 3 4 5 6 7 8	1	1	8	
Total Waste Characteristics Score			19	26	
[5] Targets					4.5
Surface Water Use	0 1 (2) 3	3	6	9	
Distance to a Sensitive Environment	(0) 1 2 3	2	0	6	
Population Served/Distance to Water Intake Downstream	(0) 4 6 8 10 12 16 18 20 24 30 32 35 40	1	0	40	
Total Targets Score			6	55	
[6] If line [1] is 45, multiply [1] x [4] x [5] If line [1] is 0, multiply [2] x [3] x [4] x [5]			4,788	64,350	
[7] Divide line [6] by 64,350 and multiply by 100 S_{sw} = 7.44					

AIR ROUTE WORK SHEET

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)
1 Observed Release	(0) 45	1	0	45	5.1
Date and Location:					
Sampling Protocol:					
If line 1 is 0, the S = 0. Enter on line 5 . If line 1 is 45, then proceed to line 2 .					
2 Waste Characteristics					5.2
Reactivity and Incompatibility	0 1 2 3	1		3	
Toxicity	0 1 2 3	3		9	
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1		8	
Total Waste Characteristics Score				20	
3 Targets					5.3
Population Within 4-Mile Radius	0 9 12 15 18 21 24 27 30	1		30	
Distance to Sensitive Environment	0 1 2 3	2		6	
Land Use	0 1 2 3	1		3	
Total Targets Score				39	
4 Multiply 1 x 2 x 3				35,100	
5 Divide line 4 by 35,100 and multiply by 100 $S_a = 0$					

	S	S ²
Groundwater Route Score (S _{gw})	65.62	4,305.98
Surface Water Route Score (S _{sw})	7.44	55.35
Air Route Score (S _a)	0	0
$S_{gw}^2 + S_{sw}^2 + S_a^2$		4,361.33
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2}$		66.04
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2} / 1.73$		S _M = 38.17

WORKSHEET FOR COMPUTING S_M

Insufficient data to score this route

FIRE AND EXPLOSION WORK SHEET


Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)
1 Containment	1 3	1		3	7.1
2 Waste Characteristics					7.2
Direct Evidence	0 3	1		3	
Ignitability	0 1 2 3	1		3	
Reactivity	0 1 2 3	1		3	
Incompatibility	0 1 2 3	1		3	
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1	-	8	
Total Waste Characteristics Score				20	
3 Targets					7.3
Distance to Nearest Population	0 1 2 3 4 5	1		5	
Distance to Nearest Building	0 1 2 3	1		3	
Distance to Sensitive Environment	0 1 2 3	1		3	
Land Use	0 1 2 3	1		3	
Population Within 2-Mile Radius	0 1 2 3 4 5	1		5	
Buildings Within 2-Mile Radius	0 1 2 3 4 5	1		5	
Total Targets Score				24	
4 Multiply 1 x 2 x 3				1,440	
5 Divide line 3 by 1,440 and multiply by 100 S F E =					

DIRECT CONTACT WORK SHEET

Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)
1 Observed Incident	0 45	1	0	45	8.1
If line 1 is 45, proceed to line 4 If line 1 is 0, proceed to line 2					
2 Accessibility	0 1 2 3	1	3	3	8.2
3 Containment	0 15	1	15	15	8.3
4 Waste Characteristics Toxicity	0 1 2 3	5	10	15	8.4
5 Targets					8.5
Population Within a 1-Mile Radius	0 1 2 3 4 5	4	8	20	
Distance to a Critical Habitat	0 1 2 3	4	0	12	
Total Targets Score			8	32	
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			2,700	21,600	
7 Divide line 6 by 21,600 and multiply by 100 SOC = 12.50					

TABLE OF CONTENTS
NYSDOT SPILL NO. 811902

	<u>Page Number</u>
1.0 EXECUTIVE SUMMARY	1-1
2.0 PURPOSE	2-1
3.0 SCOPE OF WORK	3-1
4.0 SITE ASSESSMENT	4-1
4.1 Site History	4-1
4.2 Site Topography	4-1
4.3 Site Hydrogeology	4-2
4.4 Site Contamination	4-3
5.0 PRELIMINARY APPLICATION OF THE HAZARD RANKING SYSTEM	5-1
5.1 Narrative Summary	5-1
6.0 ASSESSMENT OF DATA ADEQUACY AND RECOMMENDATIONS	6-1
6.1 Groundwater Route	6-1
6.2 Surface Water Route	6-1
6.3 Air Route	6-1
6.4 Fire and Explosion	6-1
6.5 Direct Contact	6-1
6.6 Recommendations	6-2
APPENDIX	




SCALE: 1" - 2000'
 TOPOGRAPHY TAKEN FROM
 PAWLING, NEW YORK - CONN.
 U.S.G.S. QUADRANGLE
 1958
 PHOTOREVISED 1971
 AMS 6267 II SE - SERIES 821
 7.5 MIN. SERIES



QUADRANGLE
 LOCATION

FIGURE 1

N.Y.S.D.O.T. SPILL NO.
 811902
 PAWLING, NEW YORK
 N.T.S.
 LAT. 41-32'-08"N LONG. 73-35'-08"W



- 1 Corral Ford
- 2 Surplus Store
- 3 Marios Pizza
- 4 Venezia Guest House
- 5 Amoco
- 6 Heinchon Dairy
- 7 Gold House
- 8 Stage Door Furniture
- 9 Burger King

SCALE: 1" - 200'

BASE MAP PROVIDED BY N.Y.S.D.O.T.
OIL SPILL ENGINEER.

DATE: 8/83



QUADRANGLE LOCATION

FIGURE 2
SITE SKETCH
N.Y.S.D.O.T. SPILL
NO. 811902
PAWLING, NEW YORK
N.T.S.

2.0 PURPOSE

2.0 PURPOSE

This Phase I investigation was conducted under contract to the New York State Department of Environmental Conservation Superfund Program to evaluate the potential environmental or public health hazard associated with past disposal activities at the NYSDOT Spill No. 811092 site. Divided into two parts, this initial investigation consisted of a detailed file review of available information and an initial site investigation. The culmination of this phase is the development of a preliminary Hazard Ranking System (HRS) score.

Where information is lacking and a final score cannot be computed, recommendations will be made for a Phase II investigation designed to verify the assumptions made in the preliminary scoring and to collect the additional data needed to complete the site assessment.

3.0 SCOPE OF WORK

3.0 SCOPE OF WORK

To complete the preliminary HRS score for the NYSDOT Spill No. 811902 site, the following scope of work was conducted:

- . A search of the following:
 - Available file information from federal, state, and municipal agencies
 - Published documents and maps from the U.S. Geological Survey, Soil Conservation Service and state agencies for geological, hydrological and topographical data
 - Available files, reports and drawings provided by site owners, operators and other knowledgeable parties.
- . Interviews with individuals having knowledge of the site

Information searched includes well logs, land use data, water usage patterns, critical habitats and endangered species data, meteorological data, hydrological, geological and topographical data, waste characteristics and demographic information.

Following the initial record search, a site inspection was conducted. The intent of the inspection is to verify existing file information and to conduct an HNU survey to screen for potential air releases. Items of specific interest in the site investigation include:

- . Overall site environmental conditions
- . The presence of disturbed areas
- . Visual signs of waste materials (drums, sludges, etc.)
- . The occurrence of leachate
- . Site topography

A detailed analysis was performed on all data collected in preparation of a preliminary HRS score. Where information was lacking and a final HRS score could not be computed, recommendations were made for a Phase II investigation. This investigation was designed to verify the assumptions made in the preliminary scoring and to collect the additional data needed to complete the site assessment. A summary of agencies contacted, contact person, address and information obtained follows.

SOURCES -- NYSDOT SPILL NO. 811902 SSTE
(Page 1)

<u>Name/Address/Phone</u>	<u>Type of Contact</u>	<u>Date</u>	<u>Information Provided</u>
Mr. John Czapor, Environmental Engineer USEPA, Region II 26 Federal Plaza New York, New York 10278 (212) 264-1573	Letter Office Visit	1/3/86 1/14/86 1/24/86	USEPA file information
Mr. Richard D. Spear, Chief Surveillance & Monitoring Branch USEPA, Region II Woodbridge Avenue Edison, New Jersey 08817 (201) 321-6685	Letter	1/3/86	None available
Mr. Lawrence A. Martens, District Chief U.S. Department of the Interior U.S. Geological Survey Albany District Office P.O. Box 1669 U.S. Post Office and Court House Albany, New York 12201 (518) 472-3107	Letter Telephone Call	1/3/86	Roger Waller responded - list of available county groundwater reports
Mr. Paul Dodd, State Conservationist U.S. Department of Agriculture Soil Conservation Service 771 James M. Hanley Federal Building 100 South Clinton Street Syracuse, New York 13260 (315) 423-5521	Letter Telephone Call	1/3/86 1/13/86	Fred Gilbert responded - list of available county soil surveys
Mr. Carl B. Sciple, Division Engineer Army Corps of Engineers New England Division 424 Trapelo Road Waltham, Massachusetts 02154 (617) 894-2400	Letter	1/3/86	None available
Mr. Frederick J. Scullin, Jr. U.S. Department of Justice U.S. Attorney, Northern District of New York 369 Federal Building 100 South Clinton Street Syracuse, New York 13260 (315) 423-5165	Letter	1/3/86	Craig Benedict responded - No information available

SOURCES -- NYSDOT SPILL NO. 811902 SITE
(Page 2)

<u>Name/Address/Phone</u>	<u>Type of Contact</u>	<u>Date</u>	<u>Information Provided</u>
Mr. Conrad Simon, Director Air and Waste Management Division United States Environmental Protection Agency Region 2 26 Federal Plaza New York, New York 10278	Letter	1/24/86	None available
Mr. Marsden Chen, Supervisor Division of Solid and Hazardous Waste New York State Department of Environmental Conservation 50 Wolf Road Albany, New York 12233 (518) 457-0639	Office Visit	12/4/85	NYSDEC file information
Mr. Ronald Tramontano, P.E. Chief, Surveillance and Investigation Division Bureau of Toxic Substance Assessment Surveillance and Investigation Section Empire State Plaza Corning Tower, Room 372 Albany, New York 12237	Letter Office Visit	1/3/86 1/9/86	File information
Robert H. Fakundiny, State Geologist Geological Survey of New York State State Education Department Division of Museum Services Albany, New York 12230 (518) 474-5816	Letter	1/3/86	County Groundwater Reports
Mr. Robert Abrams, Attorney General New York State Attorney General Department of Law State Capitol, Room 221 Albany, New York 12224 (581) 474-7330	Letter	1/3/86	No information
Mr. Geoff Bornemann, Principal Planner Capital District Regional Planning Commission 251 River Street, Monument Square Troy, New York 12180 (518) 272-1414	Letter	1/3/86	Rocco Ferraro responded with list of contact persons for sites

SOURCES -- NYSDOT SPILL NO. 811902 SITE
(Page 3)

<u>Name/Address/Phone</u>	<u>Type of Contact</u>	<u>Date</u>	<u>Information Provided</u>
Mr. Arthur Pasco Regional Administrative Officer NYSDOT Region 8 4 Burnett Boulevard Poughkeepsie, New York 12603	Letter Letter	1/3/86 1/28/86	Boring logs
New York State Department of Environmental Conservation 21 South Putt Corners Road New Paltz, New York 12561 (914) 255-5453	Office Visit	12/3/85	NYSDEC file information
Lucille P. Pattison County Executive Dutchess County 22 Market Street Poughkeepsie, New York 12601 (914) 431-2020	Letter	1/3/86	None available
William R. Steinhaus County Clerk Dutchess County 22 Market Street Poughkeepsie, New York 12601 (914) 431-2120	Letter	1/3/86	None available
Mr. Stephen J. Wing County Attorney Dutchess County 22 Market Street Poughkeepsie, New York 12601 (914) 431-2110	Letter	1/3/86	None available
Dr. John Scott Health Commissioner Dutchess County 22 Market Street Poughkeepsie, New York 12601 (914) 431-2015	Letter Office Visits	1/3/86	Background information
Mr. Roger A. Keley Planning Commissioner Dutchess County 47 Cannon Street Poughkeepsie, New York 12601 (914) 431-2480	Letter Telephone Call Office Visits	1/8/86 1/21/86 2/3/86	Natural Resources well logs, community water systems information

SOURCES -- NYSDOT SPILL NO. 811902 SITE
(Page 4)

<u>Name/Address/Phone</u>	<u>Type of Contact</u>	<u>Date</u>	<u>Information Provided</u>
Mr. James Spratt Public Works Commissioner Dutchess County 22 Market Street Poughkeepsie, New York 12601 (914) 431-2121	Letter Telephone Call	1/3/86 1/6/86	None available
Mr. Robert Vrana Solid Waste Management Dutchess County 22 Market Street Poughkeepsie, New York 12601 (914) 431-2115	Letter Telephone Call	1/3/86 1/6/86	None available
Soil and Water Conservation District P.O. Box 37 Farm & Home Center Millbrook, New York 12545 Attn: District Conservationist (914) 677-8011	Letter Letter	1/3/86 1/13/86	Irrigation practices County soil survey
Jay Maxwell, Sr. Route 22 Pawling, New York 12564	Personal Communication		Site access, site history
Sheryl Herrington Town Clerk Pawling, New York 12564 (914) 855-1122	Telephone Call	11/3/86	Village of Pawling water resources

4.0 SITE ASSESSMENT

4.0 SITE ASSESSMENT

4.1 SITE HISTORY

The NYSDOT Spill No. 811902 site is located along Route 22 in the Village of Pawling, Dutchess County, New York. The site consists of five parcels of land, approximately 20 acres in size. A gasoline contaminated well at Corral Ford was reported by the Dutchess County Health Department on March 22, 1982. Additional water samples taken in the vicinity of the site resulted in the discovery of gasoline contaminated wells at Mario's Pizza, Maxwell Engine Rebuilders, Venezia's Guest House, and Heinchan Dairy. Activated carbon filters were supplied by NYSDOH for private wells in the area. These filters are still in use.

On March 31, 1983 the New York State Department of Transportation authorized Empire Soils Investigations, Inc. to perform a complete hydrogeologic study of the site. As part of the initial site assessment performed by Empire Soils Investigations, Inc., a total of 19 monitoring wells were installed in the project area. Results of chemical analyses performed on groundwater samples obtained on June 22-24, 1983 from the monitoring wells conclude that the major source of hydrocarbon contamination encountered in the project area to be the Amoco gas station located along Route 22. This station is owned by Cole Petroleum of 35 Market Street, Cold Springs, New York. Presently, Cole Petroleum has not responded to NYSDEC requests to initiate clean-up activities.

4.2 SITE TOPOGRAPHY

The NYSDOT Spill No. 811902 site is located along Route 22, approximately three-quarters of a mile north of the Putnam-Dutchess County border. The area is predominately commercial with several surrounding businesses within 500 feet. Drainage in the vicinity of the site is via Brady Brook, a New York State Class C brook. Brady Brook flows approximately one mile past the site and to the southwest before flowing into the Great Pattern Swamp, a NYSDEC unique and significant habitat area. The Great Swamp is drained by the East Branch of the Croton River. The Great Swamp surface is New York State Class C in the vicinity of the site.

Elevation at the site is approximately 470 feet MSL. Higher elevation exists to the north, east, and south. On site, slopes are to the southeast for approximately 1,000 feet, while overall slopes are to the south.

4.3 SITE HYDROGEOLOGY

Information obtained from Empire Soils Investigations, Inc. and Thomsen Associates report, Hydrogeologic Evaluations Oil Spill, Village of Pawling, Dutchess County, New York indicates the site lies within the Hudson Hills physiographic province of New York State, an area characterized by igneous and metamorphic bedrock. Bedrock underlying the site consists of units of the Orodovician age Stockbrdige formation. Monitoring wells installed by Empire Soils Investigations, Inc. indicates bedrock underlying the site ranges in depth from 15 to 30 feet and consists of gray to white dolomite marble. This marble is extensively fractured and slickensided (polished and striated). Voids, soil-filled seams, weak friable zones of variable extent were commonly encountered during diamond core drilling operations and are detailed on the hydrogeologic logs.

The overburden in this area consists of a horizon of stratified glacial outwash classified by the United States Department of Agriculture (1955) as members of the Merrimae soil series. These soils are predominantly interbedded sand and gravels and are considered to be very rapidly permeable.

Water level observations in the monitoring wells indicate the water table to be situated in close proximity to the bedrock surface. Water level data obtained from the monitoring wells on May 19, 1983 were used to contour the water table over the site. These readings indicate the major component of groundwater flows beneath the site to be southward, discharging to Brady Brook south of the site, with minor southwestward and southeastward flow components also apparent. Water level data obtained from the monitoring wells indicates a general vertical downward flow component between the overburden sand and gravel and carbonate bedrock, providing a mechanism for migration of contaminants through the relatively permeable unconsolidated deposits and into the underlying bedrock aquifer.

This mechanism operates independently of, but may be enhanced by, downward flow induced locally by drawdown in water supply wells. Therefore, it is assumed that the overburden sand and gravel aquifer and the carbonate bedrock aquifer are hydraulically connected.

4.4 SITE CONTAMINATION

Results of chemical analysis performed on groundwater samples obtained on June 22-24, 1983 downgradient of the site in Monitoring Wells B-3, B-11R, and B-16R indicate hydrocarbon contamination of groundwater where the presence of gasoline is confirmed. Lesser concentrations of hydrocarbon compounds were detected downgradient of the site in Monitoring Wells B-17, B-6, and B-18R, while the remaining samples contained less than one part per billion for each of the parameters analyzed. Analysis of groundwater samples from Monitoring Well B-14, upgradient of the Amoco station, indicate no contamination of groundwater by hydrocarbons at that point. These chemical analysis results, in conjunction with the groundwater flow beneath the site to be southward, indicate a hydrocarbon (gasoline) contamination plume emanating from the Amoco station located along Route 22 in the Village of Pawling.

Actions at the site are being handled by NYSDEC, under the Division of Water, Oil Spills Program. Cost Recovery is being handled by the Attorney General's Office.


**5.0 PRELIMINARY APPLICATION OF THE
HAZARD RANKING SYSTEM**

5.0 PRELIMINARY APPLICATION OF THE HAZARD RANKING SYSTEM

5.1 NARRATIVE SUMMARY

The NYSDOT Spill No. 811902 site is located along Route 22 in the Village of Pawling, Dutchess County, New York. The site consists of five parcels of land, approximately 20 acres in size. Groundwater in the vicinity of the site has been contaminated with petroleum hydrocarbons since the spring of 1982. Subsequent hydrogeologic investigations performed by Empire Soils Investigations, Inc. included the installation of 19 monitoring wells on site. Results of chemical analysis performed on groundwater samples obtained on June 22-24, 1983 from the monitoring wells conclude that the major source of hydrocarbon contamination encountered in the project area to be the Amoco gas station located along Route 22 in Pawling, New York. This gas station is owned by Cole Petroleum of Cold Springs, New York.

LOCATION



SCALE: 1" - 2000'
 TOPOGRAPHY TAKEN FROM
 PAWLING, NEW YORK - CONN.
 U.S.G.S. QUADRANGLE
 1958
 PHOTOREVISED 1971
 AMS 6267 II SE - SERIES 821
 7.5 MIN. SERIES



QUADRANGLE
 LOCATION

FIGURE 1
 N.Y.S.D.O.T. SPILL NO.
 811902
 PAWLING, NEW YORK
 N.T.S.

LAT. 41-32'-08"N LONG. 73-35'-08"W

HRS DOCUMENTATION RECORDS

June 28, 1982

**DOCUMENTATION RECORDS
FOR
HAZARD RANKING SYSTEM**

INSTRUCTIONS: The purpose of these records is to provide a convenient way to prepare an auditable record of the data and documentation used to apply the Hazard Ranking System to a given facility. As briefly as possible summarize the information you used to assign the score for each factor (e.g., "Waste quantity = 4,230 drums plus 800 cubic yards of sludges"). The source of information should be provided for each entry and should be a bibliographic-type reference that will make the document used for a given data point easier to find. Include the location of the document and consider appending a copy of the relevant page(s) for ease in review.

FACILITY NAME: NYSDOT Spill No. 811902

LOCATION: Route 22, Pawling, New York

GROUND WATER ROUTE

1 OBSERVED RELEASE

Contaminants detected (5 maximum):

Benzene
Toluene
M-xylene
O-xylene
Ethyl benzene

Score = 45

Source: References 1, 2

Rationale for attributing the contaminants to the facility:

Analysis of water samples taken from downgradient monitoring wells indicate hydrocarbon contamination in relation to samples taken from upgradient well exhibit no contamination.

Source: Reference 2

2 ROUTE CHARACTERISTICS

Depth to Aquifer of Concern

Name/description of aquifer(s) of concern:

There are two aquifers of concern at this site. They are the sand and gravel aquifer overlying the carbonate bedrock. According to Reference 2, the aquifers are hydraulically connected.

Source: References 2, 3, 10

Depth(s) from the ground surface to the highest seasonal level of the saturated zone (water table(s)) of the aquifer of concern:

Nineteen monitoring wells have been installed on site. Well depths vary from 11.75 to 38 feet. In the wells, reported water levels range from 10 feet to 19 feet.

Source: References 1, 2, 3

Depth from the ground surface to the lowest point of waste disposal/storage:

Depth of burial unknown; assume 6 feet. Depth of water table 10 feet. Distance between waste and water table 4 feet.

Source: References 1, 2, 5

Net Precipitation

Mean annual or seasonal precipitation (list months for seasonal):

44 inches

Source: Reference 5

Mean annual lake or seasonal evaporation (list months for seasonal):

28 inches

Source: Reference 5

Net precipitation (subtract the above figures):

16 inches

Score = 3

Source: Reference 5

Permeability of Unsaturated Zone

Soil type in unsaturated zone:

The soil types are predominately interbedded sands and gravels and are considered very rapidly permeable.

Source: Reference 2

Permeability associated with soil type:

10^{-3} cm/sec.

Score = 3

Source: Reference 5

Physical State

Physical state of substances at time of disposal (or at present time for generated gases):

Gasoline spill
Liquid

Score = 3

Source: References 2, 3, 4

3 CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

Containers: groundwater data indicates tanks in leaking condition, no liner, no leachate collection system. No method of waste containment observed or documented.

Source: References 1, 2, 3, 4

Method with highest score:

No method of containment.

Score = 3

Source: References 1, 2, 3, 4

4 WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

Benzene	Trichloroethylene
Ethyl benzene	1,4-Dichlorobenzene
Tetrachloroethylene	1,3-Dichlorobenzene
Toluene	1,2-Dichlorobenzene
M-xylene	
O-xylene	

Source: References 2, 3, 4

Compound with highest score:

1,4-Dichlorobenzene = 15

Benzene = 12

Dichlorobenzene (NOS) = 18

Source: References 2, 3, 4

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

Total quantity of hazardous waste present unknown.

Score = 1

Source: References 1, 2, 3, 4

Basis of estimating and/or computing waste quantity:

No data exists for quantity of waste but analysis of water samples from monitoring wells confirm presence of gasoline.

Source: References 2, 3, 4

5 TARGETS

Ground Water Use

Use(s) of aquifer(s) of concern within a 3-mile radius of the facility:

Residential drinking water; no alternative unthreatened sources available.

Score = 3

Source: References 1, 2, 3, 4, 8

Distance to Nearest Well

Location of nearest well drawing from aquifer of concern or occupied building not served by a public water supply:

On site five supply wells draw from aquifer of concern.

Source: References 1, 2, 3, 4

Distance to above well or building:

On site; distance to well is zero.

Value = 4

Source: References 1, 2, 3, 4

Population Served by Ground Water Wells Within a 3-Mile Radius

Identified water-supply well(s) drawing from aquifer(s) of concern within a 3-mile radius and populations served by each:

One community well and one surface water intake, population served = 2,000.

Rural population = 767 houses, population = 2,915.

Source: References 8, 9

Computation of land area irrigated by supply well(s) drawing from aquifer(s) of concern within a 3-mile radius, and conversion to population (1.5 people per acre):

No known irrigation occurs within three miles.

Value = 0

Source: Reference 11

Total population served by ground water within a 3-mile radius:

Community population = 2,000; private dwellings = $767 \times 3.8 = 2,915$; total population = 4,915

Score = 4

Matrix Score = 35

Source: References 8, 9

SURFACE WATER ROUTE

1 OBSERVED RELEASE

Contaminants detected in surface water at the facility or downhill from it (5 maximum):

At this time, no observed release of contaminants to the surface water route has been reported although gasoline concentrations have been detected in on-site monitoring wells. Groundwater discharge to surface water may be occurring.

Score = 0

Source: References 1, 2, 3, 4

Rationale for attributing the contaminants to the facility:

Not applicable

2 ROUTE CHARACTERISTICS

Facility Slope and Intervening Terrain

Average slope of facility in percent:

Up to 10 percent.

Source: Reference 1

Name/description of nearest downslope surface water:

Brady Brook within 1,000 feet of site.

Source: Reference 1

Average slope of terrain between facility and above-cited surface water body in percent:

Five to six percent.

Matrix Score = 3

Source: Reference 1

Is the facility located either totally or partially in surface water?

No

Score = 3

Source: Reference 1

Is the facility completely surrounded by areas of higher elevation?

No

Source: References 1, 2, 3, 4

1-Year 24-Hour Rainfall in Inches

2.5 inches

Score = 2

Source: Reference 5

Distance to Nearest Downslope Surface Water

Approximately 1,000 feet to nearest surface water.

Score = 3

Source: Reference 1.

Physical State of Waste

Liquid

Score = 3

Source: References 2, 3, 4

3 CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

No method of waste containment observed or documented.

Source: References 1, 2, 3, 4

Method with highest score:

No method of containment.

Score = 3

Source: References 1, 2, 3, 4

4 WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

Benzene	Trichloroethylene
Ethyl benzene	1,4-Dichlorobenzene
Tetrachloroethylene	1,3-Dichlorobenzene
Toluene	1,2-Dichlorobenzene
M-xylene	
O-xylene	

Source: References 2, 3, 4

Compound with highest score:

1,4-Dichlorobenzene = 15

Benzene = 12

Dichlorobenzene (NOS) = 18

Source: References 2, 3, 4

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum);

Total quantity of hazardous waste present unknown.

Score = 1

Source: References 1, 2, 3, 4

Basis of estimating and/or computing waste quantity:

No data exists for quantity of waste but analysis of water samples from monitoring wells confirm presence of gasoline.

Source: References 2, 3, 4

5 TARGETS

Surface Water Use

Use(s) of surface water within 3 miles downstream of the hazardous substance:

Use of surface water within three miles downstream of the site includes fishing.

Score = 2

Source: Reference 6

Is there tidal influence?

No

Source: Reference 1

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

Not applicable

Source: Reference 1

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

A 50-60 acre wetland is located within three-quarter of a mile.

Score = 1

Source: Reference 1

Distance to critical habitat of an endangered species or national wildlife refuge, if 1 mile or less:

There is no significant wildlife areas within one mile.

Score = 0

Source: Reference 7

Population Served by Surface Water

Location(s) of water-supply intake(s) within 3 miles (free-flowing bodies) or 1 mile (static water bodies) downstream of the hazardous substance and population served by each intake:

No surface water intakes are located within the areas of concern.

Score = 0

Source: Reference 8

Computation of land area irrigated by above-cited intake(s) and conversion to population (1.5 people per acre):

No known uses of surface water for irrigation have been identified.

Source: Reference 11

Total population served:

No known uses of surface water have been identified.

Source: Reference 8

Name/description of nearest of above water bodies:

Brady Brook within 1,000 feet of site.

Source: Reference 1

Distance to above-cited intakes, measured in stream miles:

No surface water intakes have been identified.

Source: Reference 8

AIR ROUTE

1 OBSERVED RELEASE

Contaminants detected:

To score an air release, qualitative air sampling is required along with details on the sampling protocol and the meteorological conditions during the time of sampling. No qualitative air sampling has been performed.

Score = 0

Source: Reference 1 and File Review

Date and location of detection of contaminants:

Not applicable

Methods used to detect the contaminants:

Not applicable

Rationale for attributing the contaminants to the site:

Not applicable

2 WASTE CHARACTERISTICS

Reactivity and Incompatibility

Most reactive compound:

Not applicable

Most incompatible pair of compounds:

Not applicable

Toxicity

Most toxic compound:

Not applicable

Hazardous Waste Quantity

Total quantity of hazardous waste:

Not applicable

Basis of estimating and/or computing waste quantity:

Not applicable

3 TARGETS

Population Within 4-Mile Radius

Circle radius used, give population, and indicate how determined:

0 to 4 mi

0 to 1 mi

0 to 1/2 mi

0 to 1/4 mi

Not applicable

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

Not applicable

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

Not applicable

Distance to critical habitat of an endangered species, if 1 mile or less:

Not applicable

Land Use

Distance to commercial/industrial area, if 1 mile or less:

Not applicable

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

Not applicable

Distance to residential area, if 2 miles or less:

Not applicable

Distance to agricultural land in production within past 5 years, if 1 mile or less:

Not applicable

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

Not applicable

Is a historic or landmark site (National Register of Historic Places and National Natural Landmarks) within the view of the site?

Not applicable

FIRE AND EXPLOSION

1 CONTAINMENT

Hazardous substances present:

To score the fire and explosion hazard mode either a state or local fire marshall must have certified that the facility presents a significant fire or explosion threat to the public or to a sensitive environment, or there must be a demonstrated threat based on field observations (e.g. combustible gas indicator readings). The available records give no indication that either one of these tasks has been done. Further, the available data do not suggest any imminent threat of fire and explosion at this site. Therefore the route score cannot be completed.

Source: Reference 1 and File Review

Type of containment, if applicable:

Not applicable

2 WASTE CHARACTERISTICS

Direct Evidence

Type of instrument and measurements:

Not applicable

Ignitability

Compound used:

Not applicable

Reactivity

Most reactive compound:

Not applicable

Incompatibility

Most incompatible pair of compounds:

Not applicable

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility:

Not applicable

Basis of estimating and/or computing waste quantity:

Not applicable

3 TARGETS

Distance to Nearest Population

Not applicable

Distance to Nearest Building

Not applicable

Distance to Sensitive Environment

Distance to wetlands:

Not applicable

Distance to critical habitat

Not applicable

Land Use

Distance to commercial/industrial area, if 1 mile or less:

Not applicable

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

Not applicable

Distance to residential area, if 2 miles or less:

Not applicable

Distance to agricultural land in production within past 5 years, if 1 mile or less:

Not applicable

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

Not applicable

Is a historic or landmark site (National Register of Historic Places and National Natural Landmarks) within the view of the site?

Not applicable

Population Within 2-Mile Radius

Not applicable

Buildings Within 2-Mile Radius

Not applicable

DIRECT CONTACT

1 OBSERVED INCIDENT

Date, location, and pertinent details of incident:

There has been no confirmed incident in which direct contact with hazardous waste has been observed or documented.

Score = 0

Source: Reference 1

2 ACCESSIBILITY

Describe type of barrier(s):

No barriers are present and there are no restrictions to site access.

Score = 3

Source: Reference 1

3 CONTAINMENT

Type of containment, if applicable:

No evidence of containment measures has been found during site investigation or file review.

Score = 15

Source: Reference 1

4 WASTE CHARACTERISTICS

Toxicity

Compounds evaluated:

Benzene

Ethylbenzene

Toluene

Tetrachloroethylene

M-xylene

O-xylene

Source: References 1, 2

Compound with highest score:

Benzene

Score = 2

Source: Reference

5 TARGETS

Population within one-mile radius

Within one mile radius, population = 403

Score = 2

Source: House Count, USGS Pawling, New York Quadrangle

Distance to critical habitat (of endangered species)

There are no critical habitats within one mile.

Score = 0

Source: Reference 7

WEHRAN ENGINEERING - SITE INSPECTION FORM**1. IDENTIFICATION**

NYSDOT Spill No. 811902

Site Name

Dutchess

County

314060

NY Number

Region III

NYSDEC Region

2. LOCATION

Route 22

Street/Route No.

Town

Pawling

Village

City

Pawling

USGS Quadrangle

3. INSPECTION

1/8/86

Date of Inspection

1:00 P.M.

Time of Inspection

clear, 20°, Cold

Weather Conditions and Snow Cover

WE Inspectors (Name)**Title****Phone Number**

David B. Tompkins

Environmental Scientist

(914) 343-0660

Stephen Petrisko

Environmental Scientist

(914) 343-0660

Other Inspectors (Name)**Affiliation****Phone Number**

Reference 1.2

<u>Site Reps. Interviewed</u>	<u>Affiliation</u>	<u>Phone Number</u>
<u>Mr. Jay Maxwell, Sr.</u>	<u>Resident</u>	<u></u>
<u>Mr. Jay Maxwell, Jr.</u>	<u>Resident</u>	<u></u>
<u></u>	<u></u>	<u></u>

4. **SITE DESCRIPTION**

4.1 Site History

Active x

Inactive

Years of Operation: Unknown

Owner(s): Unknown

4.2 Storage/Disposal (Check all that apply)

	<u>Size/Amount</u>	<u>Unit of Measure</u>
<u> </u> A. Surface Impoundment	<u></u>	<u></u>
<u> </u> B. Piles	<u></u>	<u></u>
<u> </u> C. Drums, Above Ground	<u></u>	<u></u>
<u> </u> D. Tank, Above Ground	<u></u>	<u></u>
<u> x</u> E. Tank, Below Ground	<u></u>	<u></u>
<u> </u> F. Landfill	<u></u>	<u></u>
<u> </u> G. Landfarm	<u></u>	<u></u>
<u> </u> H. Open Dump	<u></u>	<u></u>
<u> x</u> I. Spill	<u></u>	<u></u>
<u> </u> J. Well Field	<u></u>	<u></u>
<u> </u> K. Other (<u> </u>)	<u></u>	<u></u>

4.3 Treatment (Check all that apply)

- | | |
|--|--|
| <input type="checkbox"/> A. Burning | <input type="checkbox"/> E. Waste Oil Processing |
| <input type="checkbox"/> B. Incineration | <input type="checkbox"/> F. Solvent Recovery |
| <input type="checkbox"/> C. Underground Injection | <input type="checkbox"/> G. Other Recycling/Recovery |
| <input type="checkbox"/> D. Chemical/Physical/Biological | <input type="checkbox"/> H. Other (_____) |

4.4 Waste Substances Observed (include hazardous)

Benzene, Toluene, Xylene, Ethyl benzene, Tetrachloroethylene

4.5 Containment of Wastes (describe)

None

4.6 Accessibility of Public to Wastes (describe)

No method of containment observed

5. ENVIRONMENTAL MEASUREMENTS (DURING INSPECTION)**5.1 HNU/OVA Readings (Note locations on site sketch)**

<u>Location</u>	<u>Value (ppm)</u>	<u>Classification</u>
Background	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

Method/Instrument: _____

5.2 Site Topography (Describe relative to regional features)

Commercial area, located in the valley of the East branch river.

Reference 1.5

5.3 Site Slope (percent) up to 10%

Reading
(Percent)

Read from highest disposal area surface to edge of disposal area.

If disposal area is within enclosed basin, report as zero.

Average

5.4 Prevailing Direction of Site Slope Southward to Southwestward

5.5 Distance to Nearest Downslope Surface Waters (from edge of disposal area)

<u>Name/Description</u>	<u>Distance</u>	<u>Units</u>	<u>Permanent/Intermittent</u>
Tributary to	1,000	ft	
east branch of the			
Croton River.			

5.6 Intervening Terrain Slope to Nearest Downslope Waters (from edge of disposal area)

<u>Name/Description</u>	<u>Reading (Percent)</u>
Tributary to east branch of the Croton River (Brady Brook)	5-6%

5.7 Distance to Nearest Downslope Wetlands (5-acre minimum)

<u>Size (Acres)</u>	<u>Distance</u>	<u>Units</u>
min. 25 acres	3/4	mi

5.8 Distance to Critical Habitat (endangered species)

<u>Name/Location</u>	<u>Distance</u>	<u>Units</u>
N/A		

5.9 Observed Site Geology (Describe from visual observations)

Overburden (soils)	Unknown
Bedrock	Unknown
Depth to Rock	Unknown

5.10 Distance to Nearest Potable Well (Identify on topographic map)

<u>Type (Private/Community/Municipal)</u>	<u>Distance</u>	<u>Units</u>
Private	on-site	

5.11 Distance to Nearest Off-Site Building

Within one-half _____ miles.

5.12 Describe Source and Use of Water on Site

Drinking Water

6.0 LAND USE**6.1 Distance to Nearest:**

Residential Area	_____ miles
Commercial/Industrial	Adjacent _____ miles
Recreation Use	_____ miles
Forest	_____ miles
Wildlife Reserve	_____ miles
Historic/Landmark Site	_____ miles
Prime Agricultural Land	_____ miles
Agricultural Land	_____ miles

7.0 SITE EVALUATION**7.1 Landfills/Open Dumps/Piles (Use N/A if not applicable) N/A**

Adequacy of Cover: _____

Adequacy of Runoff Diversion: _____

Potential/Observed Ponding: _____

Waste Piles Stabilized/Unstabilized: _____

Permeability/Compatibility of Liner: _____

Observed Seeps: _____

Adequacy of Leachate Collection: _____

Adequacy of Run-On Controls: _____

7.2 Surface Impoundments Size/Capacity

Adequacy of Diking/Diversion Structures: _____

Adequacy of Freeboard: _____

Potential/Observed Leaking: _____

Permeability/Compatibility of Liner: _____

Adequacy of Run-On Control: _____

Adequacy of Leachate Collection System: _____

7.3 Containers

Number and Type of Containers Observed: _____

Container Condition: _____

Observed Leaking (during inspection): _____

Evidence of Previous Ground Spills: _____ Suspected evidence of previous spills

Evidence of Underground Tank Leaking: _____ Suspected

Adequacy of Containment/Diversion Structures: _____

8.0 MONITORING/OBSERVATION WELLS**8.1 Number of On-Site Wells:**

19

Diameter and Materials:

Two inches PVC

8.2 Number of Off-Site Wells:**Diameter and Materials****8.3 Well Identification and Inspection (Include on-site sketch)** (See next page)

							<u>Water Level (ft)¹</u>	
<u>Well No.</u>	<u>Location/ Gradient</u>	<u>Total Depth</u>	<u>Screen Interval</u>	<u>Top of Water</u>	-	<u>Stickup</u>	=	<u>Depth to Water</u>
_____	_____	_____	_____	_____	-	_____	=	_____
_____	_____	_____	_____	_____	-	_____	=	_____
_____	_____	_____	_____	_____	-	_____	=	_____
_____	_____	_____	_____	_____	-	_____	=	_____
_____	_____	_____	_____	_____	-	_____	=	_____
_____	_____	_____	_____	_____	-	_____	=	_____
_____	_____	_____	_____	_____	-	_____	=	_____
_____	_____	_____	_____	_____	-	_____	=	_____
_____	_____	_____	_____	_____	-	_____	=	_____

¹Measurements taken during site inspection to accuracy of 0.01 ft.**8.4 Water Level Instrument/Method:**

Electric Probe

8.5 Condition of Wells/Seals:Good

8.6 Well Records (from site owner, operator, or contractor)Wells Installed by (Driller): Empire Soils InvestigationsInstalled for: Empire Soils and Thomsen AssociatesTested by (lab): Camo Labs, Galson Technical ServicesData Obtained by WE (yes/no): YesBoring Logs Obtained by WE (yes/no): Yes**8.7 Headspace HNU/OVA Readings**

<u>Well No.</u>	<u>Reading (ppm)</u>	<u>Classification</u>
Background	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>

Reference 1.11

9. COMMENTS AND INTERVIEW NOTES (IDENTIFY SOURCES)

This image shows a single sheet of white paper with horizontal black ruling lines. The lines are evenly spaced and run across the width of the page. There are approximately 20 lines visible. The paper has a slightly textured appearance and some minor blemishes or dust specks. The edges of the paper are slightly irregular.

Ref. 2:1



REG. DIR.	PERSON.
AST. TO RD.	PLANNING
ADMIN.	REAL EST.

REC'D DOT OCT 25 1983 REG 8

CONST.	SOILS MAT.
DESIGN	TRAFFIC
EORT. MCT.	CEN. FILE
HWY. MAINT.	

HYDROGEOLOGIC EVALUATIONS
OIL SPILL
VILLAGE OF PAWLING
DUTCHESS COUNTY, NEW YORK

SPILL NO. 811902
P.I.N. SP 1633.701

for

NEW YORK STATE
DEPARTMENT OF TRANSPORTATION
OIL SPILL PREVENTION & CONTROL BUREAU

and

NEW YORK STATE
DEPARTMENT OF TRANSPORTATION
REGION NO. 8

JOHN SCHAFF
Assistant Regional Oil Spill Engineer

prepared by

EMPIRE SOILS INVESTIGATIONS, INC.
&
THOMSEN ASSOCIATES

File No. GTA-82-17J
October 1983



October 24, 1983

New York State Department
of Transportation
4 Burnett Boulevard
Poughkeepsie, New York 12603

Attention: John Schaff
Assistant Regional Oil Spill Engineer

Reference: Hydrogeologic Evaluations
Hydrocarbon Spill
Pawling, Dutchess County, New York
Spill No. 811902
P.I.N. SP 1633.701

Gentlemen:

Enclosed please find three (3) copies of our report of findings prepared in connection with the referenced hydrocarbon spill.

This report presents the results of work performed on this project by Empire-Thomsen through August 31, 1983. The information contained in this report incorporates and supersedes our previously submitted correspondence.

The findings of this study indicate the major source of hydrocarbon contamination encountered in the monitoring wells in the project area to be the Amoco station on NYS Route 22. Observations during the course of this study show this contamination to be primarily dissolved hydrocarbon compounds; no measureable free product has been noted at any of the data points in the area.

This study was intentionally restricted to the upper portions of the local aquifer in efforts to determine the apparent source area(s) of hydrocarbon contamination. However, for spill remediation purposes the need to visualize this contamination problem in three dimensions cannot be overstressed. In addition to the presence of hydrocarbons in the upper zone of the aquifer, volatile contaminants are found in groundwater at depths indicating their vertical migration due to pumping from deep water supply wells. In the absence of construction details of these supply wells, or a deep groundwater quality monitoring network,



New York State Department
of Transportation
October 24, 1983
Page 2

the full extent and severity of the vertical component of contamination cannot presently be defined. Accordingly, appropriate additional work as outlined in the Recommendations section of this report is strongly urged to resolve this problem.

In terms of spill remediation a coordinated approach, involving elimination of source(s) of contaminant input as well as the mechanisms of vertical contaminant migration within the aquifer, is recommended. Subsequent to implementation of such actions ongoing assessment of local groundwater quality by means of periodic sampling from the monitoring wells is warranted, as detailed in the report.

Should you have any questions or comments regarding the contents of this report, please feel free to contact our office.

We appreciate the opportunity to assist your office with this investigation, and we look forward to working with you on future projects.

Respectfully submitted,

THOMSEN ASSOCIATES
&
EMPIRE SOILS INVESTIGATIONS, INC.

Ronald Ausburn *SA*

Ronald Ausburn, CPGS
Project Manager

Marjory B. Rinaldo-Lee, CPGS
Senior Hydrogeologist
(Reviewer)

TABLE OF CONTENTS

Cover Letter

<u>Section</u>		<u>Page</u>
1.0	<u>INTRODUCTION</u>	
1.1	Project Initiation	1
1.2	Project Objective and Scope	2
1.3	Previous Work	3
1.4	Potential Hydrocarbon Sources	4
1.5	Supply Well Inventory	4
2.0	<u>INVESTIGATIVE METHODOLOGY</u>	
2.1	Subsurface Investigations.....	5
2.2	Hydrogeologic Data	7
2.3	Geochemical Data	8
3.0	<u>FINDINGS OF INVESTIGATIONS</u>	
3.1	Site Location	9
3.2	General Local Geology	9
3.3	Site Specific Geology	11
3.4	Local Hydrogeologic Regime	14
3.5	Hydrocarbon Contamination	16
3.6	Remediation & Replacement Water Supplies	18
4.0	<u>CONCLUSIONS AND RECOMMENDATIONS</u>	
4.1	Conclusions	21
4.2	Recommendations	22
	<u>REFERENCES</u>	24

List of Appendices

- Appendix A - Drawings
- Appendix B - Hydrogeologic Logs & Key
- Appendix C - Tabulated Water Level Data
- Appendix D - Mechanical Analysis Results
- Appendix E - Chemical Analysis Results

SECTION 1

INTRODUCTION

1.1 PROJECT INITIATION

1.1.1 This report presents the results of ongoing studies by Empire Soils Investigations, Inc. and its affiliated geotechnical consultant, Thomsen Associates, related to hydrocarbon contamination of groundwater in the vicinity of the village of Pawling, Dutchess County, New York. This particular phase of study was authorized by the office of the New York State Department of Transportation (NYSDOT) Regional Oil Spill Engineer (ROSE) on March 31, 1983, and was completed under the auspices of an Agreement (Contract D200165) between the NYSDOT Oil Spill Prevention and Control Bureau and Empire Soils Investigations, Inc., pertaining to hydrogeologic investigations at oil spill sites.

1.1.2 Personnel involved in this study included the Assistant Regional Oil Spill Engineer for NYSDOT Region 8, John Schaff; Ronald Ausburn, CPGS, engineering geologist and project manager for Thomsen Associates; and Stephen Rossello, hydrogeologist with Thomsen Associates.

1.1.3 General aspects of the field exploration program dealt with herein, including specifications and locations for test borings and groundwater monitors, were agreed upon by the office of the Regional Oil Spill Engineer and Thomsen Associates prior to initiation of such work. Specific material sampling and monitor installation details were as dictated by the actual field conditions encountered. Exploratory drilling and monitoring well installations were performed by personnel and equipment from the Groton, New York operations office of Empire Soils Investigations, Inc.

Necessary site survey work was performed by Thomsen Associates personnel. For the purposes of this report, all elevations are referenced to an assumed datum of 100.0 feet at the benchmark location shown on drawings attached hereto.

1.2 PROJECT OBJECTIVE AND SCOPE

1.2.1 The goal of this investigation was to determine both the source area(s) and areal extent of hydrocarbon contamination documented by the Regional Oil Spill Engineer in several water supply wells in the project area. The supply wells involved are those serving Corral Ford, Marios Pizza, Heinchon Dairy and Hawkey's Surplus Store. If feasible, the site-specific data obtained in the process of meeting these objectives was to be utilized for formulation of general replacement supply well parameters and contamination abatement alternatives.

1.2.2 As formally authorized by the office of the Regional Oil Spill Engineer, Empire Soils Investigations, Inc./Thomsen Associates were to complete subsurface investigations and hydrogeologic analyses required to satisfy project objectives. Results of such studies, including recommendations for any supplemental work deemed advisable, were to be presented in a report submitted to the Regional Oil Spill Engineer.

1.2.3 Of concern to both the office of the Regional Oil Spill Engineer and Thomsen Associates during all phases of this investigation was the potential for vertical contaminant migration, via the exploratory boreholes, within the local aquifer. To minimize the possibility of such cross contamination, the scope of services provided by Empire Soils Investigations, Inc./Thomsen Associates included the formulation and use of specialized, site-specific drilling procedures as described in Section 2, Investigative Methodology.

1.2.4 As specifically directed by the Regional Oil Spill Engineer, use of construction details, water level data and chemical analysis results for local water supply wells, and access to these wells, was to be of limited extent in this phase of study. An additional NYSDOT-mandated limitation in this investigation included restriction of exploratory work to the uppermost zones of the local aquifer and bedrock.

1.3 PREVIOUS WORK

1.3.1 Initial hydrogeologic evaluations at this site were performed by Thomsen Associates in January 1983 and included limited assessment of the character of local unconsolidated deposits by means of shallow test borings and monitoring wells. Results of this study were furnished to the Regional Oil Spill Engineer in a preliminary report dated January 20, 1983 (Empire Soils Investigations, Inc. 1983a). Pursuant to directives from the Regional Oil Spill Engineer, no investigations of the local bedrock aquifer or contaminated water supply wells were performed at that time.

1.3.2 In March 1983, selected contaminated water supply wells in the project area, designated by the Regional Oil Spill Engineer, were investigated for presence of free hydrocarbon in the well bore itself by means of a water level probe inserted in the well. At that time, water levels were determined in these wells and were utilized to contour the water table. These findings were presented to the Regional Oil Spill Engineer in a report submitted March 10, 1983 (Empire Soils Investigations, Inc., 1983b).

1.3.3 Findings of these initial phases of work by Thomsen Associates are incorporated in, and superseded by, this report.

1.4 POTENTIAL HYDROCARBON SOURCES

1.4.1 Potential hydrocarbon sources considered in this investigation include an active Amoco service station; vehicle maintenance facilities at an active auto dealership; motor cleaning and repair facilities at Maxwell Engine Rebuilders; buried storage tanks at a florist shop, and buried fuel tanks at Heinchon Dairy. All of these potential contaminant sources are situated within the limits of the area studied, as shown on Drawing 3 of Appendix A.

1.4.2 Potential hydrocarbon contamination associated with vehicle traffic and parking areas was also considered in these evaluations.

1.5 SUPPLY WELL INVENTORY

1.5.1 In general, water supply wells in the study area are cased through unconsolidated materials and extend into bedrock to variable depths in excess of 100 feet (Schaff, 1982).

SECTION 2

INVESTIGATIVE METHODOLOGY

2.1 SUBSURFACE INVESTIGATIONS

- 2.1.1 As part of the initial site assessment (Empire Soils Investigations, Inc., 1983a), a total of nine boreholes, numbered 1 through 9, were advanced through unconsolidated deposits in the project area. Those boreholes encountering free groundwater, numbers 3 and 6, were converted to permanent groundwater monitors via the installation of PVC wellscreen and riser. For reference purposes the Subsurface Logs for these test holes are included in Appendix B. Note that due to the limited scope of investigation at that time, most boreholes were terminated upon encountering auger "refusal". In the absence of diamond core drilling, such refusal is interpreted as indicating the presence of boulders or bedrock.
- 2.1.2 Ongoing studies detailed in this report consisted of the placement of seventeen additional monitoring wells in the project area in the period April 27 through May 12, 1983. These new installations were numbered B-8 and B-10 through B-19 inclusive; borehole B-8 was made at the same location as test boring number 8 of January 1983 and retains that designation. Monitors B-8, B-10, B-11, B-14, B-16 and B-18 consist of multiple installations (monitor clusters) constructed to facilitate discrete groundwater sampling at various depths within the aquifer, as well as assessment of hydraulic relationships between overburden and bedrock. In these multiple installations the designation "R" is used to indicate the monitor screened in rock.

- 2.1.3 Each monitoring well is constructed of flush-threaded, machine slotted nominal two inch diameter PVC wellscreen and riser, with teflon tape used in all joints. The screened interval of monitors placed in unconsolidated (overburden) material extends above the water table, permitting entry into the well casing of any free hydrocarbon which may be floating upon the water table. Monitoring wells extending into bedrock are screened at various intervals which reflect the character of the bedrock at each specific well location. Construction details of specific monitors are indicated on the appropriate Subsurface and Hydrogeologic Logs in Appendix B.
- 2.1.4 Due to mechanical and size restrictions inherent in the drilling procedures used, monitor clusters were constructed in separate boreholes situated in close proximity to one another to facilitate sampling of discrete depth intervals at one location within the aquifer. This methodology was also selected over the alternative procedure of multiple-well installations in a single borehole to minimize the potential for cross-contamination. At locations where monitor clusters were installed the deeper bedrock monitor was completed first. To install the bedrock monitor, a pilot hole was drilled through overburden using hydraulically advanced hollow stem auger casing. When the apparent surface of "sound" bedrock was reached the augers were withdrawn and flush threaded pipe casing was spun into the pilot hole and seated approximately 3 to 6 inches into hard rock. Bedrock was core drilled within the casing and the monitoring well subsequently installed. A bentonite seal was placed within the casing at the soil-rock interface and the pipe casing was then withdrawn. With subsurface conditions at each well location thus defined, overburden monitors were installed to appropriate depths immediately adjacent to the deep wells.

- 2.1.5 As indicated on the test boring logs, split barrel samples (American Society for Testing and Materials, 1983a) were obtained in overburden in selected test borings to define the local soil profile. Diamond core drilling (American Society for Testing and Materials, 1983b) was performed in the upper portions of the bedrock horizon at various locations in the project area to obtain data on rock type, structure and character.
- 2.1.6 All recovered soil and rock samples were described by the on-site geologist and field foreman during operations. Following completion of field study, samples were forwarded to laboratory facilities where they were visually examined and described in greater detail by an engineering geologist, and final Subsurface and Hydrogeologic Logs (Appendix B) were prepared. Overburden samples were classified in general accordance with the Unified Soil Classification System (see Appendix B, "Key to Hydrogeologic Logs"). Rock core was also logged in detail in the laboratory (American Institute of Professional Geologists, 1977).
- 2.1.7 Grain size analyses were performed on representative split barrel samples to confirm the visual classifications and provide data on the grain size distribution of the overburden deposits. Results of these analyses are included as Appendix D.
- 2.2 HYDROGEOLOGIC DATA
- 2.2.1 On May 10, 1983, field permeability or "slug" tests (Bouwer and Rice, 1976) were performed in monitoring wells screened in overburden (B-3, B-10, B-16 and B-18); these tests included both rising head and falling head tests. On that same date, constant head tests (United States Department of the Interior, 1977) were performed in bedrock monitors B-8R

and B-12R, which reflect the extremes in rock quality noted in the boreholes. Results of these tests are discussed further in Section 3, Findings of Investigations.

- 2.2.2 Water levels in the monitoring wells and selected supply wells at the site were determined by Thomsen Associates personnel on various dates through the use of an electric well probe. Concurrently, the monitoring wells were investigated for the possible presence of free product by means of a transparent surface sampler. Water level data is summarized in tabular form in Appendix C.

2.3 GEOCHEMICAL DATA

- 2.3.1 On June 22-24, 1983, groundwater samples and water levels were obtained from monitoring wells in the project area by Camo Laboratories, Poughkeepsie, New York. In addition to samples of standing ("stagnant") water from the wells, these samples included "regenerated" water samples obtained following evacuation of five volumes of water from the wells. All samples were analyzed by Camo Laboratories for NYSDOT 602 aromatic hydrocarbons, and results of these analyses are presented in Appendix E. This appendix contains pertinent portions of a detailed analytical report prepared by Camo Laboratories for the ROSE and furnished to Thomsen Associates by the NYSDOT Oil Spill Engineer.

SECTION 3

FINDINGS OF INVESTIGATIONS

3.1 SITE LOCATION

3.1.1 The project area is located in southeastern Dutchess County, New York, approximately 19 miles southeast of the city of Poughkeepsie, New York and 18 miles northwest of Danbury, Connecticut. The site is found on the Pawling, New York/Connecticut USGS 7.5 minute topographic quadrangle, as indicated on Drawing No. 1, Site Location Map, in Appendix A.

3.1.2 This site is situated in the valley of the East Branch of the Croton River, which flows south through Putnam and Westchester Counties to a confluence with the Hudson River. Elevations on the valley floor in the area range from approximately 430 to 450 feet above mean sea level; uplands marginal to the valley form scarps rising rapidly to elevations of 850 feet or more above mean sea level.

3.2 GENERAL LOCAL GEOLOGY

3.2.1 The site lies within the Hudson Hills physiographic province of New York State, an area characterized by igneous and metamorphic bedrock, drainage controlled by the Hudson River, and narrow steep-walled valleys (Thompson, 1966). These valleys generally reflect local bedrock structures, being developed along zones of bedrock faults and folds which trend regionally to the northeast (New York State Museum and Science Services, 1962). Valley floors are relatively level, underlain by limestone and filled with glacial drift, while uplands consist of resistant crystalline rocks (Simmons, et.al., 1961).

- 3.2.2 Unconsolidated deposits in the project area consist of a horizon of stratified glacial outwash classified by the United States Department of Agriculture (1955) as members of the Merrimac soil series. These soils are predominantly interbedded sands and gravels, deep to bedrock, and are considered generically "very rapidly permeable". Glacial outwash deposits comprise the most productive unconsolidated aquifer in Dutchess County (Simmons, et.al., 1961).
- 3.2.3 Local bedrock consists of units of the Orodovician-age Stockbridge Formation (New York State Museum and Science Service, 1970). In northwestern Dutchess County these units are essentially undisturbed dolomitic limestone (magnesium-calcium carbonate). Southeastward across the county, however, the deformation and metamorphism of these units, related to the Taconic Orogeny, intensifies to the extent that the limestones have been totally metamorphosed and recrystallized to dolomitic marbles. Impure, friable (crumbly) sandy interbeds are commonly noted within the limestone and marble. The Stockbridge Formation is the major bedrock aquifer in Dutchess County and ranges from approximately 1000 to 3000 feet in thickness in the county (Simmons, et.al., 1961).
- 3.2.4 The East Branch of the Croton River occupies a topographic feature, referred to as the Harlem Valley, which is actually the surface expression of underlying bedrock structure. Based upon detailed fieldwork, Balk (1936) concluded that the Harlem Valley represents an anticline (upfold), the limbs of which are defined by scarps of crystalline rock and the core of which is composed of marble. Differential weathering, i.e., more rapid weathering and erosion of the weaker carbonate bedrock in the center of the anticline, accounts in large part for the topography presently observed.

3.2.5 Locally, bedrock structure is extremely complex; both normal and thrust faults are common as are overturned folds and belts or zones of "plastic deformation" (Balk, 1936). As a result of this deformation, the orientation of features critical to groundwater flow through bedrock, such as bedding planes and fractures ("secondary permeability") varies significantly over short distances.

3.2.6 The variation in orientation of secondary permeability features is further complicated by incipient karst (sinkhole) topography developed in the readily-weathered marble (Simmons, et.al., 1961). Through time, groundwater flow through secondary channels has resulted in solution, erosion and enlargement of these features into interconnected, open or sand-filled cavities and conduits within the rock. In addition to such solution activity along planar features, differential weathering of poorly-cemented and/or relatively more permeable strata within the rock mass is also extensive, as is apparent from inspection of outcrops in the vicinity of the project area.

3.3 SITE SPECIFIC GEOLOGY

3.3.1 As shown on Drawing 2, Vicinity Map, the site occupies a stretch of terrain along New York State Route 22, which in the project area is itself situated on a ridge rising slowly to the north. Ground slopes moderately to the southwest and southeast from the central portion of the site toward Brady Brook, a tributary of the East Branch of the Croton River. Overall topographic relief in the study area is on the order of twenty-five feet.

- 3.3.2 As indicated on the test boring logs (Appendix B) the boreholes completed for this investigation penetrated surficial fill materials underlain by granular glacial outwash consisting of loose to firm, interbedded sands and gravels. Results of grain size analyses performed on representative samples recovered from various locations and depths within this horizon (Appendix D) indicate these sediments to be largely fine to coarse sand with variable percentages of gravel and generally twenty percent or less of "fine" material (silt and clay).
- 3.3.3 Compact glacial till was noted beneath the outwash horizon in several test borings. However, this till layer is thin and discontinuous, and in most areas of the site the granular outwash deposits were seen to directly overlie bedrock.
- 3.3.4 In several test borings (B-11, B-13, B-16 and B-17), subsurface conditions and the limited sampling program undertaken made delineation of the bedrock surface in those areas difficult. Immediately overlying hard bedrock in these boreholes is a zone which may represent glacial till, "nested" boulders in outwash, severely to completely weathered bedrock (saprolite) or, in some instances, solution breccia related to collapse of cavities in bedrock. Although generally three to four feet in thickness, this zone appears to be in excess of ten feet thick in some portions of the site (B-16 and B-17) and, in these areas, is believed to represent saprolite or collapsed rock (see section 3.3.6).

3.3.5 Bedrock underlies the project area at depths ranging from fifteen to thirty feet in the boreholes and consists of gray to white dolomitic marble. This marble is extensively jointed (fractured), and slickensided (polished and striated) fracture surfaces attest to folding and faulting of the rock. Voids, soil-filled seams and weak, friable zones of variable extent were commonly encountered during diamond core drilling operations and are detailed on the Hydrogeologic Logs. Also shown on the test boring logs are the core recovery ratios and RQD (Rock Quality Designation) in each borehole. These figures range from 90 percent or better in boreholes B-8, B-10, and B-13 in which they are indicative of excellent quality, relatively sound rock (American Institute of Professional Geologists, 1977) to 50 percent or less in test holes B-12 and B-18, values characteristic of poor quality rock. This range in RQD values illustrates the wide variation in bedrock quality over the area. The detailed descriptions on the Hydrogeologic Logs also reflect the vertical irregularities common in the bedrock which result from selective weathering, with hard, sound zones found interbedded with extremely weathered strata.

3.3.6 Comparison of site plans (Drawings 1, 2 and 3) with the results of the rock coring performed for this study suggests correlation between bedrock quality and several topographic depressions in the project area, aligned immediately east of Route 22. Several of the boreholes which reflect complex or uncertain subsurface conditions and poor bedrock quality (B-12, B-16, B-17 and B-18) are situated within, peripheral to, or along the alignment of these depressions, which are themselves believed to be areas of subsidence (sinkholes) over concealed bedrock structure or weak, poor-quality rock.

3.3.7 Based upon test boring data, an interpretation of the general configuration of the bedrock surface is presented as Drawing No. 4 in Appendix A. The contours inferred for the concealed bedrock surface indicate a bedrock "high" immediately south of the Amoco station, with the rock surface sloping moderately to the northeast, south and southwest. The inferred presence of concealed bedrock structure(s) near borehole B-17 is illustrated on Drawing 4 by the depression contour around that point.

3.4 LOCAL HYDROGEOLOGIC REGIME

3.4.1 Water level observations in the monitors indicate the water table in the project area to be situated in close proximity to the bedrock surface. Due to seasonal fluctuations the water table itself, periodically, may be within bedrock in some areas of the site. Water level data from the cluster monitors indicates a general vertical downward flow component between the overburden and bedrock, providing a mechanism for migration of contaminants through the relatively permeable unconsolidated deposits and into the underlying bedrock aquifer. This mechanism operates independently of, but may be enhanced by, downward flow induced locally by drawdown in water supply wells.

3.4.2 Water level readings in the monitoring wells for May 19, 1983, were used to contour the water table over the site as illustrated on Drawing 5 of Appendix A. These readings indicate the major component of groundwater flow beneath the site to be southward, discharging to Brady Brook south of the site, with minor southwestward and southeastward flow components also apparent. This flow regime is indicated by the large and small arrows, respectively, on Drawing 5. Although not plotted, water level data obtained on other dates from the monitoring wells indicate similar groundwater flow conditions in the project area.

- 3.4.3 Results of slug tests performed in monitors screened in overburden indicate the horizontal permeability of the glacial outwash deposits to vary between 1×10^{-2} cm/sec to 8×10^{-5} cm/sec. The range of results may be attributed to the stratified nature of the sediments, with horizontal permeabilities being greater in coarser strata and layers lower in content of "fines" (minus 200 sieve material). Utilization of effective grain size (d_{10}), as determined by laboratory tests on representative split barrel samples (Appendix D), to estimate overall permeability of the overburden deposits (Rose and Smith, 1957) yields values of approximately 5×10^{-2} cm/sec.
- 3.4.4 Constant head tests were performed in monitoring wells constructed in bedrock and selected as representing extremes in rock quality in the boreholes in the project area. Tests in sound rock (B-8R) yield results of 2×10^{-3} cm/sec, while tests conducted in poor quality, "seamy" bedrock (B-12R) indicate a greater permeability, on the order of 1×10^{-2} cm/sec.
- 3.4.5 Moderate horizontal groundwater gradients are noted in the area, ranging from 0.01 between monitors B-14 and B-12 on May 19, 1983, to 0.02 between wells B-14 and B-8 on that date. Utilizing the permeability (k) value of 1×10^{-2} cm/sec obtained from field tests, and assuming an average horizontal gradient of 0.015 and an effective porosity of 25 percent in the overburden deposits, horizontal groundwater flow velocity in the project area is estimated to be of the order of magnitude of 1.5 feet per day, or in excess of 500 feet per year.

3.4.6 Water levels noted in the monitoring wells through the course of this study indicate depth to the water table over the site to vary seasonally by several feet or more. In that portion of the site in the vicinity of boreholes B-10, B-15 and B-18, these fluctuations result in the seasonal high water table being within the unconsolidated deposits and low water tables in the underlying bedrock. Vertical transport of contaminants through the soil profile with the fluctuating water table results in a zone of variable thickness of residually contaminated soil; infiltration through this zone may leach contaminants from the soil, with resultant increase in severity and/or persistence of groundwater contamination. This situation may be noted for some time following removal of actual source(s) of contamination.

3.4.7 It should be pointed out that groundwater flow is intergranular, occurring through pore spaces in unconsolidated materials. Groundwater flow through bedrock, however, is facilitated predominantly by secondary permeability features as discussed above. Selective or preferential contaminant migration along certain fractures or fracture sets commonly occurs in bedrock.

3.5 HYDROCARBON CONTAMINATION

3.5.1 Results of chemical analyses performed on groundwater samples obtained on June 22 - 24, 1983, from the monitoring wells in the project area are included with this report as Appendix E. Note that samples from the surface of the standing water column as well as of "regenerated" groundwater were collected from those monitors containing water; all samples obtained were analyzed for concentrations of selected aromatic hydrocarbons.

2.21

- 3.5.2 The chemical analysis results indicate hydrocarbon contamination of groundwater in monitors B-3, B-11R and B-16R, where the presence of gasoline is indicated, as well as in monitor B-18R, where gasoline was not confirmed. Lesser concentrations of hydrocarbon compounds are also apparent in analyses of regenerated water from monitors B-17 and B-6, while remaining samples contained less than one part per billion of each of the parameters analyzed.
- 3.5.3 A plot of total aromatic hydrocarbon concentrations in regenerated water samples is presented as Drawing 6 in Appendix A. As indicated on Drawing 6 and by the geochemistry of water samples from monitoring wells B-3, B-11R, B-16R and B-18R, a contaminant plume extends downgradient from the Amoco station and encompasses the Surplus Store water supply well. Analyses of groundwater samples from monitor cluster B-14, upgradient of the Amoco station, indicate no contamination of groundwater by hydrocarbons at that point.
- 3.5.4 Data pertaining to hydrocarbon contamination in monitor B-17, due to location of this monitor downgradient of both the Amoco station and Maxwell Engine Rebuilders, is presently inconclusive and therefore open to alternative interpretations. This contamination may represent either the periphery of the contaminant plume emanating from the Amoco station, or hydrocarbon contamination originating from Maxwell Engine Rebuilders.
- 3.5.5 No measurable free product has been observed in the monitors or supply wells investigated in the project area during the time frame of this study. However, a distinct hydrocarbon odor and film in auger cuttings and wash water were observed during the drilling of monitor B-15 immediately south (down-gradient) of buried storage tanks at the Amoco station. Due to fluctuation of the water table (3.4.6), this monitor was dry at the time of chemical sampling in June 1983.

3.5.6 Geochemical data, in conjunction with site hydrogeology, indicate the major source of hydrocarbon contamination of the subsurface in the project area to be the active Amoco station on Route 22.

3.5.7 The presence of "windows" (deep, active supply wells) in the local aquifer, within and immediately downgradient of the source area and contaminant plume, enhances the potential for vertical migration of contaminants within the aquifer due to pumping from these wells. This occurrence is documented by cluster monitor B-16, where geochemical data indicates the presence of volatile hydrocarbon compounds in deep monitor B-16R but not in the monitor screened across the water table, where such contamination would normally be found. This situation is interpreted as indicating vertical migration of contaminants within the aquifer resulting from pumping in the Supply Store water well.

3.6 REMEDIATION & REPLACEMENT WATER SUPPLIES

3.6.1 Efforts should be undertaken to ascertain and remove the actual sources of contaminant loss at the Amoco station, and to determine the nature of any such losses, such as isolated versus ongoing release from tanks, plumbing, pumps or other sources. Following cessation of any direct contaminant release, residual contamination (3.4.6) should be minimized through removal of contaminated soil and its replacement by clean material, with the source area capped with impermeable material as appropriate to reduce infiltration and leaching of residual contaminants into groundwater. Removal, replacement and encapsulation is recommended due to the restricted areas and volumes anticipated and the probability of persistent groundwater contamination if action is not taken to reduce or eliminate residual soil contamination.

- 3.6.2 Use of hydrocarbon-containing agents to clean equipment at Maxwell Engine Rebuilders should be restricted, or such cleansing should be performed only on decontamination pads allowing containment and recovery of any solvents used.
- 3.6.3 Surface runoff from the engine wash area at Maxwell Engine Rebuilders flows toward the wellhouse at Mario's Pizza, with resultant potential for direct hydrocarbon contamination of that supply well. Measures in addition to 3.6.2 above to reduce this potential are recommended.
- 3.6.4 Under present conditions, new large-capacity water supply wells in the area, such as that for Burger King immediately north of the Amoco station, may alter groundwater and contaminant flow directions and rates or otherwise effect the local groundwater flow regime. Cluster monitor B-14 does not extend to depths in the aquifer suitable for detection of possible contaminant migration toward the Burger King supply well.
- 3.6.5 Remedial actions should include, but not be limited to, measures outlined in 3.6.1 and 3.6.2. In addition, dilution and dispersion of hydrocarbon contamination in groundwater should occur in a relatively short time if contaminant input were to be restricted through procedures outlined above, and vertical migration of contaminants into the deep bedrock groundwater system was eliminated by temporary abandonment of the deep water supply wells affected by contamination.
- 3.6.6 It should be realized that an aquifer system such as that in the project area, with relatively permeable granular sediments unprotected at the surface and hydraulically connected to a bedrock aquifer of high permeability itself, is very susceptible to widespread lateral and vertical contamination

2.24

if reasonable precautions are not undertaken. "Normal" hydrocarbon contamination associated with vehicle traffice areas can, in time, cause problems with groundwater quality; water supply wells should ideally be located at some distance from, or upgradient of, vehicle traffic, parking and maintenance areas, or otherwise protected from contamination related to these potential sources.

2.25

SECTION 4

CONCLUSIONS AND RECOMMENDATIONS

4.1 CONCLUSIONS

- 4.1.1 The local aquifer is comprised of hydraulically connected unconsolidated granular deposits and carbonate bedrock.
- 4.1.2 Hydrocarbon contamination of groundwater in the project area has been documented, independently of the local supply well system, by this hydrogeologic study.
- 4.1.3 The major source of hydrocarbon contamination encountered in this study is indicated to be the Amoco station in the project area.
- 4.1.4 Pumping of deep water supply wells in the area enhances the potential for contamination of the aquifer over a wide depth interval.
- 4.1.5 Determination of the full vertical extent of hydrocarbon contamination of the aquifer in the project area is beyond the scope of the existing monitoring well network and this phase of study.
- 4.1.6 The lower contaminant concentrations noted in several supply wells and monitors may represent the margins of the contaminant plume or may be related to activities in the vicinity of these wells.
- 4.1.7 Initial indications are that the contaminant plume may disperse in a relatively short period if both contaminant input at its source(s) and residual contamination are eliminated.

4.2 RECOMMENDATIONS

- 4.2.1 Inspection of operations and facilities at the Amoco station should be undertaken and remedial measures completed as warranted to remove sources of contamination at that facility. Potential sources of residual contamination should also be remediated as discussed previously.
- 4.2.2 Ongoing assessment of groundwater quality in supply wells and monitors through same-day sampling at all data points is recommended to evaluate the rate of migration of the plume downgradient of the indicated source, and to investigate whether hydrocarbon contamination found at a distance downgradient of the indicated source is the result of contaminant plume migration or localized hydrocarbon contamination.
- 4.2.3 Remediation of local groundwater contamination and provision of replacement water supplies to affected parties must involve coordinated removal of contaminant sources and temporary abandonment of affected supply wells. As a minimum, the Surplus Store and Corral Ford supply wells should be temporarily abandoned to eliminate possible ongoing verticle migration of contaminants, resulting from use of these wells, into the deep bedrock aquifer.
- 4.2.4 A survey of supply wells in the project area should be considered mandatory in providing data critical to project resolution. Well depths, static water levels, pumping levels, pump/intake elevations and cased versus open hole intervals are among the data necessary for both the assessment of the nature and extent of local groundwater contamination and generation of design details for any required replacement supply wells.

- 4.2.5 Installation of replacement supply wells should be held in abeyance until additional data on site hydrogeology and existing wells is obtained. Data presently available in these regards is insufficient for consideration of new supply well locations and installation details.
- 4.2.6 Additional work to define the vertical extent of hydrocarbon contamination in the aquifer may be warranted to target suitable intake zones for replacement supply wells, and to provide data for design of such wells. This work may include conversion of existing deep supply wells to multiple-level sampling points and/or installation of purpose-built instrumentation for that purpose.
- 4.2.7 A deep groundwater monitor, of suitable design, should be installed between the Amoco station and Burger King. Routine assessment of groundwater quality utilizing this monitor would facilitate early detection of any contaminant migration which may occur toward the Burger King supply well.
- 4.2.8 The enclosure for the supply well for Marios Pizza should be shielded against direct entry of surface runoff from the surrounding parking area and the engine wash area at Maxwell Engine Rebuilders.
- 4.2.9 In addition to all monitors installed for this investigation, any abandoned water supply wells in which groundwater contamination is not observed to abate through time should be grouted upon project closure.

REFERENCES

- American Institute of Professional Geologists, 1977. Geologic Logging and Sampling of Rock Core for Engineering Purposes (Tentative Guide).
- American Society for Testing and Materials, 1983a. Penetration Test and Split-Barrel Sampling of Soils. Designation D-1586.
- American Society for Testing and Materials, 1983b. Diamond Core Drilling for Site Investigation. Designation D-2113.
- Balk, R., 1936. Structural and Petrologic Studies in Dutchess County, New York. Part I. Geologic Structure of Sedimentary Rocks. Bulletin of the Geological Society of America, v. 47, pp. 685-774.
- Bouwer, H. and Rice, R. C., 1976. A Slug Test for Determining Hydraulic Conductivity of Unconfined Aquifers with Completely or Partially Penetrating Wells. Water Resources Research, v. 12, no. 3, pp. 423-427.
- Empire Soils Investigations, Inc., 1983a. Preliminary Hydrogeologic Evaluations, Oil Spill, Village of Pawling, Dutchess County, New York. File No. GTA-82-17J.
- Empire Soils Investigations, Inc., 1983b. Interim Report, Oil Spill, Village of Pawling, Dutchess County, New York. File No. GTA-82-17J.
- New York State Museum and Science Service, 1962. The Geology of New York State. Map and Chart Series No. 5 (Text).
- New York State Museum and Science Service, 1970. Geologic Map of New York. Map and Chart Series No. 15 (Lower Hudson Sheet).
- Rose, H. Glen and Smith, H. F., 1957. A Method for Determining Permeability and Specific Capacity from Effective Grain Size. State of Illinois, Department of Registration and Education, State Water Survey Division. Circular No. 59.
- Schaff, J., Assistant Regional Oil Spill Engineer, New York State Department of Transportation Region 8, 1982. Personal Communication.
- Simmons, E. T.; Grossman, I. G. and Heath, R. C., 1961. Ground Water Resources of Dutchess County, New York. State of New York Department of Conservation, Water Resources Commission. Bulletin GW-43.

Thompson, J. H., 1966. Geography of New York State. Syracuse University Press.

United States Department of Agriculture, 1955. Soil Survey of Dutchess County, New York.

United States Department of the Interior, Bureau of Reclamation, 1977. Design of Small Dams.

United States Geological Survey, 1958. Pawling, New York/Connecticut 7.5 Minute Topographic Quadrangle. Photorevised 1971.


2.30

APPENDIX A


Drawings



SCALE 1:24000



CONTOUR INTERVAL 10 FEET
DATUM IS MEAN SEA LEVEL



DETAIL FROM:

PAWLING, N. Y. - CONN.
N4130-W7330/7.5

1958
PHOTOREVISED 1971
AMS 6267 II SE-SERIES 821

**THOMSEN
ASSOCIATES**


CONSULTING GEOTECHNICAL
ENGINEERS & GEOLOGISTS

Groton • Buffalo • Rochester • Syracuse • Albany
New York • Woodbridge • Harrisburg • Washington

OIL SPILL CONTAINMENT - PAWLING, N.Y.


SITE LOCATION MAP

DR BY:	SCALE as shown	PROJ NOGTA-82-17J
CK'D BY:	DATE 1-83	DRWG NO 1



BURGER KING

AMOCO
Pump Island



SURPLUS STORE
ENGINE AREA

MARIO'S PIZZA

VENEZIA
QUEST HOUSE

FLORIST

STAGE
DOOR
FURN.

CORRAL
FORD

GOLD HOUSE

Farm Drive

HEINCHON
DAIRY

LEGEND


- Soil Boring of January 1983 by Empire Soils
- ✦ Soil Boring & Permanent 2" Monitor by Empire Soils, January 1983
- 2" Monitor in Unconsolidated Deposits, by Empire Soils, April/May 1983
- 2" Monitor in Bedrock, by Empire Soils, April/May 1983
- ⊙ Monitor Cluster by Empire Soils, April/May 1983
- Water Supply Well Referenced in Text
 - 1. Surplus Store
 - 2. Corral Ford
 - 3. Mario's Pizza
 - 4. Heinrich Dairy
- * Spot Elevation
- / Total aromatic hydrocarbon isopleth (ppb) extrapolated from analyses of June 1983. Number adjacent to monitor number

Map based on field survey by Thomsen Associates.

"BM" Denotes Benchmark: Nail in Pole 6" Above Ground
Elevation Assumed 100.0'

THOMSEN ASSOCIATES		CONSULTING GEOTECHNICAL ENGINEERS & GEOLOGISTS	
Gorton • Buffalo • Rochester • Syracuse • Albany		New York • Woodbridge • Harrisburg • Washington	
OIL SPILL CONTAINMENT PAWLING, NEW YORK TOTAL AROMATIC HYDROCARBONS			
DATE 198	SCALE 1" = 100'	PROJECT	GTA-82-17J
DATE 6'83	DATE 6'83	DESIGN	6

237



LEGEND

- Soil Boring of January 1983 by Empire Soils
- ✦ Soil Boring & Permanent 2" Monitor by Empire Soils, January 1983
- 2" Monitor in Unconsolidated Deposits, by Empire Soils, April/May 1983
- 2" Monitor in Bedrock, by Empire Soils, April/May 1983
- ① Monitor Cluster by Empire Soils, April/May 1983
- Water Supply Well Referenced in Text
 1. Surplus Store
 2. Corral Ford
 3. Mario's Pizza
 4. Heinchon Dairy

✧ Spot Elevation

Water table contours, extrapolated from water level readings in monitors. Arrows indicate general direction of groundwater flow.

Map based on field survey by Thomson Associates.

"BM" Denotes Benchmark: Nail in Pole 6" Above Ground
Elevation Assumed 100.0'

Contour Interval 2 feet.





CONSULTING GEOTECHNICAL
ENGINEERS & GEOLOGISTS
Glen - Buffalo - Rochester - Syracuse - Albany
New York - Woodbridge - Harrisburg - Washington

**OIL SPILL CONTAINMENT
PAWLING, NEW YORK
WATER TABLE CONTOURS 19 MAY 1983**

DES BY	rga	SCALE	1" = 100'	PROJECT	GTA-82-17J
CHECKED		DATE	6/83	DESIGNED	5

237



LEGEND

- Soil Boring of January 1983 by Empire Soils
- ✦ Soil Boring & Permanent 2" Monitor by Empire Soils, January 1983
- 2" Monitor in Unconsolidated Deposits, by Empire Soils, April/May 1983
- 2" Monitor in Bedrock, by Empire Soils, April/May 1983
- ① Monitor Cluster by Empire Soils, April/May 1983
- Water Supply Well Referenced in Text
 1. Surplus Store
 2. Corral Ford
 3. Mario's Pizza
 4. Heinchon Dairy
- * Spot Elevation
- Bedrock Contour, dashed where inferred

Map based on field survey by Thomson Associates.

"BM" Denotes Benchmark: Nail in Pole 6" Above Ground
Elevation Assumed 100.0'


Bedrock contours based on information extrapolated from test boring logs.

THOMSEN ASSOCIATES CONSULTING GEOTECHNICAL ENGINEERS & GEOLOGISTS
Groton • Buffalo • Rochester • Syracuse • Albany • New York • Woodbridge • Harrisburg • Washington

OIL SPILL CONTAINMENT PAWLING, NEW YORK BEDROCK CONTOURS

DR BY	rgs	SCALE	1" = 100'	PROJ NO	GTA-82-17
CA'D BY		DATE	6/83	DRWG NO	4

1434



BURGER KING

B14 AMOCO

Pump Island

Buried Tanks

B 2

B 15

B 16

B 13

B 18

B 10

B 19

Engine Wash Area

SURPLUS STORE
ENGINE REPAIR

B 17

MARIO'S PIZZA

B 5

B 12

98.4

VENEZIA
GUEST HOUSE

111.6

FLORIST

109.5

STAGE
DOOR
FURN.

103.8

B 10

CORRAL
FORD

105.6

B 8

B 11

Farm Drive

95.5

GOLD HOUSE

98.6

LEGEND

- Soil Boring of January 1983 by Empire Soils
- ✦ Soil Boring & Permanent 2" Monitor by Empire Soils, January 1983
- 2" Monitor in Unconsolidated Deposits, by Empire Soils, April/May 1983
- 2" Monitor in Bedrock, by Empire Soils, April/May 1983
- ① Monitor Cluster by Empire Soils, April/May 1983
- Water Supply Well Referenced in Text
 1. Surplus Store
 2. Corral Ford
 3. Mario's Pizza
 4. Heinchon Dairy
- ✦ Spot Elevation

Map based on field survey by Thomson Associates.

"BM" Denotes Benchmark: Nail in Pole 6" Above Ground
Elevation Assumed 100.0'

**THOMSEN
ASSOCIATES**

CONSULTING GEOTECHNICAL
ENGINEERS & GEOLOGISTS


Graton • Buffalo • Rochester • Syracuse • Albany
New York • Woodbridge • Harrisburg • Washington

**OIL SPILL CONTAINMENT
PAWLING, NEW YORK
SITE PLAN**

HEINCHON
DAIRY

B 6

2.36



- 1 Corral Ford
- 2 Surplus Store
- 3 Marios Pizza
- 4 Venezia Guest House
- 5 Amoco
- 6 Heinchon Dairy
- 7 Gold House
- 8 Stage Door Furniture
- 9 Burger King

Base map provided by NYSDOT Oil Spill Engineer.

THOMSEN
ASSOCIATES

CONSULTING GEOTECHNICAL
ENGINEERS & GEOLOGISTS

Groton • Buffalo • Rochester • Syracuse • Albany
New York • Woodbridge • Harrisburg • Washington

OIL SPILL CONTAINMENT PAWLING, NEW YORK VICINITY MAP

DATE	1/88	SCALE	1" = 200'	PROJECT	NY GTA-82-17J
DATE	8/83	DATE	8/83	DRAWING NO.	2

236

2.37

APPENDIX B

Subsurface & Hydrogeologic Logs

DEPTH	ELEVATION	SAMPLES	SAMPLE NO.	CHEM. SMPL. RECOVERY (Inches)	N	SOIL or ROCK CLASSIFICATION	UNITED SOIL CLASSIF.	DENSITY (pcf)	WATER CONTENT (Percent)	PERMEABILITY (cm/sec)	MONITOR PIEZOMETER CONSTRUCTION DETAILS			WATER PROBE READINGS				NOTES
											B-BR	B-S		Temp. (°C)	Cond. (µmho/cm)	Eh (mV)	pH	
0	93.3					SURFICIAL FILL 0.0'												
5						Stratified brown fine to coarse SAND and fine to coarse GRAVEL, trace to little silt, cobbles	SM, GM											Core drilled 26.2'-36.2'. Recovery 9.4' (94%) NX double tube, 10' barrel. Tricone roller bit to 36.2'. Left 0.5' core stump in hole.
10						Grading wet at 12'												Water level at completion of B-BR 8.2' below grade.
15																		Monitor B-BR: Bottom of 2" PVC well at 36.2'. Screen 36.2'-26.2' (0.010" slot). Bentonite 26.2'-25.5'. Native backfill 25.5' to surface. Curb box at surface.
20																		Monitor B-S: Bottom of 2" PVC well at 15.0'. Screen 15.0'-10.0' (0.020" slot). Native backfill 15.0' to surface. Curb box at surface.
25	67.8																	
30						Light gray, medium grained, dolomitic MARBLE. Thick bedded, very slightly weathered, hard, with pronounced banding. Solution zone 26.8'-26.9': tight, parallel, stained, slicken-sided(?) 45° fractures @ 1/2" spacing, with secondary carbonate film.				$k = 2 \times 10^{-3}$ cm/sec								
35	57.1		1	94	94													
40						BORING TERMINATED @ 36.2'												

238

NOTE: See reverse side for key and explanation to log.		RUN NO.	RECOVERY (Percent)	ROD	Surface Elevation <u>93.3</u>		Project No. <u>GTA-82-17J</u>		<div style="text-align: center;"> THOMSEN ASSOCIATES </div>		<div style="text-align: center;"> HYDROGEOLOGIC LOG </div>	
					Date Started <u>4-29-83</u>		Project Title <u>Oil Spill Containment</u>					
					Date Completed <u>5-2-83</u>		Location <u>Pawling, New York</u>					
					Number of Installations in Boring <u>2</u>		Classified By <u>rga</u> Checked <u></u>					
					Method of Installation <u>Hollow Stem Augers and Flush Joint Casing</u>						MONITOR NO. <u>B-8</u> Sheet <u>1</u> of <u>1</u>	

DEPTH	ELEVATION	SAMPLES	SAMPLE NO.	CHEM. ANAL.	RECOVERY (inches)	N	SOIL or ROCK CLASSIFICATION	UNIFIED SOIL CLASSIF.	DENSITY (PCF)	WATER CONTENT (Percent)	PERMEABILITY (cm/sec)	MONITOR/PIEZOMETER CONSTRUCTION DETAILS		WATER PROBE READINGS				NOTES
												B-10R	B-10S	Temp. (°C)	Cond. (µmho/cm)	Eh (mV)	pH	
0	101.1						SURFICIAL FILL 0.0'											
1			1			16	Stratified brown fine to coarse SAND and fine to coarse GRAVEL, trace to little silt, cobbles	SM,GM										
2			2			14												
3			3			10												
4			4			18												
5			5			21												
6			6			9												
7			7			5	Grading wet at 14'											
8			8			16												
9			9			26												
10			10			31												
25	76.6						Light gray to white, medium grained dolomitic MARBLE. Thin to medium bedded, moderately weathered, with numerous tight & open 40°-50° stained fractures and irregular solution cavities. Fractures exhibit secondary, slickensided(?) carbonate films. 28'±											
30	73.1						Gray dolomitic MARBLE. Thick bedded, slightly weathered, with several tight slickensided 50° fractures. Fractures stained & discoloration extends into rock up to several inches. 35.0'											
35	66.1		1	98	98		BORING TERMINATED @ 35.0'											
NOTE: See reverse side for key and explanation to log.		RUN NO.	RECOVERY (Percent)	RQD	Surface Elevation <u>101.1</u> Date Started <u>5-5-83</u> Date Completed <u>5-9-83</u> Number of Installations in Boring <u>2</u> Method of Installation <u>Hollow Stem Augers and Flush Joint Casing</u>			Project No. <u>GTA-82-17J</u> Project Title <u>Oil Spill Containment</u> Location <u>Pawling, New York</u> Classified By <u>rga</u> Checked <u></u>				HYDROGEOLOGIC LOG THOMSEN ASSOCIATES MONITOR NO. <u>B-10</u> Sheet <u>1</u> of <u>1</u>						

239

DEPTH	ELEVATION	SAMPLE NO.	CHEM. SMPL. RECOVERY (Percent)	N	SOIL or ROCK CLASSIFICATION	UNIFIED SOIL CLASSIF.	DENSITY (pcf)	WATER CONTENT (Percent)	PERMEABILITY (cm/sec)	MONITOR/PIEZOMETER CONSTRUCTION DETAILS			WATER PROBE READINGS				NOTES
										B-11R	B-11S		Temp. (°C)	Cond. (µmho/cm)	Eh (mV)	pH	
0	97.3				SURFICIAL FILL 0.0'												
5					Brown SAND & GRAVEL, Some Silt, cobbles, boulders												Core drilled 21.7'-31.7'. Run 1: 21.7'-26.7' Recovery 4.7' (94%) Run 2: 26.7'-31.7' Recovery 4.8' (96%) NX double tube, 10' barrel. Water level at completion of B-11R 12.5' below grade. Monitor B-11R: Bottom of 2" PVC well at 31.7'. Screen 31.7'-21.7' (0.010" slot). Bentonite 21.7'-21.2'. Native backfill 21.2' to surface. Curb box at surface. Monitor B-11S: Bottom of 2" PVC well at 14.0'. Screen 14.0'-4.0' (0.020" slot). Native backfill 14.0' to surface. Curb box at surface.
10																	
15					Wet @ 13'												
20	79.3				18'±												
25	75.6				21.7'												
30		1	94	83	Light brown to white, medium grained dolomitic MARBLE. Thin to medium bedded, very slightly weathered, hard. Fractures generally horizontal, tight and fresh or very slightly stained. 0.3' void or seam at 23'±.												
35	65.6	2	96	78	31.7'												
					BORING TERMINATED @ 31.7'												

240

NOTE:
See reverse side for key and explanation to log.

Surface Elevation 97.3
 Date Started 4-27 and 5-10-83
 Date Completed 4-27 and 5-10-83
 Number of Installations in Boring 2
 Method of Installation Hollow Stem Augers and Flush Joint Casing

Project No. GTA-82-173
 Project Title Oil Spill Containment
 Location Pawling, New York
 Classified By rga Checked

HYDROGEOLOGIC LOG

THOMSEN ASSOCIATES

MONITOR NO. **B-11**
 Sheet 1 of 1

DEPTH	ELEVATION	SAMPLES	SAMPLE NO.	CHEM. ANAL.	RECOVERY (inches)	N	SOIL or ROCK CLASSIFICATION	UNIFIED SOIL CLASSIF.	DENSITY (pcf)	WATER CONTENT (Percent)	PERMEABILITY (cm/sec)	MONITOR/PIEZOMETER CONSTRUCTION DETAILS				WATER PROBE READINGS				NOTES	
												B-12R				Temp. (°C)	Cond. (µmhos/cm)	EH (mV)	pH		
0	101.1						SURFICIAL FILL 0.0'														
5							Stratified brown fine to coarse GRAVEL & SAND, little to some silt, cobbles														
15	85.2																				
20	81.7						Gray, banded dolomitic MARBLE. Thick bedded, very slightly weathered, hard. 15.9'														
25	74.5				58	41	Gray to white dolomitic MARBLE, interbedded with harder banded marble. Moderately to severely weathered, with numerous stained fractures. Voids or seams: 19.4'-19.6'; 19.7'-19.9'; 21.8'-22.0'; 23.6'-24.3'; 24.4'-24.9'. Loosely cemented and friable below 23'. 26.6'				$k = 1 \times 10^{-2}$ cm/sec										
30							BORING TERMINATED @ 26.6'														
35																					

NOTE:
See reverse side for key and explanation to log.

Surface Elevation 101.1
Date Started 5-3-83
Date Completed 5-3-83
Number of Installations in Boring 1
Method of Installation Hollow Stem Augers
and Flush Joint Casing

Project No. GTA-82-173
Project Title Oil Spill Containment
Location Fawling, New York
Classified By XGA Checked

HYDROGEOLOGIC LOG

THOMSEN ASSOCIATES

MONITOR NO. B-12
Sheet 1 of 1

2.41

DEPTH	ELEVATION	SAMPLE NO.	CHEM. ANALY.	RECOVERY Inches	N	SOIL or ROCK CLASSIFICATION	UNIFIED SOIL CLASSIF.	DENSITY pcf	WATER CONTENT Percent	PERMEABILITY lcm/sec	MONITOR/PIEZOMETER CONSTRUCTION DETAILS				WATER PROBE READINGS				NOTES	
											B-13R				Temp. °C	Cond. µmhos/cm	Eh mV	pH		
0	104.4					SURFICIAL FILL 0.0'														
5						Stratified brown fine to coarse SAND and fine to medium GRAVEL, Some Silt														Core drilled 16.4'-26.4'. Recovery 9.9' (99%) NX double tube, 10' barrel. Monitor B-13R: Bottom of 2" PVC well at 26.4'. Screen 26.4'-16.4' (0.010" slot). Bentonite 16.4'-16.0'. Native backfill 16.0' to surface. Curb box at surface. No water in borehole prior to introduction of drilling water. Water level 10.5' at completion of hole 1030 hrs 5/3/83. Set 2" monitor and pumped well dry. Water level in well 12.5' 1430 hrs 5/3/83.
10	91.4					13'±														
15	88.4					Glacial till or weathered bedrock. 16.0'														
20	82.4					Gray, medium grained dolomitic MARBLE, thick bedded, very slightly weathered, with pronounced banding. Solution zone(?) 17.7'-17.8'. Grading at 20' to white, loosely cemented, moderately weathered, friable marble with vertical stained fractures. Severely weathered soft zone 21'-22' (±) 22.0'														
25	78.0	1	99	95		Gray banded MARBLE, very slightly weathered with occasional very gentle stained fractures. 26.4'														
30						BORING TERMINATED @ 26.4'														

NOTE:
See reverse side for key and explanation to log.

Surface Elevation 104.4
 Date Started 5-2-83
 Date Completed 5-3-83
 Number of Installations in Boring 1
 Method of Installation Hollow Stem Augers and Flush Joint Casing

Project No. GTA-82-17J
 Project Title Oil Spill Containment
 Location Pawling, New York
 Classified By rga Checked

HYDROGEOLOGIC LOG

THOMSEN ASSOCIATES

MONITOR NO. **B-13**
 Sheet 1 of 1

242

DEPTH	ELEVATION	SAMPLES	SAMPLE NO.	CHEM. SMP.	RECOVERY (inches)	N	SOIL or ROCK CLASSIFICATION	UNITED SOIL CLASSIF.	DENSITY (pcf)	WATER CONTENT (Percent)	PERMEABILITY (cm/sec)	CONSTRUCTION DETAILS		READINGS				NOTES
												B-14R	B-14S	Temp (°C)	Cond. (µmho/cm)	Eh (mV)	pH	
0	106.3						SURFICIAL FILL 0.0'											
5							Stratified brown fine to coarse SAND & fine to coarse GRAVEL, little to some Silt, cobbles											Core drilled 29.9'-39.9'. Recovery 6.7' (67%) NX double tube, 10' barrel.
10																		Monitor B-14R: Bottom of 2" PVC well at 35.5'. Screen 35.5'-30.5' (0.010" slot). Bentonite 30.5'-29.4'. Native backfill 29.4' to surface. Curb box at surface.
15							Grading wet at 15'											Monitor B-14S: Bottom of 2" PVC well at 25.0'. Screen 25.0'-10.0' (0.010" slot). Native backfill: 25.0' to surface. Curb box at surface.
20																		
25																		
30	76.9						White dolomitic MARBLE. Moderately to severely weathered and friable with stained fractures. Occasional gray, very slightly weathered, banded interbeds. Void or seam 30.3'-31.3'											
35	71.3						Gray dolomitic MARBLE. Thick bedded, very slightly weathered, with pronounced banding. Stained, soft solution zone 35.5'-35.7'											Lost drilling water at 34.6'.
40	66.4	1	67	56														
							BORING TERMINATED @ 39.9'											

2.43

NOTE:
See reverse side for key and explanation to log.

Surface Elevation 106.3
Date Started 5-11-83
Date Completed 5-11-83
Number of Installations in Boring 2
Method of Installation Hollow Stem Augers and Flush Joint Casing

Project No. GTA-82-177
Project Title Oil Spill Containment
Location Pawling, New York
Classified By rga Checked _____

HYDROGEOLOGIC LOG

THOMSEN ASSOCIATES

MONITOR NO. B-14
Sheet 1 of 1

DEPTH	ELEVATION	SAMPLE NO.	CHEM. SMPL.	RECOVERY (Inches)	N	SOIL or ROCK CLASSIFICATION	UNIFIED SOIL CLASSIF.	DENSITY (pcf)	WATER CONTENT (Percent)	PERMEABILITY (cm/sec)	CONSTRUCTION DETAILS				READINGS				NOTES	
											B-15S				Temp. (°C)	Cond. (µmho/cm)	En (mV)	pH		
0	105.0					0.0'														
						FILL: Brown SAND & GRAVEL with miscellaneous materials														Monitor B-15S: Bottom of 2" PVC well at 18.5'. Screen 18.5'-8.5' (0.010" slot). Native backfill to surface. Curb box at surface.
5	97.0	1			10	8'±														
		2			29	Stratified brown SAND & GRAVEL, little silt, cobbles														
-10		3			17	(Moist-Firm)														
		4			10															
-15		5			17	Grading wet at 14'														Hydrocarbon odor noted in samples 5 & 6.
	86.5	6			32	18.5'														
-20						BORING TERMINATED @ 18.5' Refusal - Possible bedrock or boulder														

244

NOTE:
See reverse side for key and explanation to log.

RUN NO.

RECOVERY (Percent)

ROD

Surface Elevation 105.0
Date Started 5-4-83
Date Completed 5-4-83
Number of Installations in Boring 1
Method of Installation Hollow Stem Augers and Flush Joint Casing

Project No. GTA-82-173
Project Title Oil Spill Containment
Location Pawling, New York
Classified By rga Checked

HYDROGEOLOGIC LOG

THOMSEN ASSOCIATES

MONITOR NO. B-15
Sheet 1 of 1

DEPTH	ELEVATION	SAMPLES	SAMPLE NO.	CHEM. SMPL	RECOVERY (Inches)	N	SOIL or ROCK CLASSIFICATION	UNIFIED SOIL CLASSIF.	DENSITY (pcf)	WATER CONTENT (Percent)	PERMEABILITY (cm/sec)	MONITOR/PIEZOMETER CONSTRUCTION DETAILS			WATER PROBE READINGS				NOTES
												B-16R	B-16S		Temp. (°C)	Cond. (µmhos/cm)	Sh (mV)	pH	
0	100.8						SURFICIAL FILL 0.0'												
5						13	Stratified brown fine to coarse SAND and fine to medium GRAVEL, trace to little silt, cobbles (Damp-Firm)	SM, GM											Core drilled 22.0'-32.0'. Recovery 8.2' (82%) NX double tube, 10' barrel.
10	91.1					18													Water level at completion of B-16R 9.7' below grade.
15						19	Grading wet at 10'												Monitor B-16R: Bottom of 2" PVC well at 32.0'. Screen 32.0'-27.0' (0.010" slot). Bentonite 24.5'-25.0'. Native backfill 25.0' to surface. Protective pipe at surface. PVC extends 2.2' above grade.
20						28	Severely to completely weathered bedrock and/or glacial till (?)				$k = 2 \times 10^{-4}$ cm/sec								Monitor B-16S: Bottom of 2" PVC well at 16.5'. Screen 16.5'-2.0' (0.010" slot). Protective pipe at surface. PVC extends 2.4' above grade.
25	80.3						Severely weathered, fragmented friable white MARBLE (Boulders?) Sand seam 21.4'-22.0'												At completion of core drilling borehole caved to 25'. Spur casing to 25.2', cleaned hole to 32' and installed B-16R.
30	75.8						Light gray dolomitic MARBLE. Thick bedded, hard, very slightly weathered and well banded. Several very gentle tight fractures and steep (45° and 60°), stained and weathered fractures.												
35	68.8					68													
							BORING TERMINATED @ 32.0'												

NOTE:
See reverse side for key and explanation to log.

Surface Elevation 100.8
Date Started 5-3-83
Date Completed 5-4-83
Number of Installations in Boring 2
Method of Installation Hollow Stem Augers
and Flush Joint Casing

Project No. GTA-82-173
Project Title Oil Spill Containment
Location Pawling, New York
Classified By Rga Checked _____

HYDROGEOLOGIC LOG

THOMSEN ASSOCIATES

MONITOR NO. B-16
Sheet 1 of 1

245

DEPTH	ELEVATION	SAMPLES	SAMPLE NO.	CHEM. SMPL. RECOVERY (Inches)	N	SOIL or ROCK CLASSIFICATION	UNIFIED SOIL CLASSIF.	DENSITY (pcf)	WATER CONTENT (Percent)	PERMEABILITY (cm/sec)	MONITOR PIEZOMETER CONSTRUCTION DETAILS				WATER PROBE READINGS				NOTES	
											B-17S				Temp. (°C)	Cond. (µmho/cm)	Eh (mV)	pH		
0	102.1					SURFICIAL FILL 0.0'														
5						Stratified brown fine to coarse SAND and fine to coarse GRAVEL, little to some silt, cobbles														
10																				
15	88.1					Nested boulders in overburden, or possible severely weathered, sandy bedrock. 14.9'														Monitor B-17S: Bottom of 2" PVC well at 19.6'. Screen 19.6'-14.6' (0.010" slot). Bentonite 14.6'-14.0'. Native backfill 14.0' to surface. Curb box at surface.
20																				Water level 14.9' in monitor at completion of installation.
25	79.1					BORING TERMINATED @ 23.0'														

NOTE:
See reverse side for key and explanation to log.

Surface Elevation 102.1
Date Started 5-11-83
Date Completed 5-12-83
Number of Installations in Boring 1
Method of Installation Hollow Stem Augers and Flush Joint Casing

Project No. GTA-82-17J
Project Title Oil Spill Containment
Location Pawling, New York
Classified By rga Checked _____

HYDROGEOLOGIC LOG

THOMSEN ASSOCIATES

MONITOR NO. **B-17**

Sheet 1 of 1

942

DEPTH	ELEVATION	SAMPLES	SAMPLE NO.	CHEM. SMPL	RECOVERY (inches)	N	SOIL or ROCK CLASSIFICATION	UNIFIED SOIL CLASSIF.	DENSITY (pcf)	WATER CONTENT (percent)	PERMEABILITY (cm/sec)	MONITOR/PIEZOMETER CONSTRUCTION DETAILS				WATER PROBE READINGS				NOTES	
												B-18R	B-18S			Temp. (°C)	Cond. (µmhos/cm)	Eh (mV)	pH		
0	100.3						SURFICIAL FILL 0.0'														
5							Stratified brown fine to coarse SAND and fine to coarse GRAVEL, little to Some Silt, cobbles														
10							Grading wet at 11'				$k = 7 \times 10^{-5}$ cm/sec										
15	83.9						Light gray, banded dolomitic MARBLE. Thick bedded, very slightly weathered, hard.														
20	80.3						White, friable, moderately to severely weathered and fractured dolomitic MARBLE. Voids or seams: 20.2'-21.9', 22.5'-22.7'.														
25	73.9		1	55	42																Core drilled 16.4'-26.4'. Recovery 5.5' (55%) NX double tube, 10' barrel. Monitor B-18R: Bottom of 2" PVC well at 21.1'. Screen 21.1'-17.1' (0.020" slot). Bentonite 16.5'-15.9'. Native beachfill 15.9' to surface. Protective pipe at surface. PVC extends 3.3' above grade. Monitor B-18S: Bottom of 2" PVC well at 14.5'. Screen 14.5'-4.5' (0.020" slot). Native backfill 14.5' to surface. Protective pipe at surface. PVC extends 3.2' above grade. Lost drilling water at 20.1'. At completion of core drilling, borehole caved to 20.4' and water level 11.0' below grade. Water level in monitor 11.0' at completion of installation. Pumped from well at 3gpm for 5 mins. with no drawdown.
30							BORING TERMINATED @ 26.4'														

NOTE:
See reverse side for key and explanation to log.

Surface Elevation 100.3
Date Started 5-5-83
Date Completed 5-5-83
Number of Installations in Boring 2
Method of Installation Hollow Stem Augers and Flush Joint Casing

Project No. GTA-82-17J
Project Title Oil Spill Containment
Location Pawling, New York
Classified By rga Checked _____

HYDROGEOLOGIC LOG

THOMSEN ASSOCIATES

MONITOR NO. **B-18**

Sheet 1 of 1

247

DEPTH	ELEVATION	SAMPLES	SAMPLE NO.	CHEM. ANAL.	RECOVERY (Inches)	N	SOIL or ROCK CLASSIFICATION	UNIFIED SOIL CLASSIF.	DENSITY (pcf)	WATER CONTENT (Percent)	PERMEABILITY (cm/sec)	MONITOR / PIEZOMETER CONSTRUCTION DETAILS				WATER PROBE READINGS				NOTES	
												B-19S				Temp. (°C)	Cond. (µmhos/cm)	Ek (mV)	pH		
0	100.8						0.0'														
5							Stratified brown fine to coarse SAND and fine to coarse GRAVEL, Some Silt, cobbles														
10																					
15							Grading wet at 15'														Monitor B-19S: Bottom of 2" PVC well at 19.0'. Screen 19.0'-9.0' (0.020" slot). Native backfill 19.0' to surface. Protective pipe at surface. PVC extends 2.7' above grade.
20	81.8						19.0'														Water level 9.5' in monitor at completion of installation.
25							BORING TERMINATED @ 19.0'														

NOTE:
See reverse side for key and explanation to log.

Project No. GTA-82-173
 Project Title Oil Spill Containment
 Location Pawling, New York
 Classified By rga Checked _____

HYDROGEOLOGIC LOG
THOMSEN ASSOCIATES
 MONITOR NO. B-19
 Sheet 1 of 1

Surface Elevation 100.8
 Date Started 5-9-83
 Date Completed 5-9-83
 Number of Installations in Boring 1
 Method of Installation Hollow Stem Augers and Flush Joint Casing

RUN NO. _____
 RECOVERY (Percent) _____
 ROD _____

249

DEPTH	ELEVATION	SAMPLES	SAMPLE NO	CHEM. SMP.	RECOVERY	N	SOIL or ROCK CLASSIFICATION	UNIFIED SOIL CLASSIF.	DENSITY (pcf)	WATER CONTENT (Percent)	PERMEABILITY (cm/sec)	MONITOR, PIEZOMETER, CONSTRUCTION DETAILS					WATER PROBE READINGS				NOTES	
																	Temp. (°C)	Cond. (µmho/cm)	Eh (mV)	pH		
1	2	3	4	5	6	7	8	9	10	11	12	13	14					15	16	17	18	19

The figures in the Column 1 defines the scale of the Subsurface Log.

The associated elevation is shown in the second column.

The third column graphically shows the exact depth range from which a soil sample or rock core was recovered.

See Table I for a description of the symbols used to signify the various types of samples.

The Sample or Run No. is used for identification on sample containers and/or Laboratory Test Reports.

The Chemical Sample column graphically shows the depth range from which a sample was recovered for chemical analysis.

The recovery column shows the recovery in inches for a soil sample. Rock core recovery is shown in percent.

N shows the number of blows required to drive a split spoon sampler into the soil. Unless otherwise stated, the results are for a "Standard Penetration Test", driving a two-inch diameter spoon 12 inches with a 140 pound hammer dropped 30 inches. RQD is the Rock Quality Designation for rock core. This equals the sum of the length of pieces greater than 4 inches divided by the length of the core run.

All recovered soil samples are reviewed in the laboratory. The visual descriptions are made on basis of the sample as recovered and in accordance with the Unified Classification System shown on Table VI. The Unified group symbol is shown in Column 9.

Guidelines for the terms used in descriptions are presented in Tables II and III. The description of the relative soil compactness or consistency is based upon the penetration records as defined in Table IV. The description of the soil moisture is based upon the condition of the sample as recovered. The moisture condition is described as dry, damp, moist or wet. Water used to advance the boring may have affected the in-situ moisture content of the sample. Special terms are used as required to describe materials in greater detail; several such terms are listed in Table V. When sampling gravely soils with a standard two-inch diameter split spoon, the true percentage of gravel is often not recovered due to the relatively small sampler diameter. The presence of boulders and large gravel is sometimes, but not necessarily, detected by evaluation of the casing and sampler blows or through the "action" of the drill rig as reported by the driller.

The results from nuclear field tests or laboratory tests for soil density and moisture are shown in Columns 11 and 12.

Soil or rock permeability, the testing method, and the depth range tested are shown in Column 12.

Column 13 is a graphic description of the monitor or piezometer installation. A Key to the description is presented on Table VII. Details of materials are noted in the NOTES column. The static water level (SWL) and date measured are noted in the adjacent column.

Columns 15 to 18 indicate the results of field tests at the depth tested. The date of the test is noted below the readings.

TABLE I

	Split Spoon Sample
	Shelby Tube Sample
	Auger or Pig Sample
	Rock Core

TABLE II

Identification of soil type is made on basis of an estimate of particle sizes, and in the case of fine grained soils also on basis of plasticity.	
Soil Type	Soil Particle Size
Boulder	>12"
Cobble	3"-12"
Gravel-Coarse	3"-3/4"
-Fine	24-810
Sand-Coarse	810-240
-Medium	240-8200
-Fine	
Silt-Non Plastic (Granular)	<200
Clay-Plastic (Cohesive)	<200
	Fine Grained

TABLE III

The following terms are used in classifying soils consisting of mixtures of two or more soil types. The estimate is based on weight of total sample.	
Term	Percent of Total Sample
and some	35-50
little	20-35
trace	10-20
	less than 10
(When sampling gravely soils with a standard split spoon, the true percentage of gravel is often not recovered due to the relatively small sampler diameter.)	

TABLE IV

The relative compactness or consistency is described in accordance with the following terms:			
Term	Granular Soils	Term	Cohesive Soils
	Blows per Foot, N		Blows per Foot, N
Loose	<10	Very Soft	<2
Firm	11-30	Soft	3-5
Compact	31-50	Medium	6-15
Very Compact	>51	Stiff	16-25
		Hard	>25
(Large particles in the soils will often significantly influence the blows per foot recorded during the Penetration Test.)			

TABLE V

Varved	Alternating layers, seams, and partings of soils.
Layer	Soil deposit more than 6" thick.
Seam	Soil deposit less than 6" thick.
Parting	Soil deposit less than 1/8" thick.
Uniform	All grains are of about the same diameter

TABLE VI

UNIFIED SOIL CLASSIFICATION			
Major Division	Group Symbol	Soil Description	
Coarse-grained (over 50% by weight coarser than No. 200 sieve)	GW	Well-graded gravels, sandy gravels.	Little or no fines.
	GP	Gap-graded or uniform gravel, sandy gravels.	Little or no fines.
	GM	Silty gravels, silty sandy gravels.	
	GC	Clayey gravels, clayey sandy gravels.	
Sandy soils (over half of coarse fraction finer than No. 4)	SW	Well-graded sand, gravelly sands.	Little or no fines.
	SP	Gap-graded or uniform sands, gravelly sands.	Little or no fines.
	SM	Silty sands, silty gravelly sands.	
	SC	Clayey sands, clayey gravelly sands.	
Fine-grained (over 50% by weight finer than No. 200 sieve)	ML	Silts, very fine sands, silty or clayey fine sands, rock flour.	
	CL	Low plasticity clays, sandy or silty clays.	
	OL	Low plasticity organic silts and clays.	
	OH	Micaceous or diatomaceous silts. Highly plastic clays and sandy clays. Organic silts and highly plastic clays.	
Organic Soils			

TABLE VII

	Curb Box
	Riser
	Well Screen
	Point Piezometer
	Sand Pack
	Bentonite Seal
	Concrete Seal
	Gravel Fill

244

DATE		HOLE NO. <u>2</u>
STARTED <u>1-3-83</u>		SURF ELEV <u>106.0</u>
FINISHED <u>1-3-83</u>		C. W DEPTH <u>None at</u>
SHEET <u>1</u> OF <u>1</u>		<u>completion.</u>

PROJECT	<u>Oil Spill Investigation</u>	LOCATION	<u>Route 22, Pawling, NY</u>
	Job No. GTA-82-17G		Dutchess County

DEPTH	SAMPLE NO.	BLOWS ON SAMPLER					BLOWS ON CASING	SOIL OR ROCK CLASSIFICATION	NOTES
		0-6	6-12	12-18	18-24	24-30			
0								TOPSOIL 0.1'	
								Brown fine SAND and fine to medium GRAVEL, little to some silt. (Moist-loose)	
5			4	4		8			
	1	4	6						
10								10.5'	
	2	25	50	12				Brown SILT with embedded ROCK FRAGMENTS and BOULDERS (glacial till). (Moist-very compact)	
15									
	3	6	33	47	80			17.0'	
20								Boring terminated @ 17.0'	
								Auger refusal - possible bedrock or boulder.	

No. of blows to drive 2 spoon 12 with 140 lb. pin wt. falling 30 "per blow CLASSIFICATION Visual by
 No. of blows to drive _____ casing _____ with _____ lb. weight falling _____ per blow geologist
 METHOD OF INVESTIGATION 3-1/4" I.D. hollow stem auger casing

DATE STARTED <u>1-4-83</u> FINISHED <u>1-4-83</u> SHEET _____ OF _____	EMPIRE SOILS INVESTIGATIONS INC.	SUBSURFACE LOG HOLE NO. <u>4</u> SURF ELEV <u>101.7</u> C. W. DEPTH <u>None at completion</u>
---	--	--

PROJECT <u>Oil Spill Investigation</u> Job No. <u>GTA-82-17J</u>	LOCATION <u>Route 22, Pawling, NY</u> <u>Dutchess County</u>
---	---

DEPTH	SAMPLE NO	BLOWS ON SAMPLER					BLOWS ON CASING	SOIL OR ROCK CLASSIFICATION	NOTES
		1	2	3	4	5			
0								Stratified brown fine to coarse SAND and fine to coarse GRAVEL; trace to some silt, cobbles. (Moist-loose to firm)	
5									
10								Brown SILT with embedded ROCK FRAGMENTS and BOULDERS (glacial till) (Moist-very compact) 18.5'	
15								Boring terminated @ 18.5'. Auger refusal - possible bedrock or boulder.	

No. of blows to drive 2 spoon 12 with 140 lb pin wt falling 30 per blow CLASSIFICATION Visual by
 No. of blows to drive _____ casing _____ with _____ lb weight falling _____ per blow geologist
 METHOD OF INVESTIGATION 3-1/4" I.D. hollow stem auger casing

2.54

DATE STARTED <u>1-4-82</u> FINISHED <u>1-4-82</u> SHEET <u>1</u> OF <u>1</u>	EMPIRE SOILS INVESTIGATIONS INC. 	SUBSURFACE LOG HOLE NO <u>5</u> SURF ELEV <u>100.9</u> C W DEPTH <u>None at completion</u>
---	---	---

PROJECT Oil Spill Investigation
 Job No. GTA-82-17J

LOCATION Route 22, Pawling, NY
Dutchess County

DEPTH	SAMPLE NO	BLOWS ON SAMPLER					BLOW ON CASING	SOIL OR ROCK CLASSIFICATION	NOTES
		0	6	12	18	24			
0								Stratified brown fine to coarse SAND and fine to coarse GRAVEL, cobbles, trace to little silt. (Moist-firm)	
5		5	3			12			
	1	9	11						
10		6	10			21		17.5'	
	2	11	14						
15		5	12			31			
	3	19	41						
								Boring terminated @ 17.5'. Auger refusal - possible bedrock or boulder.	
20									

N = No. blows to drive 2 spoon 12 with 140 lb pin wt falling 30 per blow CLASSIFICATION Visual by
 C = No. blows to drive _____ casing _____ with _____ lb weight falling _____ per blow geologist
 METHOD OF INVESTIGATION 3-1/4" I.D. hollow stem auger casing

DATE		SUBSURFACE LOG	HOLE NO	7	
STARTED			1-4-83	SURF ELEV	90.4
FINISHED			1-4-83	C. W. DEPTH	None at completion
SHEET			1	OF	1

PROJECT Oil Spill Investigation
Job No. GTA-82-17J

LOCATION Route 22, Pawling, NY
Dutchess County

DEPTH	SAMPLE NO	BLOW COUNT					BLOW COUNT	SOIL OR ROCK CLASSIFICATION	NOTES
		SAMPLER							
		0	6	12	18	24			
0								Stratified brown fine to coarse SAND and fine to coarse GRAVEL, cobbles, trace to little silt. (Moist-firm)	
5									
10								Similar; wet. 14.0'	
15								Boring terminated @ 14.0'. Auger refusal - possible bedrock or boulder.	

V = No blows to drive 2 spoon 12 with 140 lb pin wt falling 30 per blow

6. No blows to off-center _____ with _____ lb weight falling _____ per blow

ACKNOWLEDGMENTS

CLASSIFICATION Visual by
geologist

257

DATE STARTED <u>1-4-83</u> FINISHED <u>1-4-83</u> SHEET <u>1</u> OF <u>1</u>	EMPIRE SOILS INVESTIGATIONS INC.	SUBSURFACE LOG HOLE NO <u>8</u> SURF ELEV <u>93.4</u> C. W DEPTH <u>None at completion</u>
---	--	---

PROJECT Oil Spill Investigation
 Job No. GTA-82-17J

LOCATION Route 22, Pawling, NY
Dutchess County

DEPTH	SAMPLES	BLOWSON SAMPLER					BLOWSON CASING	SOIL OR ROCK CLASSIFICATION	NOTES
		0	6	12	18	24			
0								Brown fine to coarse SAND and fine to coarse GRAVEL, little to some silt, cobbles. (Moist-loose to firm)	
5		4	4				8		
	1	4	4						
10		2	5	7	8	15			
15		3	20	46					
17.0'								Mixed glacial till and weathered rock. (Moist/wet-very compact) 17.0'	Boring terminated @ 17.0'. Auger refusal - possible bedrock or boulder

N = No. blows to drive 2 spoon 12 with 140 lb. pin wt. falling 30 per blow
 C = No. blows to drive casing with 3-1/4" I.D. hollow stem auger casing. per blow
 METHOD OF INVESTIGATION Visual by geologist

DATE STARTED <u>1-4-83</u> FINISHED <u>1-4-83</u> SHEET <u>1</u> OF <u>1</u>	EMPIRE SOILS INVESTIGATIONS INC. SUBSURFACE LOG	HOLE NO. <u>9</u> SURF ELEV. <u>106.1</u> G.W. DEPTH <u>28'</u> in casing at completion
---	---	---

PROJECT Oil Spill Investigation
Job No. GTA-82-17J

LOCATION Route 22, Pawling, NY
Dutchess County

DEPTH	SAMPLE NO.	BLOWS ON SAMPLER					BLOW IN CASING	SOIL OR ROCK CLASSIFICATION	NOTES
		0	6	12	18	24			
0								TOPSOIL	0.5'
								Brown SILT and fine SAND. (Moist-loose)	
5		3	3				5		
		1	2	2					
10		2	3	5	8	13			11.0'
								Stratified brown fine to coarse SAND and fine to coarse GRAVEL, trace to some silt, cobbles. (Moist-loose)	
15		2	2				6		
		3	4	4					
20		4	4				9	Similar; wet	
		4	5	9					
25		5	8	10	20	30		Brown SILT with embedded GRAVEL and ROCK FRAGMENTS. (Wet-compact)	23.5' ±
									28.0'
30								Boring terminated @ 28.0'. Auger refusal - possible bedrock or boulder.	

N = No. blows to drive 2 spoon 12 with 140 lb pin wt. falling 30 per blow CLASSIFICATION Visual by
 C = No. blows to drive casing with lb weight falling per blow geologist
 METHOD OF INVESTIGATION 3-1/4" I.D. hollow stem auger casing



RQD - ROCK QUALITY DESIGNATION

after Deer, D.U. (1963)

"Technical Description of Rock Cores for Engineering Purposes",

Felsmechanik und Ingenieurgeologie, 1, 1, 16-22.

RQD - is a modified core recovery ratio (minimum core diameter - NX,
2 1/8" inch)

Method: Determine by considering only segments of core that are at
least 4 inches long and are hard and sound.

Mechanical Breaks obviously caused by drilling are ignored.

(These breaks are fresh and when the two pieces of core
are fitted together they form a tight single piece.)

Measure the entire length of such segments, divide this
sum by the length of core run and multiply by 100% (RQD
is expressed as a percentage).

Example: A total of 2.5 feet of 4 inch plus pieces was recovered
from Run #1.

Run #1 from 15.0' to 20.0'

$$RQD = \frac{2.5'}{5.0'} = 50\%$$

NOTE: Carefully examine core to distinguish differences between
drilling breaks and natural fractures. Fractures will generally
have some type of film or rust stains along the fracture surface.
"Healed" fractures should also be considered a natural break in
the rock if the mineral in the fracture is softer or weaker
than the surrounding rock core.

APPENDIX C

Tabulated Water Level Data

2.62-

OBSERVATION WELL READINGS

PROJECT Oil Spill Containment

LOCATION Pawling, New York

METHOD of READING ELECTRIC PROBE

REFERENCE POINT (or MARK) Top of Well csg

DATE 19 May 1983 TIME 1000 (Start)

Well No.	Depth	Ref. Elev.	Elev.
3	8.5	98.1	89.6
6	7.7	90.4	82.7
8	10.7	93.4	82.7
8R	10.8	93.2	82.4
10	15.5	103.7	88.2
10R	15.2	103.7	88.5
11	12.0	97.1	85.1
11R	13.7	97.5	83.8
12R	16.7	101.1	84.4
13R	17.3	104.3	87.0
14	16.0	106.1	90.1
14R	16.2	106.2	90.0
15	15.2	104.9	89.7
16	13.6	103.2	89.6
16R	13.7	103.0	89.3
17	15.7	102.0	86.3
18	15.6	103.5	87.9
18R	15.7	103.6	87.9
19	18.3	103.5	85.3
Marios	15.7	100.3	84.6
Surplus Store	24.1	103.6	79.5
Corral Ford	21.8	105.4	83.6

TIME 1115 (Finish)

REFERENCE POINT (or MARK).

DATE _____ TIME _____ (Start

[illegible]


TIME _____ (Finish)

TIME _____ :05

APPENDIX D

Mechanical Analysis Results

GRAIN SIZE DISTRIBUTION CURVE



SAMPLE INFORMATION:

Shaded area represents approximate range of grain size distribution curves obtained from mechanical analyses of nine 2" O.D. X 1-3/8" I.D. split barrel samples recovered from test borings. For individual analysis results refer to tabulation following this figure.

NOTE: VISUAL SOIL CLASSIFICATIONS ON E.S.I. SUBSURFACE LOGS ARE BASED ON THE UNIFIED SOIL CLASSIFICATION SYSTEM.

EMPIRE
SOILS INVESTIGATIONS INC.

MECHANICAL
ANALYSIS

OIL SPILL CONTAINMENT
PAWLING, NEW YORK

DR. BY:

CH'D.

DATE: 9/83


PROJ. NO. 82-17.1

2.65

APPENDIX E

Chemical Analysis Results

2.67



CAMO LABORATORIES

A DIVISION OF CAMO POLLUTION CONTROL, INC.

POUGHKEEPSIE AREA FACILITY
CAMO LABORATORY
367 VIOLET AVENUE
POUGHKEEPSIE, N.Y. 12601
(914) 473-9200

ROCHESTER AREA FACILITY
LOZIER/CAMO LABORATORY
23 NORTH MAIN STREET
FAIRPORT, N.Y. 14450
(716) 425-2210

July 13, 1983

New York State Department
of Transportation
4 Burnett Boulevard
Poughkeepsie, New York 12603

Attn: Mr. John Schaff

RE: Pawling, Dutchess County
Contract No.: D200177
Spill No.: 811902, PIR: SP1633.701
CAMO Log No.: 83-6-12457

Dear Sir:

CAMO Laboratories' personnel collected thirty (30) water samples June 22 - 24, 1983, with a request to analyze for DOT 602 Aromatics; the presence of gasoline.

All analyses were performed in accordance with The New York State Department of Health modified EPA 602 method "Guidelines Establishing Test Procedures for the Analysis of Pollutants; Proposed Regulations", Federal Register, Monday, December 3, 1979.

The results of this analytical investigation are the subject of this report. If you have any questions, please feel free to call. Thank you.

Sincerely,

John P. Dullaghan
Director
Measurement Services

JPD:sas
Enclosures

TABLE 1

2.68

AROMATICS

(DOT ADAPTED METHOD 602)

All results in ug/l unless noted otherwise

STAGNANT WELL WATER

COMPOUND	SAMPLE IDENTIFICATION				
	MW #1 B - 14s	MW #2 B - 14r	MW #3 B - 3s	MW #4 B - 15s*	MW #5 B - 16r
Benzene	<1	<1	63		220
Trichloroethylene	<1	<1	<1		1
Toluene	<1	<1	3900		1700
Tetrachloroethylene	<1	<1	<1		<1
Ethylbenzene	<1	<1	56		9
P-Xylene	<1	<1	230		9
M-Xylene	<1	<1	960		26
Chlorobenzene	<1	<1	<1		<1
O-Xylene	<1	<1	650		62
1,4,Dichlorobenzene	<1	<1	<1		<1
1,3,Dichlorobenzene	<1	<1	<1		<1
1,2,Dichlorobenzene	<1	<1	<1		<1
Presence of Gasoline	Not Present	Not Present	(Xylene ratio >2) Present		(Xylene ratio >2) Present

Presence of Gasoline Criteria: (A) - The presence of benzene, toluene, ethylbenzene and all three isomers of xylene. (B) - The xylene isomers present at approximately the same concentration (within a factor of 2).

*Sample Not Received, well dry at time of collection.

TABLE 1 - (Cont.)

2.69-

AROMATICS(DOT ADAPTED METHOD 602)

All results in ug/l unless noted otherwise

STAGNANT WELL WATER

COMPOUND	SAMPLE IDENTIFICATION				
	MW #6 B - 16s	MW #7 B - 13r	MW #8 B - 18r	MW #9 B - 18s*	MW #10 B - 10r
Benzene	<1	<1	10		<1
Trichloroethylene	2	<1	<1		<1
Toluene	2	<1	33		1.4
Tetrachloroethylene	1	<1	<1		<1
Ethylbenzene	<1	<1	<1		<1
P-Xylene	<1	<1	3		<1
M-Xylene	<1	<1	11		<1
Chlorobenzene	<1	<1	<1		<1
O-Xylene	<1	<1	10		<1
1,4,Dichlorobenzene	<1	<1	<1		<1
1,3,Dichlorobenzene	<1	<1	<1		<1
1,2,Dichlorobenzene	<1	<1	<1		<1
Presence of Gasoline	Not Present	Not Present	Not Present		Not Present

Presence of Gasoline Criteria: (A) - The presence of benzene, toluene, ethylbenzene and all three isomers of xylene. (B) - The xylene isomers present at approximately the same concentration (within a factor of 2).

*Sample Not Received, well dry at time of collection.

TABLE 1 - (Cont.)

AROMATICS

(DOT ADAPTED METHOD 602)

All results in ug/l unless noted otherwise

STAGNANT WELL WATER

2.69

COMPOUND	SAMPLE IDENTIFICATION				
	MW #11 B - 10s*	MW #12 B - 19s	MW #13 B - 17	MW #14 B - 12r	MW #15 B - 11s
Benzene		<1	<1	<1	360
Trichloroethylene		<1	<1	<1	<1
Toluene		<1	<1	<1	100
Tetrachloroethylene		<1	<1	<1	<1
Ethylbenzene		<1	<1	<1	32
P-Xylene		<1	<1	<1	66
M-Xylene		<1	<1	<1	85
Chlorobenzene		<1	<1	<1	<1
O-Xylene		<1	<1	<1	350
1,4,Dichlorobenzene		<1	<1	<1	<1
1,3,Dichlorobenzene		<1	<1	<1	<1
1,2,Dichlorobenzene		<1	<1	<1	<1
Presence of Gasoline		Not Present	Not Present	Not Present	(Xylene ratio > 2) Present

Presence of Gasoline Criteria: (A) - The presence of benzene, toluene, ethylbenzene and all three isomers of xylene. (B) - The xylene isomers present at approximately the same concentration (within a factor of 2).

*Sample Not Received, well dry at time of collection.

AROMATICS(DOT ADAPTED METHOD 602)

All results in ug/l unless noted otherwise

STAGNANT WELL WATER

COMPOUND	SAMPLE IDENTIFICATION				
	MW #16 B - 11s*	MW #17 B - 8r	MW #18 B - 8s	MW #19 B - 6s	Field Blank
Benzene		<1	<1	<1	<1
Trichloroethylene		<1	<1	1	<1
Toluene		<1	<1	<1	<1
Tetrachloroethylene		<1	<1	<1	<1
Ethylbenzene		<1	<1	<1	<1
P-Xylene		<1	<1	<1	<1
M-Xylene		<1	<1	<1	<1
Chlorobenzene		<1	<1	<1	<1
O-Xylene		<1	<1	1	<1
1,4,Dichlorobenzene		<1	<1	<1	<1
1,3,Dichlorobenzene		<1	<1	<1	<1
1,2,Dichlorobenzene		<1	<1	<1	<1
Presence of Gasoline		Not Present	Not Present	Not Present	Not Present

Presence of Gasoline Criteria: (A) - The presence of benzene, toluene, ethylbenzene and all three isomers of xylene. (B) - The xylene isomers present at approximately the same concentration (within a factor of 2).

*Sample Not Received, well dry at time of collection.

TABLE 2

AROMATICS

(DOT ADAPTED METHOD 602)

All results in ug/l unless noted otherwise

REGENERATED WELL WATER

COMPOUND	SAMPLE IDENTIFICATION				
	MW #1 B - 14s	MW #2 B - 14r	MW #3 B - 3s	MW #4 B - 15s*	MW #5 B - 16r
Benzene	<1	<1	440		220
Trichloroethylene	<1	<1	200		<1
Toluene	<1	<1	7100		1900
Tetrachloroethylene	<1	<1	<1		<1
Ethylbenzene	<1	<1	200		25
P-Xylene	<1	<1	300		14
M-Xylene	<1	<1	1200		20
Chlorobenzene	<1	<1	<1		<1
O-Xylene	<1	<1	780		38
1,4-Dichlorobenzene	<1	<1	350		14
1,3-Dichlorobenzene	<1	<1	75		3
1,2-Dichlorobenzene	<1	<1	35		4
Presence of Gasoline	Not Present	Not Present	(Xylene ratio >2) Present		(Xylene ratio >2) Present

Presence of Gasoline Criteria: (A) - The presence of benzene, toluene, ethylbenzene and all three isomers of xylene. (B) - The xylene isomers present at approximately the same concentration (within a factor of 2).

*Sample Not Received, well dry at time of collection.

2.71

AROMATICS(DOT ADAPTED METHOD 602)

All results in ug/l unless noted otherwise

REGENERATED WELL WATER

COMPOUND	SAMPLE IDENTIFICATION				
	MW #6 B - 16s	MW #7 B - 13r	MW #8 B - 18r	MW #9 B - 18s*	MW #10 B - 10
Benzene	<1	<1	<1		<1
Trichloroethylene	<1	<1	<1		<1
Toluene	<1	<1	4000		<1
Tetrachloroethylene	<1	<1	<1		<1
Ethylbenzene	<1	<1	290		<1
P-Xylene	<1	<1	70		<1
M-Xylene	<1	<1	5000		<1
Chlorobenzene	<1	<1	<1		<1
O-Xylene	<1	<1	320		<1
1,4,Dichlorobenzene	<1	<1	300		<1
1,3,Dichlorobenzene	<1	<1	130		<1
1,2,Dichlorobenzene	<1	<1	<1		<1
Presence of Gasoline	Not Present	Not Present	Not Present		Not Present

Presence of Gasoline Criteria: (A) - The presence of benzene, toluene, ethylbenzene and all three isomers of xylene. (B) - The xylene isomers present at approximately the same concentration (within a factor of 2).

*Sample Not Received, well dry at time of collection.

TABLE 2 - (Cont.)

AROMATICS

(DOT ADAPTED METHOD 602)

All results in ug/l unless noted otherwise

REGENERATED WELL WATER

COMPOUND	SAMPLE IDENTIFICATION				
	MW #11 B - 10s*	MW #12 B - 19s	MW #13 B - 17	MW #14 B - 12r	MW #15 B - 11r
Benzene		<1	<1	<1	520
Trichloroethylene		<1	1.4	<1	1
Toluene		<1	1	<1	100
Tetrachloroethylene		<1	23	<1	1
Ethylbenzene		<1	<1	<1	8.2
P-Xylene		<1	<1	<1	57
M-Xylene		<1	<1	<1	28
Chlorobenzene		<1	<1	<1	<1
O-Xylene		<1	<1	<1	510
1,4,Dichlorobenzene		<1	<1	<1	<1
1,3,Dichlorobenzene		<1	<1	<1	<1
1,2,Dichlorobenzene		<1	<1	<1	<1
Presence of Gasoline		Not Present	Not Present	Not Present	(Xylene ratio >2) Present

Presence of Gasoline Criteria: (A) - The presence of benzene, toluene, ethylbenzene and all three isomers of xylene. (B) - The xylene isomers present at approximately the same concentration (within a factor of 2).

*Sample Not Received, well dry at time of collection.

2.73

TABLE 2 - (Cont.)

AROMATICS

(DOT ADAPTED METHOD 602)

All results in ug/l unless noted otherwise

REGENERATED WELL WATER

COMPOUND	SAMPLE IDENTIFICATION				
	MW #16 B - 11s*	MW #17 B - 8r	MW #18 B - 8s	MW #19 B - 6s	Field Blank
Benzene		<1	<1	<1	<1
Trichloroethylene		<1	<1	<1	<1
Toluene		<1	<1	1	<1
Tetrachloroethylene		<1	<1	2	<1
Ethylbenzene		<1	<1	<1	<1
P-Xylene		<1	<1	1	<1
M-Xylene		<1	<1	<1	<1
Chlorobenzene		<1	<1	<1	<1
O-Xylene		<1	<1	<1	<1
1,4,Dichlorobenzene		<1	<1	<1	<1
1,3,Dichlorobenzene		<1	<1	<1	<1
1,2,Dichlorobenzene		<1	<1	<1	<1
Presence of Gasoline		Not Present	Not Present	Not Present	Not Present

Presence of Gasoline Criteria: (A) - The presence of benzene, toluene, ethylbenzene and all three isomers of xylene. (B) - The xylene isomers present at approximately the same concentration (within a factor of 2).

*Sample Not Received, well dry at time of collection.

2.74

TABLE 3

N.Y.S. D.O.T. - Pawling, New York Project

Well Measurements

<u>Well Number</u>	<u>Well Depth</u>	<u>Static Water Level</u>	<u>Height of Water Column</u>
B-14s	23'	18'	5'
B-14r	35'	18'1"	16'11"
B-3s	Not Recorded		
B-15s	16'	16'	0
B-16r	35'	16'6"	18'6"
B-16s	16'6"	15'8"	8"
B-13r	26'6"	18'6"	7'6"
B-18r	16'6"	16'6"	0
B-18s	25'	17'6"	7'6"
B-10r	38'	17'3"	20'9"
B-10s	Dry		
B-19s	21'	19'8"	1'4"
B-17	19'	17'1"	1'11"
B-12r	23'6"	18'6"	5'
B-11r	32'	16'6"	15'6"
B-11s	11'9"	11'9"	0
B-8r	35'11"	12'9"	23'2"
B-8s	14'6"	12'9"	1'9"
B-6s	13'	10'	3'



Ref. 3.1

January 17, 1984

New York State Department
of Transportation
4 Burnett Boulevard
Poughkeepsie, New York 12603

Attention: John Schaff
Assistant Regional Oil Spill Engineer

Reference: Hydrocarbon Spill
Pawling, Dutchess County, New York
Spill No. 811902
P.I.N. SP 1633.701
Empire File GTA-82-17J
SUPPLEMENTAL HYDROGEOLOGIC EVALUATIONS
LETTER REPORT

Gentlemen:

This correspondence is intended to summarize hydrogeologic evaluations by Empire-Thomsen supplemental to our formal report dated October 24, 1983, previously submitted to your office.

In the wake of heavy rainfall in eastern New York State on December 12-14, 1983, the writer returned to the referenced spill site on December 17, 1983 to obtain additional hydrogeologic data. It was anticipated that the heavy precipitation would result in a rise of the water table at this site, of sufficient magnitude to permit groundwater sampling of a key monitoring well, B-15, which was dry at the time of earlier sampling in June, 1983.

Water level readings were obtained on December 17, 1983 in all monitors with the exception of B-6, which had been destroyed. This water level data, presented on the attached tabulation sheet, was used to contour the water table in the project area on the date of readings, as illustrated on Drawing No. 7, attached. This drawing indicates the hydrogeologic regime at this site on December 17, 1983 to be essentially the same as that detailed in Empire-Thomsen's October, 1983 report. Overall groundwater flow in the area is in a southward to southwestward direction, as shown by the arrows on Drawing No. 7. Groundwater monitor cluster B-14 lies upgradient of the Amoco station, while monitor B-15 is located downgradient of those facilities.

REG. DIR.		PERSNL.	
AST. TO RD		PLANNING	
ADMIN.		REAL EST.	

REC'D
DOT JAN 18 1984
REG
8

CONST.		SOILS VAT.	
EXP.			
ENV.			

Comparison of specific water level determinations in the monitors on December 17 with similar data for the chemical sampling dates in June, 1983 (presented in our formal report) indicates the water table to be generally one (1) to three (3) feet higher in elevation on December 17. As a result of this overall rise of the water table, groundwater was present in monitor B-15 on December 17, 1983.

Grab samples of groundwater were obtained by the writer on December 17 from the surface of the "standing" water column in the following monitors:

B-3	B-16 (B-16 Shallow)
B-11R (B-11 Deep)	B-16R (B-16 Deep)
B-13R	B-17
B-14 (B-14 Shallow)	B-18 (B-18 Shallow)
B-15	B-18R (B-18 Deep)

These grab samples were recovered prior to obtaining water level data in the monitors, in order to eliminate potential cross-contamination via the well probe used for water level determinations.

Groundwater samples were obtained through the use of 40 milliliter septum vials immersed several times in the upper portion of the water column in each monitor, allowing recovery of sufficient sample volume to fill a duplicate vial and eliminate vapor bubbles from that duplicate receptacle. Sample retrieval vials were not reused; two new, clean vials were employed for sample recovery and preservation at each sampling point. All samples remained under refrigeration in the custody of Thomsen Associates until their delivery on December 19, 1983 to Galson Technical Services, Inc., East Syracuse, New York.

In addition to the ten groundwater samples obtained, a "blank", consisting of distilled water, was prepared and kept with the samples at all times.

Following authorization from your office, samples from selected monitors, including those wells screened over the water table in the vicinity of the Amoco station (B-14 and B-15), were analyzed by Galson Technical Services, Inc. for concentrations of benzene, toluene, xylene and total hydrocarbons exclusive of these three components. Analysis results have been furnished to your office directly under separate cover by the testing agency; a copy of these results is attached to this letter.



3,3
John Schaff
January 17, 1984
Page 3

The sample from monitoring well B-14, upgradient of the Amoco station, contained less than one microgram per liter (ug/l) of each of the parameters analyzed. However, monitor B-15, downgradient of Amoco, exhibited hydrocarbon contamination of groundwater identified by the analytical laboratory as "gasoline".

These chemical analysis results, in conjunction with the configuration of the water table over the site on the date of sampling, indicate a hydrocarbon (gasoline) contamination plume emanating from the active Amoco station in the project area.

The results discussed above are in agreement with, and collectively corroborate, Empire-Thomsen's previous findings relating to this investigation.

We trust that this additional information is of assistance to your office in efforts to remediate this hydrocarbon spill.

Should you have any questions, comments or additional input in this regard, please contact the writer at your convenience.

Respectfully submitted,

THOMSEN ASSOCIATES

A handwritten signature in cursive script, reading "Ronald Ausburn".

Ronald Ausburn, CPGS
Project Manager

LOCATION Pawling, N.Y.


TIME _____ (Finish)

315

Galson

Technical Services, Inc.

6601 Kirkville Road
Post Office Box 546
E. Syracuse, N.Y. 13057
Tel: (315) 432-0506



Environmental Sciences
Division

RECEIVED
E.S.I.—ALBANY

JAN 16 1984

January 9, 1984

Mr. John Schaff
Asst. Regional Oil Spill Engineer
N.Y.S. Dept. of Transportation, Region 8
4 Burnett Blvd.
Poughkeepsie, NY 12603

RE: GTS #61-047

Dear Mr. Schaff:

Enclosed are the results of the analyses performed on the samples we received from Empire Soils on December 19, 1983.

Originally, you authorized us to analyze only samples B-14 and B-15.

On December 29, 1983, you told us also to analyze B-3, B-11-deep, B-16-deep, B-18-deep, and B-18-shallow. We also did B-16-shallow.

Of the set, only B-15 definitely contained gasoline. B-11-deep had a pattern of early eluting peaks that did not match gasoline. B-16-deep had only a single large peak. The shallow wells had miscellaneous small peaks.

If you have any questions concerning our results, please feel free to call.

Sincerely,


GALSON TECHNICAL SERVICES, INC.

Eva Galson
Laboratory Director

EG/sl

Enclosure

xc: Ron Ausburn, Empire Thompson



Galson

Technical Services, Inc.

6601 Kirkville Road
Post Office Box 546
E. Syracuse, N.Y. 13057
Tel: (315) 432-0506

LABORATORY ANALYSIS REPORT

Client: EMPIRE SOILS INVES.
Task Number: 83121901
Location: PAWLING, NY

Job Number: G1-047

Date Sampled: 12/17/83

SPILL: 811902
PIN: SP1633.701

BENZENE, TOLUENE, XYLENE, THC IN WATER


SAMPLE ID	GTS #	BENZENE (ug/l)	TOLUENE (ug/l)	XYLENE (ug/l)	*TOTAL HYDROCARBONS (ug/l)
WELL B-3	A17281	<1	<1	<1	7
WELL B-11 DEEP	A17282	<1	<1	1	701
WELL B-16 SHALLOW	A17285	<1	<1	<1	7
WELL B-18 SHALLOW	A17288	<1	<1	<1	2
WELL B-14 SHALLOW	A17283	<1	<1	<1	<1
WELL B-15	A17284	91	2870	1610	6690
WELL B-16 DEEP	B268	<1	<1	<1	123
WELL B-18 DEEP	A17287	<1	<1	<1	11
BLANK	A17289	<1	<1	<1	<1
WELL B-17	A17286	NOT ANALYZED	NA	NA	NA
WELL B-13	A17290	NOT ANALYZED	NA	NA	NA

(<) LESS THAN
(>) GREATER THAN
NA - NOT APPLICABLE
ND - NOT DETECTABLE
NS - NOT SPECIFIED

Footnotes: *Other than benzene, toluene, xylene, quantified as heptane.

Submitted by: *[Signature]*
Approved by:
Date: 1/9/84

3.7



3.7

Ref. 4

PRIORITY CODE: 2a SITE CODE: 314060
NAME OF SITE: NYSDOT Spill No. 811902 REGION: 3
STREET ADDRESS: Route 22
TOWN/CITY: Pawling COUNTY: Dutchess
NAME OF CURRENT OWNER OF SITE: Jay Maxwell
ADDRESS OF CURRENT OWNER OF SITE: Maxwell Engine Rebuilders, Rt. 22, Pawling

ESTIMATED SIZE: 20 ACRES

Commercial area along Route 22, north of Brady Brook and south of Akindale Rd., just north of town line of Patterson in Putnam County.

- 1) Maxwell Engine Rebuilders
- 2) Inex Venezia, guest house
- 3) Corral Ford
- 4) Heinchon Dairy
- 5) Mario's Pizza

<u>TYPE</u>	<u>QUANTITY</u> (POUNDS, DRUMS, TONS, GALLONS)
Benzene	
Toluene	
M-xylene	
O-xylene.	
Ethyl benzene	
Tetrachloroethylene	

TIME PERIOD SITE WAS USED FOR HAZARDOUS WASTE DISPOSAL:

_____, 19 ____ TO _____, 19 ____

OWNER(S) DURING PERIOD OF USE: _____

SITE OPERATOR DURING PERIOD OF USE: _____

ADDRESS OF SITE OPERATOR: _____

ANALYTICAL DATA AVAILABLE: AIR ☐ SURFACE WATER ☐ GROUNDWATER ☒
SOIL ☐ SEDIMENT ☐ NONE ☐

CONTRAVENTION OF STANDARDS: GROUNDWATER ☐ DRINKING WATER ☒
SURFACE WATER ☐ AIR ☐

SOIL TYPE: _____

DEPTH TO GROUNDWATER TABLE: _____

LEGAL ACTION: TYPE: _____ STATE ☐ FEDERAL ☐

STATUS: IN PROGRESS ☐ COMPLETED ☐

REMEDIAL ACTION: PROPOSED ☐ UNDER DESIGN ☐

IN PROGRESS ☐ COMPLETED ☐

NATURE OF ACTION: _____

ASSESSMENT OF ENVIRONMENTAL PROBLEMS:

Chemicals in private wells and groundwater.

ASSESSMENT OF HEALTH PROBLEMS:

INDEPENDENT INFORMATION

PERSON(S) COMPLETING THIS FORM:

NEW YORK STATE DEPARTMENT OF
ENVIRONMENTAL CONSERVATION

NEW YORK STATE DEPARTMENT OF HEALTH

NAME A. Woodard

NAME Ronald Tramontano

TITLE SWMS

TITLE Bur. Tox. Subst. Assess.

NAME R.A. Olazagasti

NAME _____


TITLE SWMS

TITLE _____

DATE: 12/83

DATE: 12/83

1" = 400'




Uncontrolled Hazardous Waste Site Ranking System

A Users Manual (HW-10)

**Originally Published in
the July 16, 1982, *Federal Register***

**United States
Environmental Protection
Agency**

1984



Source: Rainfall Frequency Atlas of the United States, Technical Paper No. 40, U.S. Department of Commerce, U.S. Government Printing Office, Washington, D.C., 1963.

FIGURE 8
1-YEAR 24-HOUR RAINFALL
(INCHES)

513

TABLE 2


PERMEABILITY OF GEOLOGIC MATERIALS*

Type of Material	Approximate Range of Hydraulic Conductivity	Assigned Value
Clay, compact till, shale; unfractured metamorphic and igneous rocks	$<10^{-7}$ cm/sec	0
Silt, loess, silty clays, silty loams, clay loams; less permeable limestone, dolomites, and sandstone; moderately permeable till	$10^{-5} - 10^{-7}$ cm/sec	1
Fine sand and silty sand; sandy loams; loamy sands; moderately permeable limestone, dolomites, and sandstone (no karst); moderately fractured igneous and metamorphic rocks, some coarse till	$10^{-3} - 10^{-5}$ cm/sec	2
Gravel, sand; highly fractured igneous and metamorphic rocks; permeable basalt and lavas; karst limestone and dolomite	$>10^{-3}$ cm/sec	3

*Derived from:


Davis, S. N., Porosity and Permeability of Natural Materials in Flow-Through Porous Media, R.J.M. DeWiest ed., Academic Press, New York, 1969

Freeze, R.A. and J.A. Cherry, Groundwater, Prentice-Hall, Inc., New York, 1979



Source: Climatic Atlas of the United States, U.S. Department of Commerce, National Climatic Center, Asheville, N.C., 1979.

FIGURE 5
NORMAL ANNUAL TOTAL PRECIPITATION (INCHES)



Source: Climatic Atlas of the United States, U.S. Department of Commerce, National Climatic Center, Asheville, N.C., 1979.

FIGURE 4
MEAN ANNUAL LAKE EVAPORATION
(IN INCHES)

**SUPERFUND
NATIONAL PRIORITIES LIST SEMINAR
EPA REGION II
ALBANY, NY**

The MITRE Corporation

April 2-3, 1986

56

Observed Release

The release and the background well must be in the same aquifer at comparable elevations.

Knowledge of flow gradients helps in determining where to look for background versus contamination...but beware of local or seasonal variation. The purpose is to find a nearby well in the aquifer of concern that is not under the influence of the site.

Background well(s) must discriminate out any alternative sources of the contamination.

The attribution of the release to the facility is strengthened if the substances found in the release are documented to have been deposited at the facility.

Depth of the Aquifer of Concern (Page 12)

- Distance between the deepest point of known contamination and the top of the aquifer of concern.
 - Deepest level at which contamination is documented.
 - Highest seasonal level of the saturated zone of the aquifer.
- If depth of deposit is unknown, 6 feet may be assumed.

Reference 6.1
STATE OF NEW YORK

OFFICIAL COMPILATION

OF

CODES, RULES AND REGULATIONS

MARIO M. CUOMO
Governor

GAIL S. SHAFFER
Secretary of State

Published by
DEPARTMENT OF STATE
162 Washington Avenue
Albany, New York 12231

1/83

than 4.0 mg/l.

Note 1: Refer to Note 1 under Class "AA" which is also applicable to Class "B" standards.

CLASS "C"

Best usage of waters. Suitable for fishing and all other uses except as a source of water supply for drinking, culinary or food processing purposes and primary contact recreation.

397 CN 9-30-74

2634 CN 11-15-86

TABLE I (contd.)

Item No.	Waters Index Number	Name	Comments	Map Ref. No.	Class	Standards
346	H-31-P 44-24-31-1a-P 102a	Subtrib. of East Branch Croton River		0-25se	B	B
347	H-31-P 44-24-31-P 102b	Subtrib. of East Branch Croton River		0-25sw	B	B
348	H-31-P 44-24-31-P 89o	Ballard Pond		0-25sw	B	B
X 349	H-31-P 44-24-32 portion	Brady Brook	From mouth to trib. 5.	0-25se	C	C(T)
350	H-31-P 44-24-32 portion	Brady Brook	From trib. 5 to source.	0-25se	D	D
351	H-31-P 44-24-32-2,3,5	Triba. of Brady Brook		0-25se	C	C(T)
352	H-31-P 44-24-32-3-P 89p	Subtrib. of Brady Brook		0-25se	D	D
353	H-31-P 44-24-32-5-P 89q	Subtrib. of Brady Brook		0-25se	D	D
354	H-31-P 44-24-32-6,8,9,10,12,13,15 and tribs. 8-1,8-2,8-P 89x,10-P 89r	Triba. of Brady Brook and subtribs.		0-25se	D	D

§ 864.6

TITLE 6 CONSERVATION

6.2

TABLE I (cont'd)

Item No.	Waters Index Number	Name	Description	Map Ref. No.	Class	Standards
280	H-31-P 44-23-5-P 80	Black Pond		0-24se	B	B
281	H-31-P 44-23-P 76j	Sagamore Lake		P-24ne	B	B
282	H-31-P 44-23-8,9,10 and tribs. 8-1, 8-1a,8-1b,8-1b-P 76K	Tribs. of West Branch Croton River and subtribs.		P-24ne	D	D
283	H-31-P 44-24 portion	East Branch Croton River	From mouth to P 89 (East Branch Reservoir).	P-25sw P-25nw P-25ne	A	A(T)
284	H-31-P 44-24 portion	East Branch Croton River	From P 89 (East Branch Reservoir) to trib. 16.	P-25ne	A	A
285	H-31-P 44-24 portion	* East Branch Croton River	From trib. 16 to Pawling.	P-25ne 0-25se	C	C(T)
286	H-31-P 44-24 portion	East Branch Croton River	From Pawling to source.	0-25se	D	D
287	H-31-P 44-24-1 portion	Holly Stream	From mouth to trib. 3. Parts not in New York City-owned lands.	P-25sw P-25nw P-25se	C	C
288	H-31-P 44-24-1 portion	Trib. of East Branch Croton River	From trib. 3 to source.	P-25se	C	C

S 864.6


TITLE 6 CONSERVATION

6.3

CHAPTER X DIVISION OF WATER RESOURCES
PAWLING QUADRANGLE

§ 864.9

6.4



MAP O-25 se

SIGNIFICANT HABITAT OVERLAY NO. 2 OF 2

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

DIVISION OF FISH AND WILDLIFE

BUREAU OF WILDLIFE

PREPARED FOR: SIGNIFICANT HABITAT UNIT

WILDLIFE RESOURCES CENTER

DELMAR, NEW YORK 12054

(518) 457-5782

PREPARED BY: HABITAT INVENTORY UNIT

GRID ZONE DESIGNATION: 18T OF 2

TO GIVE A SAMPLE REFERENCE THIS SHEET IS 1000 METERS

WB XB YB

WA XA YA

Locate first vertical line of unit and label it at unit and label it at unit margin up on the line itself. Estimate points from grid line to point. Locate first HORIZONTAL grid line below unit and label it. Labeling the line either on the left or right of the line itself. SAMPLE REFERENCE: SCALE: 1:250,000

QUAD: HARTFORD

45/0000

HARTFORD, MASS

REVISED: 12/31/85

Ref. 7.1

New York State Atlas of Community Water System Sources 1982

NEW YORK STATE
DEPARTMENT OF HEALTH




TABLE OF CONTENTS


FORWARD	PAGE 1						
COUNTY	PAGE	COUNTY	PAGE	COUNTY	PAGE	COUNTY	PAGE
ALBANY	56	FRANKLIN	42	ONEIDA	32	SCHOHARIE	60
ALLEGANY	14	FULTON	58	ONONDAGA	28	SCHUYLER	18
BRONX	70	GENESEE	8	ONTARIO	12	SENECA	24
BROOME	20	GRIFIN	64	ORANGE	72	STEBLIN	16
CATTARAUGUS	4	HAMILTON	48	ORLEANS	8	SUFFOLK	78
CAYUGA	24	HERKIMER	34	OSWEGO	30	SULLIVAN	70
CHAUTAUQUA	2	JEFFERSON	38	OTSEGO	60	TIOGA	20
CHEMUNG	16	KINGS	76	PUTNAM	66	TOMPKINS	18
CHENANGO	22	LEWIS	36	QUEENS	76	ULSTER	68
CLINTON	44	LIVINGSTON	10	RIENSSLAER	56	WARREN	50
COLUMBIA	64	MADISON	28	RICHMOND	76	WASHINGTON	52
CORTLAND	22	MONROE	8	ROCKLAND	74	WAYNE	26
DELAWARE	62	MONTGOMERY	58	ST. LAWRENCE	40	WESTCHESTER	74
DUTCHESS	66	NASSAU	76	SARATOGA	54	WYOMING	10
ERIE	6	NEW YORK	76	SCHENECTADY	56	YATES	12
ESSEX	46	NIAGARA	6				

8.2

LOCATION OF COMMUNITY WATER SYSTEM SOURCES-1982

NEW YORK STATE DEPARTMENT OF HEALTH
DIVISION OF ENVIRONMENTAL PROTECTION
BUREAU OF PUBLIC WATER SUPPLY PROTECTION

DUTCHESS and PUTNAM COUNTIES



SCALE 1:250,000

NORTH

[illegible]

POPULATION COUNT

Population within a 3-mile radius of each Phase I site is determined using the coordinate system illustrated below. The number of residences for each quadrant and section is determined by overlaying this pattern onto a U.S.G.S. 7.5 minute topographic map. A multiplier of 3.8 persons per residence is used to determine population in accordance with Mitre Model 1985.

A = 1 mile radius

$$106 \text{ dwellings} \times 3.8 = 403$$

B = 2 mile radius


$$121 \text{ dwellings} \times 3.8 = 460$$

C = 3 mile radius

$$314 \text{ dwellings} \times 3.8 = 1213$$

$$\text{Total Population} = 2915$$

(Figure not To Scale)



Reference
10.1

NEW YORK

MAP OF DUTCHESS COUNTY, NEW YORK
SHOWING LOCATION OF SELECTED WELLS AND SPRINGS



10.2




Table 13.--Records of selected wells in Dutchess County

Location: See section entitled "Explanation of Tables."

Altitude above sea level: Approximate altitude from topographic maps.

Type of well: Drl, drilled; Dn, driven.

Water level: Reported average water level. Plus sign (+) preceding figure indicates level to which water rises above land surface.

Use: Com, commercial; Dom, domestic; Ind, industrial; PS, public supply.

Remarks: gpd, gallons per day; gpm, gallons per minute; (a) water analysis in table 10; (b) log of well in table 12.

Well number	Location	Owner or occupant	Altitude above sea level (feet)	Type of well	Depth below land surface (feet)	Diameter (inches)	Depth to bedrock (feet)	Water-bearing formation	Water level below land surface (feet)	Method of lift	Yield (gallons per minute)	Use	Remarks
Du 1	13Y, 4.3W, 5.8W	Edward Lasher	80	Drl	69	6	44	Hudson River formation	8	Force	20	Farm	
Du 2	13Y, 3.7W, 6.2W	J. M. Coon	190	Drl	75	6	54	do.	25	None	2	None	Yield inadequate. Well destroyed.
Du 4	13Y, 3.2W, 6.0W	W. H. Redder	200	Drl	77	6	50	do.	12	--	35	Dom	
Du 7	13Y, 3.7W, 6.7W	Edward Sturges	220	Drl	210	6	6	do.	20	Suction	20	Dom	
Du 8	13Y, 3.8W, 7.1W	J. Rockefeller	280	Drl	144	6	12	do.	12	do.	40	Dom	
Du 9	13Y, 3.6W, 7.6W	Charles Denegar	220	Drl	112	6	8	do.	17	Jet	3	Farm	No increase in yield below a depth of 70 ft.
Du 12	13Y, 4.0W, 9.0W	Roland Redmond	60	Drl	321	8 to 6	99	do.	34	None	--	None	Well abandoned.
Du 13	13Y, 4.0W, 8.7W	do.	100	Drl	320	10 to 8	43	do.	39	--	4	None	do.
Du 14	13Y, 4.1W, 8.0W	Village of Tivoli	120	Drl	60	10	40	do.	20	Turbine	60	PS	Average consumption is 4,000 gpd. (b).
Du 15	13Y, 4.9W, 8.6W	Albert Sengstack	180	Drl	79	6	23	do.	26	Force	4	Dom	
Du 16	13Y, 5.1W, 8.8W	Howland Davis	160	Drl	202	6	9	do.	--	do.	36	Dom	
Du 18	13Y, 4.8W, 7.3W	G. L. Cole	180	Drl	127	6	62	do.	7	--	20	Farm	
Du 19	13Y, 4.5W, 6.7W	J. Hainshon	180	Drl	67	6	40	do.	14	Force	20	Farm	
Du 20	13Y, 3.2W, 4.1W	George Hubbard	180	Drl	60	6	25	do.	5	Suction	20	Dom	
Du 25	13Y, 1.0W, 6.7W	C. Schaffer	200	Drl	137	6	19	do.	32	None	10	Dom	Yield 0.75 gpm when well was 90 ft deep. (b).
Du 26	13Y, 1.9W, 6.3W	Malcolm Cooper	200	Drl	197	6	57	do.	2	do.	20	Farm	
Du 28	13Y, 3.3W, 7.6W	M. Schweiger	200	Drl	54	6	13	do.	30	Force	5	Dom	
Du 32	13Y, 1.7W, 7.9W	Samuel Robbins	200	Drl	98	6	15	do.	35	do.	12	Farm	
Du 35	13Y, 1.4W, 8.3W	William Blohm	160	Drl	78	6	10	do.	2	Jet	2	Dom	
Du 36	13Y, 1.6W, 8.2W	C. Sottery	160	Drl	132	6	--	do.	17	Suction	5	Dom	Yield 2.5 gpm when well was 27 ft deep. (a).
Du 38	13Y, 0.8W, 8.3W	R. Bolander	160	Drl	74	6	18	do.	--	--	5	Com	
Du 39	13Y, 0.1W, 8.5W	Duncan Watt	180	Drl	97	6	11	do.	13	Suction	8	Dom	
Du 40	13Y, 1.5W, 8.7W	A. C. Zebriskie	120	Drl	620	6	40	do.	60	do.	3	Dom	Listed in U. S. Geol. Survey Water-Supply Paper 102 (see well 147, p. 173).
Du 41	13Y, 0.9W, 6.3W	Ira Barringer	200	Drl	110	6	52	do.	6	--	40	Dom	
Du 42	13Y, 1.9W, 5.4W	H. Fraleigh	200	Drl	84	6	14	do.	12	--	30	Dom	
Du 43	13Y, 2.4W, 7.2W	Percy Sherman	260	Drl	132	6	40	do.	12	--	17	Dom	
Du 44	13Y, 2.3W, 7.6W	Harold Wheeler	240	Drl	88	6	17	do.	3	--	30	Dom	
Du 45	13Y, 2.3W, 4.6W	J. J. Rail	180	Dug	12	48	--	Pleistocene deposit	8	Suction	2	Dom	
Du 46	13Y, 2.8W, 3.6W	G. Osborne	340	Drl	86	6	5	Hudson River formation	24	--	12	Dom	
Du 48	13Y, 1.1W, 3.0W	A. Singhar	380	Drl	229	6	--	do.	40	Force	15	Farm	(a).
Du 50	13Y, 1.9W, 2.8W	P. Clemets	360	Drl	62	6	28	do.	--	--	5	Dom	Well supplies two homes.
Du 51	13Y, 2.7W, 2.7W	F. C. Wolcott	290	Drl	118	6	15	do.	14	Suction	5	Farm	
Du 53	13Y, 0.5W, 2.6W	John Odak	540	Drl	84	6	15	do.	20	--	4	Dom	
Du 54	13Y, 1.0W, 2.3W	Clinton Gallagher	580	Drl	118	6	6	do.	6	Suction	4	Farm	Yield 2 gpm when well was 40 ft deep.
Du 55	13Y, 1.7W, 1.3W	E. A. Trotter	500	Drl	107	6	85	do.	15	Force	5	Dom	

Table 13.--Records of selected wells in Dutchess County (Continued)

Well number	Location	Owner or occupant	Altitude above sea level (feet)	Type of well	Depth below land surface (feet)	Diameter (inches)	Depth to bedrock (feet)	Water-bearing formation	Water level below land surface (feet)	Method of lift	Yield (gallons per minute)	Use	Remarks
Du 519	14Y, 13.0S, 5.0E	Sanita Hills Camp	900	Drl	185	6	0	Hudson River formation	37	Force	20	None	Three other abandoned wells on property.
Du 524	14Y, 13.3S, 4.3E	Interchurch Camp Society, Inc.	740	Drl	52	8 to 6	20	Cheshire quartzite and granite and gneiss, undiff.	18	do.	8	Dom	Drawdown 30 ft after pumping 8 gpm for 8 hrs.
Du 525	14Y, 12.8S, 4.5E	Whaley Lake Inn	720	Drl	72	6	62	Granite and gneiss, undiff.	24	do.	--	Dom	
Du 526	15Y, 2.0N, 8.6W	Robert Lyons	220	Drl	30	6	--	Pleistocene sand and gravel	4	Suction	25	Dom	
Du 527	14Y, 7.2S, 9.5E	Wingdale Hotel	430	Drl	130	6	0	Stockbridge limestone	--	--	--	Dom	
Du 528	14Y, 6.2S, 10.0E	Brockshire Manor	330	Drl	180	6	80	do.	7	Suction	--	Dom	
Du 529	15Y, 8.0N, 2.6W	Mary Sickle	400	Drl	87	6	30	Hudson River formation	16	do.	6	Dom	(b).
Du 530	14Y, 15.4S, 10.7E	G. O'Hara	1,260	Drl	185	6	2	do.	--	Jet	30	Dom	Yield 20 gpm when well was 150 ft deep. Temperature 50°F, June 1949.
Du 531	14Y, 13.8S, 7.3E	Charles Utter	520	Drl	300	6	8	Stockbridge limestone	8	Suction	6	Dom	
Du 532	14Y, 15.5S, 6.7E	H. Krojalis	700	Dug	12	48	--	Pleistocene sand and gravel	--	do.	--	Dom	
Du 533	14Y, 15.0S, 8.5E	Ralph Gwinn	450	Drl	130	6	28	Stockbridge limestone	26	Turbine	40	Com	Temperature 54°F, June 1949.
Du 534	14Y, 15.6S, 7.2E	A. Pennell	530	Dug	22	48	--	Pleistocene sand and gravel	14	Suction	--	Farm	
Du 535	14Y, 11.4S, 7.8E	H. J. Kurris	460	Drl	130	6	--	Pleistocene deposit	--	Jet	--	Farm	
Du 536	14Y, 10.8S, 7.3E	George Dykeman	530	Dug	21	48	--	Pleistocene till	6	Suction	--	Dom	
Du 537	14Y, 9.0S, 7.3E	William Greimer	500	Dug	15	57	--	do.	10	do.	--	Farm	
Du 539	14Y, 5.7S, 1.3E	J. B. Walsh	540	Dug	29	48	--	do.	13	do.	--	Dom	Well used only in summer.
Du 540	14Y, 5.1S, 2.1E	A. Broome	750	Dug	34	53	34	Pleistocene sand	18	Hand	--	Dom	do.
Du 541	14Y, 3.9S, 1.6E	E. F. Acken	730	Drl	102	6	50	Hudson River formation	14	Jet	8	Farm	Yield 2 gpm when well was 75 ft deep.
Du 542	14Y, 1.8S, 0.8E	El Pancho	520	Drl	98	6	21	do.	18	do.	7	Com	Yield did not increase below depth of 83 ft.
Du 543	14Y, 3.1S, 0.7E	Paul Berger	720	Drl	293	6	12	do.	--	Force	30	Farm	
Du 545	14Y, 4.8S, 1.1E	W. R. Parlman	580	Drl	64	6	6	do.	4	Suction	8	Farm	
Du 546	15Y, 0.9S, 10.2W	Dutchess County Broadcasting Co.	1,305	Drl	185	6	0	Granite and gneiss, undiff.	--	--	5	Dom	
Du 547	14Y, 0.2S, 8.6E	Carl Sabo	400	Drl	184	6	--	Pleistocene deposit	--	None	7.5	Dom	Well abandoned; water contained clay.
Du 548	15Y, 11.7N, 1.4W	Dutchess Hatchery	330	Drl	115	6	16	Hudson River formation	--	--	11	Farm	Two other wells on property, 415 ft and 385 ft deep produced no water.
Du 549	13Y, 17.1S, 8.7E	F. Schern	400	Drl	155	6	110	Stockbridge limestone	38	Jet	40	Dom	
Du 550	14Y, 12.5S, 7.9E	Pauling Rubber Corp.	440	Drl	145	6	20	do.	4	do.	50	Ind	Drawdown 10 ft after pumping 50 gpm for 10 hrs. Temperature 51°F, June 1949. Average consumption is 30,000 gpd. (a).
Du 551	14Y, 11.9S, 0.7E	Peter O'Brien	360	Dug	10	36	10	Pleistocene gravel	9	Suction	14	Dom	Well supplies 5 families and small airport.
Du 552	14Y, 11.5S, 1.7E	Samuel Sottile	380	Drl	96	6	--	do.	--	Jet	40	Dom	Well flows; supplies restaurant and 15 families. (a) (b).

Table 13.--Records of selected wells in Dutchess County (Continued)

Well number	Location	Owner or occupant	Altitude above sea level (feet)	Type of well	Depth below land surface (feet)	Diameter (inches)	Depth to bedrock (feet)	Water-bearing formation	Water level below land surface (feet)	Method of lift	Yield (gallons per minute)	Use	Remarks
Du 553	14Y, 9.25, 0.2E	Samuel Sottile	480	Drl	271	6	8	Hudson River formation	18	Force	9	Dom	
Du 554	14Y, 10.85, 2.9E	Kendall Bros.	460	Drl	205	6	22	Stockbridge limestone	35	Jet	7	Farm	
Du 555	14Y, 10.95, 4.4E	Joseph B. Inness	580	Dug	16	36	16	Pleistocene till	6	Suction	--	Dom	
Du 556	14Y, 11.35, 4.7E	Albert Burdick	550	Drl	125	6	5	Granite and gneiss, undiff.	21	Force	25	Dom	Well supplies 3 families.
Du 557	14Y, 11.85, 5.3E	John Tartaro	820	Drl	50	6	13	do.	10	Suction	8	Dom	
Du 558	14Y, 11.85, 5.5E	do.	900	Drl	235	6	5	do.	12	Jet	6	Dom	Yield 2 - 3 gpm when well was 90 ft deep.
Du 559	14Y, 12.75, 7.1E	do.	500	Drl	125	6	10	Stockbridge limestone	5	Suction	20	Dom	
Du 560	14Y, 13.45, 0.7E	Bertha Van Anden	380	Drl	135	6	--	do.	10	Force	--	Farm	
Du 561	14Y, 14.55, 1.0E	A. Petersen	980	Dug	34	36	19	Pleistocene gravel	29	do.	--	Dom	
Du 562	14Y, 15.25, 1.4E	Camp Alamar, Inc.	660	Dug	37	36	27	Pleistocene sand	7	Suction	--	Dom	
Du 563	14Y, 15.45, 2.3E	C. Thornton	800	Dug	12	36	--	Pleistocene till	9	do.	--	Dom	
Du 564	14Y, 15.05, 4.3E	M. Pendley	920	Dug	29	48	--	do.	16	do.	--	Dom	
Du 566	14Y, 14.05, 3.4E	F. J. Clamp	920	Dug	14	54	12	do.	11	do.	--	Dom	
Du 567	15Y, 10.5N, 6.6W	George Wolf	140	Drl	65	6	40	Hudson River formation	--	Jet	9	Dom	Well flows at 3 gpm. (a).
Du 568	14Y, 12.65, 0.2E	Farm Supply Co.	340	Drl	226	6	56	Stockbridge limestone	15	Suction	45	Dom	
Du 570	14Y, 11.05, 7.4E	G. E. Stone	550	Drl	499	6	14	do.	42	Force	7	Farm	
Du 572	14Y, 13.45, 10.5E	H. Littell	950	Drl	406	6	12	Hudson River formation	42	do.	4	Dom	
Du 573	14Y, 13.05, 10.5E	J. R. Branch	960	Drl	307	6	12	do.	47	Turbine	5	Dom	
Du 574	14Y, 11.65, 10.8E	Anna Thomas	1,260	Drl	235	6	8	do.	19	Force	--	Dom	
Du 575	14Y, 10.35, 9.9E	Quaker Lake Inc.	810	Drl	153	6	17	do.	20	Jet	18	Dom	
Du 576	14Y, 12.05, 9.2E	T. E. Dewey	770	Drl	850	8	--	do.	--	Force	--	Farm	
Du 577	14Y, 1.05, 9.4E	Dutchess County Lime Co.	400	Drl	418	6	4	Stockbridge limestone	5	--	--	None	
Du 578	13Y, 16.75, 8.9E	Charles Webster	470	Drl	55	6	39	do.	19	Jet	12	Dom	
Du 580	14Y, 4.65, 8.4E	Fairview Manor	450	Drl	160	6	11	do.	--	do.	30	Com	(a).
Du 582	14Y, 3.85, 8.3E	John Hauff	410	Drl	100	6	3	Unknown	22	--	8	Dom	(a).
Du 583	15Y, 3.0N, 8.0W	Fishkill Rural Cemetery	240	Drl	126	6	8	Stockbridge limestone	9	Centrifugal	10	Dom	(a).
Du 584	14Y, 3.15, 3.6E	E. Dunlavey	690	Dug	14	36	--	Pleistocene till	11	Suction	--	Dom	
Du 585	14Y, 2.65, 3.1E	Claude Abel	730	Drl	94	6	30	Hudson River formation	18	Jet	25+	Farm	Two other wells and several other springs also on property.
Du 586	14Y, 2.05, 1.8E	William Adel	590	Drl	100	6	10	do.	20	do.	--	Dom	
Du 587	14Y, 7.75, 1.1E	A. B. Hughes	740	Drl	450	6	18	do.	--	Force	--	Dom	
Du 588	14Y, 8.35, 0.6E	W. J. Crocker	680	Drl	250	6	10	do.	--	Jet	60	Farm	Well supplies two homes.
Du 589	14Y, 7.15, 5.8E	A. B. Hamal	1,220	Drl	159	6	20	do.	--	Force	3	Dom	

10.5

Reference 11

TELEPHONE CONVERSATION MEMORANDUM

CLIENT NYSDEC PROJ. No. 06281
PROJECT _____ DATE 10/30/86
TIME 1:20 P.M.
CALL TO/FROM Laura Zaines REPRESENTING Dutchess County Soil
and Water Conservation
District
PHONE No. (914) 677-8011

SUMMARY OF CONVERSATION:

Laura Zaines representing the Dutchess County Soil and Water Conservation knows of no such irrigation practices being done within a three mile radius of the NYSDOT spill.

COPIES TO: _____

BY: S. Petrisko
S. Petrisko

WE WEHRAN ENGINEERING
CONSULTING ENGINEERS

EPA FORMS 2070-12 AND 2070-13



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY 314060

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) NYSDOT Spill No. 811902		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER Route 22			
03 CITY Pawling	04 STATE NY	05 ZIP CODE 12564	06 COUNTY Dutchess	07 COUNTY CODE	08 CON- DIST
09 COORDINATES LATITUDE -----		LONGITUDE -----			

10 DIRECTIONS TO SITE (Starting from nearest public road)

Take Route 22 north Brady Brook, south of Akindale Road to Corrol Ford (off Route 22)

III. RESPONSIBLE PARTIES

01 OWNER (If known) Cole Petroleum		02 STREET (Business, mailing, residential) Route 22			
03 CITY Pawling	04 STATE NY	05 ZIP CODE 12564	06 TELEPHONE NUMBER ()		
07 OPERATOR (If known and different from owner) -----		08 STREET (Business, mailing, residential) -----			
09 CITY -----	10 STATE -----	11 ZIP CODE -----	12 TELEPHONE NUMBER ()		
13 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL: _____ (Agency name) <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER: _____ (Specify) <input type="checkbox"/> G. UNKNOWN					

14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply)

☐ A. RCRA 3001 DATE RECEIVED: ____/____/____ MONTH DAY YEAR ☐ B. UNCONTROLLED WASTE SITE (CERCLA 102 (c)) DATE RECEIVED: ____/____/____ MONTH DAY YEAR ☐ C. NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON SITE INSPECTION <input checked="" type="checkbox"/> YES DATE <u>1, 8, 86</u> MONTH DAY YEAR <input type="checkbox"/> NO		BY (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input type="checkbox"/> C. STATE <input checked="" type="checkbox"/> D. OTHER CONTRACTOR <input type="checkbox"/> E. LOCAL HEALTH OFFICIAL <input type="checkbox"/> F. OTHER: _____ (Specify) CONTRACTOR NAME(S): <u>Wehran Engineering</u>			
02 SITE STATUS (Check one) <input checked="" type="checkbox"/> A. ACTIVE <input type="checkbox"/> B. INACTIVE <input type="checkbox"/> C. UNKNOWN		03 YEARS OF OPERATION BEGINNING YEAR _____ ENDING YEAR _____ <input checked="" type="checkbox"/> UNKNOWN			
04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED Gasoline Components; Benzene O-Xylene Toluene Ethyl benzene M-Xylene Tetrachloroethylene					

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION

Chemicals present in water supply wells.

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Constituents and Monitoring)
☒ A. HIGH (Inspection required promptly) ☐ B. MEDIUM (Inspection required) ☐ C. LOW (Inspection on time available basis) ☐ D. NONE (No further action needed, immediate cleanup unnecessary)

VI. INFORMATION AVAILABLE FROM

01 CONTACT Dennis G. Fenn	02 OF (Agency/Organization) Wehran Engineering	03 TELEPHONE NUMBER (914) 343-0660
04 PERSON RESPONSIBLE FOR ASSESSMENT Stephen R. Petrisko	05 AGENCY Wehran Engineering	06 ORGANIZATION Wehran Engineering
		07 TELEPHONE NUMBER (914) 343-0660
		08 DATE 11 / 5 / 86 MONTH DAY YEAR



☒ I. HIGHLY VOLATILE
☐ J. EXPLOSIVE
☐ K. REACTIVE
☐ L. INCOMPATIBLE
☐ M. NOT APPLICABLE

EPA FORM 2070-12 (7-81)



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

L IDENTIFICATION
01 STATE 02 SITE NUMBER
NY 314060

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☒ OBSERVED (DATE: 6/24/83) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Observed groundwater contamination determined from laboratory analysis of samples obtained from monitoring wells installed on-site.

01 ☐ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Potential surface water contamination due to gasoline spill, and nearest surface water approximately 1,000 feet from site.

01 ☐ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☒ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Potential fire/explosive conditions exist due to gasoline spill.

01 ☒ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Possible direct contact due to gasoline contaminated drinking wells.

01 ☒ F. CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Potential soil contamination due to gasoline spill, and observed groundwater contamination.

01 ☒ G. DRINKING WATER CONTAMINATION 02 ☒ OBSERVED (DATE: 3/22/82) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Private drinking water wells contaminated with gasoline

01 ☐ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☒ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Possible population exposure/injury via direct contact route due to gasoline contaminated drinking wells.



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

L IDENTIFICATION
01 STATE 02 SITE NUMBER
NY 314060

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

Unknown

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include number of species)

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

Unknown

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

Unknown

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES
(Restrained/leaking underground storage tanks)

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: _____

04 NARRATIVE DESCRIPTION

No method of containment of wastes has been observed or documented.

01 ☒ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

Unknown

01 ☒ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

Unknown

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

V. SOURCES OF INFORMATION (City records, references, e.g., state files, aerial photos, reports)

NYSDEC Inactive Hazardous Waste Disposal Site Report
Hydrogeologic evaluations oil spill Village of Pawling Dutchess County, NY



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION
01 STATE NY 02 SITE NUMBER 314060

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) NYSDOT Spill No. 811902		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER Route 22			
03 CITY Pawling	04 STATE NY	05 ZIP CODE 12564	06 COUNTY Dutchess	07 COUNTY CODE	08 CONG DIST
09 COORDINATES LATITUDE 41° 32' 08" N LONGITUDE 73° 35' 08" W		10 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER <input type="checkbox"/> G. UNKNOWN			

III. INSPECTION INFORMATION

01 DATE OF INSPECTION 1 / 8 / 86 MONTH DAY YEAR	02 SITE STATUS <input checked="" type="checkbox"/> ACTIVE <input type="checkbox"/> INACTIVE	03 YEARS OF OPERATION 1 BEGINNING YEAR ENDING YEAR <input checked="" type="checkbox"/> UNKNOWN
04 AGENCY PERFORMING INSPECTION (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input type="checkbox"/> C. MUNICIPAL <input type="checkbox"/> D. MUNICIPAL CONTRACTOR <input type="checkbox"/> E. STATE <input checked="" type="checkbox"/> F. STATE CONTRACTOR <u>Wehran Engineering</u> <input type="checkbox"/> G. OTHER		

05 CHIEF INSPECTOR David B. Tompkins	06 TITLE Environmental Scientist	07 ORGANIZATION Wehran	08 TELEPHONE NO. (914) 343-0660
09 OTHER INSPECTORS Stephen R. Petrisko	10 TITLE Environmental Technician	11 ORGANIZATION Wehran	12 TELEPHONE NO. (914) 343-0660
			()
			()
			()
			()

13 SITE REPRESENTATIVES INTERVIEWED Mr. Jay Maxwell, Sr.	14 TITLE Resident	15 ADDRESS Rt. 22, Pawling, NY	16 TELEPHONE NO. ()
Mr. Jay Maxwell, Jr.	Resident	Rt. 22, Pawling, NY	()
			()
			()
			()
			()

17 ACCESS GAINED BY <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT	18 TIME OF INSPECTION 1:00 p.m.	19 WEATHER CONDITIONS 20°, Clear, Cold
---	------------------------------------	---

IV. INFORMATION AVAILABLE FROM

01 CONTACT Dennis G. Fenn	02 OF (Agency/Organization) Wehran Engineering	03 TELEPHONE NO. (914) 343-0660		
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM Stephen R. Petrisko	05 AGENCY	06 ORGANIZATION Wehran	07 TELEPHONE NO. (914) 343-0660	08 DATE 11 / 5 / 86 MONTH DAY YEAR



☒ I. HIGHLY VOLATILE
☐ J. EXPLOSIVE
☐ K. REACTIVE
☐ L. INCOMPATIBLE
☐ M. NOT APPLICABLE

EPA FORM 2070-13(7-81)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION
01 STATE: NY 02 SITE NUMBER: 314060

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☒ OBSERVED (DATE: 6/24/83) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION
Observed groundwater contamination determined from laboratory analysis of samples obtained from monitoring wells installed on-site.

01 ☐ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE:) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION
Potential surface water contamination due to gasoline spill.
Nearest surface water approximately 1,000 feet from site.

01 ☐ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE:) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION

01 ☒ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE:) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION
Potential fire/explosive conditions exist due to gasoline spill.

01 ☒ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE:) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION
Possible direct contact due to gasoline contaminated drinking wells.

01 ☒ F. CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE:) ☒ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION
Potential soil contamination due to gasoline spill.

01 ☒ G. DRINKING WATER CONTAMINATION 02 ☒ OBSERVED (DATE: 3/22/82) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION
Private drinking water wells contaminated with gasoline

01 ☐ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE:) ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION

01 ☒ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE:) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION
Possible population exposure/injury via direct contact route due to gasoline contaminated drinking wells.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION	
01 STATE	02 SITE NUMBER
NY	314060

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

Unknown

01 ☐ K. DAMAGE TO FAUNA 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION (Include methods of abatement)

Unknown

01 ☐ L. CONTAMINATION OF FOOD CHAIN 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

Unknown

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
(Spill/Leak/Standing Water, Leaking Drums)
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

No method of containment of wastes has been observed or documented.

01 ☐ N. DAMAGE TO OFFSITE PROPERTY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

Unknown

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

Unknown

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, company records, reports)

NYSDEC Inactive Hazardous Waste Disposal Site Report
Hydrogeologic Evaluations Oil Spill Village of Pawling, Dutchess County, NY



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION
01 STATE NY 02 SITE NUMBER 314060

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A. NPDES				
<input type="checkbox"/> B. UIC				
<input type="checkbox"/> C. AIR				
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input type="checkbox"/> F. SPCC PLAN				
<input type="checkbox"/> G. STATE (Specify)				
<input type="checkbox"/> H. LOCAL (Specify)				
<input type="checkbox"/> I. OTHER (Specify)				
<input type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE/DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input type="checkbox"/> A. SURFACE IMPONEMENT <input type="checkbox"/> B. PILES <input type="checkbox"/> C. DRUMS, ABOVE GROUND <input type="checkbox"/> D. TANK, ABOVE GROUND <input checked="" type="checkbox"/> E. TANK, BELOW GROUND <input type="checkbox"/> F. LANDFILL <input type="checkbox"/> G. LANDFARM <input type="checkbox"/> H. OPEN DUMP <input type="checkbox"/> I. OTHER (Specify)			<input type="checkbox"/> A. INCINERATION <input type="checkbox"/> B. UNDERGROUND INJECTION <input type="checkbox"/> C. CHEMICAL/PHYSICAL <input type="checkbox"/> D. BIOLOGICAL <input type="checkbox"/> E. WASTE OIL PROCESSING <input type="checkbox"/> F. SOLVENT RECOVERY <input type="checkbox"/> G. OTHER RECYCLING/RECOVERY <input type="checkbox"/> H. OTHER (Specify)	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE 06 AREA OF SITE 20 (Acres)

07 COMMENTS

Gasoline contaminated drinking wells located in a commercial area along Route 22 in Pawling, NY

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one)
☐ A. ADEQUATE, SECURE ☐ B. MODERATE ☐ C. INADEQUATE, POOR ☒ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.

No method of containment of wastes has been observed or documented.

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: ☒ YES ☐ NO
02 COMMENTS

Private drinking water wells contaminated with gasoline.

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, agency reports, records)

NYSDEC Inactive Hazardous Waste Disposal Site Report
Hydrogeologic Evaluations, Oil Spill, Village of Pawling by
Empire Soils Investigations, Inc. and Thomsen Associates



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 03 SITE NUMBER
NY 314060

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY (Check all applicable)	02 STATUS	03 DISTANCE TO SITE															
<table border="0"><tr><td>SURFACE</td><td>WELL</td></tr><tr><td>COMMUNITY A <input type="checkbox"/></td><td>B <input type="checkbox"/></td></tr><tr><td>NON-COMMUNITY C <input type="checkbox"/></td><td>D <input checked="" type="checkbox"/></td></tr></table>	SURFACE	WELL	COMMUNITY A <input type="checkbox"/>	B <input type="checkbox"/>	NON-COMMUNITY C <input type="checkbox"/>	D <input checked="" type="checkbox"/>	<table border="0"><tr><td>ENDANGERED</td><td>AFFECTED</td><td>MONITORED</td></tr><tr><td>A <input type="checkbox"/></td><td>B <input type="checkbox"/></td><td>C <input type="checkbox"/></td></tr><tr><td>D <input type="checkbox"/></td><td>E <input checked="" type="checkbox"/></td><td>F <input checked="" type="checkbox"/></td></tr></table>	ENDANGERED	AFFECTED	MONITORED	A <input type="checkbox"/>	B <input type="checkbox"/>	C <input type="checkbox"/>	D <input type="checkbox"/>	E <input checked="" type="checkbox"/>	F <input checked="" type="checkbox"/>	A. On-site (mi) B. (mi)
SURFACE	WELL																
COMMUNITY A <input type="checkbox"/>	B <input type="checkbox"/>																
NON-COMMUNITY C <input type="checkbox"/>	D <input checked="" type="checkbox"/>																
ENDANGERED	AFFECTED	MONITORED															
A <input type="checkbox"/>	B <input type="checkbox"/>	C <input type="checkbox"/>															
D <input type="checkbox"/>	E <input checked="" type="checkbox"/>	F <input checked="" type="checkbox"/>															

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)

☒ A. ONLY SOURCE FOR DRINKING ☐ B. DRINKING
(Other sources available)
COMMERCIAL, INDUSTRIAL, IRRIGATION
(No other water sources available)
☐ C. COMMERCIAL, INDUSTRIAL, IRRIGATION
(Limited other sources available)
☐ D. NOT USED, UNUSABLE

02 POPULATION SERVED BY GROUND WATER	03 DISTANCE TO NEAREST DRINKING WATER WELL			
2,915	on-site (mi)			
04 DEPTH TO GROUNDWATER	05 DIRECTION OF GROUNDWATER FLOW	06 DEPTH TO AQUIFER OF CONCERN	07 POTENTIAL YIELD OF AQUIFER	08 SOLE SOURCE AQUIFER
10-19 (ft)	Southward to Southwestward	(ft)	(gpd)	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO

09 DESCRIPTION OF WELLS (including casing, depth, and location relative to population and buildings)

19 monitoring wells installed on-site. Depths range from 11 feet to 38 feet.

10 RECHARGE AREA	11 DISCHARGE AREA
<input type="checkbox"/> YES <input type="checkbox"/> NO COMMENTS	<input type="checkbox"/> YES <input type="checkbox"/> NO COMMENTS

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)

☒ A. RESERVOIR, RECREATION DRINKING WATER SOURCE ☐ B. IRRIGATION, ECONOMICALLY IMPORTANT RESOURCES ☐ C. COMMERCIAL, INDUSTRIAL ☐ D. NOT CURRENTLY USED

02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME	AFFECTED	DISTANCE TO SITE
Brady Brook	<input type="checkbox"/>	1,000 ft. (mi)
	<input type="checkbox"/>	(mi)
	<input type="checkbox"/>	(mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN	02 DISTANCE TO NEAREST POPULATION									
<table border="0"><tr><td>ONE (1) MILE OF SITE</td><td>TWO (2) MILES OF SITE</td><td>THREE (3) MILES OF SITE</td></tr><tr><td>A. 403</td><td>B. 1,596</td><td>C. 2,915</td></tr><tr><td>NO. OF PERSONS</td><td>NO. OF PERSONS</td><td>NO. OF PERSONS</td></tr></table>	ONE (1) MILE OF SITE	TWO (2) MILES OF SITE	THREE (3) MILES OF SITE	A. 403	B. 1,596	C. 2,915	NO. OF PERSONS	NO. OF PERSONS	NO. OF PERSONS	1/4 (mi)
ONE (1) MILE OF SITE	TWO (2) MILES OF SITE	THREE (3) MILES OF SITE								
A. 403	B. 1,596	C. 2,915								
NO. OF PERSONS	NO. OF PERSONS	NO. OF PERSONS								
03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE	04 DISTANCE TO NEAREST OFF-SITE BUILDING									
227	1/8 (mi)									

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g., rural, village, densely populated urban area)

The area is predominantly commercial with few homes scattered throughout the area. There are private homes within 1,000 feet of the site.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY 314060

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A. $10^{-6} - 10^{-8}$ cm/sec ☐ B. $10^{-4} - 10^{-6}$ cm/sec ☐ C. $10^{-2} - 10^{-3}$ cm/sec ☒ D. GREATER THAN 10^{-2} cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☐ A. IMPERMEABLE
(Less than 10^{-6} cm/sec)
☐ B. RELATIVELY IMPERMEABLE
($10^{-6} - 10^{-8}$ cm/sec)
☒ C. RELATIVELY PERMEABLE
($10^{-2} - 10^{-4}$ cm/sec)
☐ D. VERY PERMEABLE
(Greater than 10^{-2} cm/sec)

03 DEPTH TO BEDROCK

15-30
(ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

Unknown
(ft)

05 SOIL pH

Unknown

06 NET PRECIPITATION

16
(in)

07 ONE YEAR 24 HOUR RAINFALL

2.5
(in)

08 SLOPE
SITE SLOPE
up to 10 %

DIRECTION OF SITE SLOPE
Southwest

TERRAIN AVERAGE SLOPE
5-6 %

09 FLOOD POTENTIAL

SITE IS IN 100 YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (if none estimate)

ESTUARINE

OTHER

A. _____ (mi)

B. > 1 _____ (mi)

12 DISTANCE TO CRITICAL HABITAT (if none estimate)

N/A _____ (mi)

ENDANGERED SPECIES: _____

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS: NATIONAL/STATE PARKS,
FORESTS, OR WILDLIFE RESERVES

AGRICULTURAL LANDS
PRIME AG LAND AG LAND

A. on-site _____ (mi)

B. _____ (mi)

C. _____ (mi) D. _____ (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

The site is situated in the valley of the East Branch of the Croton River. Elevations on the valley floor in the area range from approximately 430 to 450 feet above mean sea level. Uplands marginal to the valley form scarps rising rapidly to elevations of 850 feet or more above mean sea level.

VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, company studies, reports)

Hydrogeologic Evaluations by Empire Soils Investigations, Inc. and Thomsen Associates.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NY 314060

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER	N.A.	Camo Laboratories; Galson Technical	available
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL			
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input checked="" type="checkbox"/> GROUND <input type="checkbox"/> AERIAL	02 IN CUSTODY OF <u>Wehran Engineering</u> <small>(Name of organization or individual)</small>
03 MAPS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS <u>Wehran Engineering</u>

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, agency analyses, reports)

Hydrogeologic Evaluations by Empire Soils Investigations, Inc.
and Thomsen Associates.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NY 314060

II. CURRENT OWNER(S)				PARENT COMPANY (If applicable)			
01 NAME Maxwell Engine Rebuilders		02 D+S NUMBER		08 NAME		09 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, APO #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME Corral Ford		02 D+S NUMBER		08 NAME		09 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, APO #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME Heinchon Dairy		02 D+S NUMBER		08 NAME		09 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, APO #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME Mario's Pizza		02 D+S NUMBER		08 NAME		09 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, APO #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
III. PREVIOUS OWNER(S) (Last owner present first)				IV. REALTY OWNER(S) (If applicable; see above present first)			
01 NAME		02 D+S NUMBER		01 NAME		02 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+S NUMBER		01 NAME		02 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+S NUMBER		01 NAME		02 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, aerial photos, reports)							
NYSDEC Region 3 File Documents							



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NY 314060

II. CURRENT OPERATOR (Provide if different from owner)

OPERATOR'S PARENT COMPANY (if applicable)

01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, APO #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER					

III. PREVIOUS OPERATOR(S) (List most recent first; provide only if different from owner)

PREVIOUS OPERATORS' PARENT COMPANIES (if applicable)

01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, APO #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, APO #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD /					

01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, APO #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, APO #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

IV. SOURCES OF INFORMATION (Give specific references, e.g., state files, company records, reports)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NY 314060

II. ON-SITE GENERATOR

01 NAME	02 D+S NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	
05 CITY	06 STATE 07 ZIP CODE	

III. OFF-SITE GENERATOR(S)

01 NAME	02 D+S NUMBER	01 NAME	02 D+S NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+S NUMBER	01 NAME	02 D+S NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

IV. TRANSPORTER(S)

01 NAME	02 D+S NUMBER	01 NAME	02 D+S NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+S NUMBER	01 NAME	02 D+S NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

V. SOURCES OF INFORMATION (List specific references, e.g., MSDS files, company records, reports)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10- PAST RESPONSE ACTIVITIES

L IDENTIFICATION

01 STATE 02 SITE NUMBER
NY 314060

I. PAST RESPONSE ACTIVITIES

01 ☐ A. WATER SUPPLY CLOSED

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ B. TEMPORARY WATER SUPPLY PROVIDED

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ C. PERMANENT WATER SUPPLY PROVIDED

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ D. SPILLED MATERIAL REMOVED

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ E. CONTAMINATED SOIL REMOVED

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ F. WASTE REPACKAGED

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ G. WASTE DISPOSED ELSEWHERE

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ H. ON SITE BURIAL

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ I. IN SITU CHEMICAL TREATMENT

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ J. IN SITU BIOLOGICAL TREATMENT

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ K. IN SITU PHYSICAL TREATMENT

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ L. ENCAPSULATION

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ M. EMERGENCY WASTE TREATMENT

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ N. CUTOFF WALLS

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ O. EMERGENCY DIXING/SURFACE WATER DIVERSION

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ P. CUTOFF TRENCHES/SUMP

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown

01 ☐ Q. SUBSURFACE CUTOFF WALL

02 DATE _____

03 AGENCY _____

04 DESCRIPTION

Unknown



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

L IDENTIFICATION
01 STATE 02 SITE NUMBER
NY 314060

II PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Unknown

01 ☐ S. CAPPING/COVERING
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Unknown

01 ☐ T. BULK TANKAGE REPAIRED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Unknown

01 ☐ U. GROUT CURTAIN CONSTRUCTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Unknown

01 ☐ V. BOTTOM SEALED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Unknown

01 ☐ W. GAS CONTROL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Unknown

01 ☐ X. FIRE CONTROL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Unknown

01 ☐ Y. LEACHATE TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Unknown

01 ☐ Z. AREA EVACUATED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Unknown

01 ☐ 1. ACCESS TO SITE RESTRICTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Unknown

01 ☐ 2. POPULATION RELOCATED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Unknown

01 ☐ 3. OTHER REMEDIAL ACTIVITIES
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

Unknown

III SOURCES OF INFORMATION (Cite specific references, e.g., MSDS files, written analyses, reports)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01. STATE	02. SITE NUMBER
NY	314060

II. ENFORCEMENT INFORMATION

01. PAST REGULATORY/ENFORCEMENT ACTION ☐ YES ☒ NO

02. DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, reports, studies, records)

**6.0 ASSESSMENT OF DATA ADEQUACY
AND RECOMMENDATIONS**

6.0 ASSESSMENT OF DATA ADEQUACY AND RECOMMENDATIONS

6.1 GROUNDWATER ROUTE

With quantitative evidence available to confirm a direct release to groundwater, a complete Phase II investigation is not recommended at this time.

A preliminary score of $S_{gw} = 65.62$ was computed from information in the Federal and State files and the site inspection.

6.2 SURFACE WATER ROUTE

The preliminary surface water route score is 7.44. Brady Brook is located approximately within 1,000 feet of the site. No documentation of any release to this surface water has been obtained. In order to verify the threat of potential surface water contamination, a one-time sampling event is recommended to determine if migration of contaminants to the stream has occurred.

6.3 AIR ROUTE

No measurable readings of organic vapors were detected with the HNU Photoionizer during the site inspection. To score an air release, qualitative sampling is required along with details on the sampling protocol and the meteorological conditions during the sampling event.

6.4 FIRE AND EXPLOSION

To score the fire and explosion hazard mode either a state or local fire marshall must have certified that the facility presents a significant fire or explosion threat to the public or to a sensitive environment, or there must be a demonstrated threat based on field observations (e.g., combustible gas indicator readings). The available records give no indication that either one of these tasks has been done.

6.5 DIRECT CONTACT

The direct contact route score (S_{DC}) for this site is 12.50. There are no incidents due to direct contact; however, migration of contamination off site is suspect and of concern.

6.6 RECOMMENDATIONS

Due to the existing data documenting a release to the groundwater route, a Phase II investigation is not warranted at the NYSDOT Spill No. 811902 site. Therefore, the site is recommended for consideration by the NYSDEC Bureau of Remedial Action for an appropriate remedial program.

APPENDIX

RECEIVED
DUTCHESS CO. HEALTH DEPT.

'85 SEP 11 AM 11:44

September 9, 1985

Corral Ford
Route 22
Pawling, NY 12564
Attn: Robert Carpenter

Re: Spill No. 811902, PIN SP 1633.701
Pawling, Dutchess County

Dear Mr. Carpenter:

Attached find the chemical analysis (Gasoline Components in Water) of one water sample taken before a previously installed charcoal filter at your location on August 13, 1985.

The analysis indicates that your well water is free of gasoline contamination at this time. For questions regarding the interpretation of this report, contact the Dutchess County Health Department for assistance.

Based on the laboratory results for the last several months, this office will cease any further active involvement in this portion of the project.

The charcoal filters are scheduled to be removed at the end of September, 1985. If you choose to maintain the filters yourself, contact Culligan Water Conditioning at (914) 454-4010 to make the necessary arrangements.

Should you have any questions concerning this matter, contact this office at (914) 431-5771.

Very truly yours,

James D. Bailey
Regional Oil Spill Engineer

by:


John Schaff
Assistant Oil Spill Engineer

JDB/JS/lb
Attachment

cc: M. Clarke, Oil Spill Bureau, Albany, 5/216
C. Manfredi, NYSDEC—Region 3, White Plains

COUNTY OF WESTCHESTER
DEPARTMENT OF LABORATORIES AND RESEARCH
VALHALLA, NEW YORK 10595

RESULTS OF ANALYSES - GASOLINE COMPONENTS (DOH 310-19)

Lab No. 3439
Date Rec'd 8/14/85

Bottle No. _____
Date Coll'd 8/13/85
Time: 1-55 pm

Agency Coll'd for NYS DCT Coll'd by M. Wetzel
Collected From: Name Corral Ford
(Last) (First)

Address Pawling N.Y. Dutch
(St. Rd.) (Town Village City) (Zip Code) (County)

Sampling Point _____ Identification of Source Spill # 811902

Gasoline Criteria according to New York State Department of Transportation. Test Procedure for Gasoline Components in Water (Purgeable Aromatics) (DOH Procedures 310-19): PIN: SP1633-70

1. The following compounds must be present:

Compounds	ug/L
Benzene	<u>3.2</u>
Toluene	<u><1</u>
Ethylbenzene	<u><1</u>
m-xylene	<u><1</u>
p-xylene	<u><1</u>
o-xylene	<u><1</u>

2. The xylene isomers must be approximately the same concentration (within a factor of 2).

3. Presence of additional peaks in the chromatogram with the following retention times (Benzene = 1.0 minutes)
*Major peaks - must be present.

Method R. T.'s (min.)	Actual R. T.'s (min.)
3.9	<u>—</u>
4.25*	<u>—</u>
4.5*	<u>—</u>
4.7*	<u>—</u>
5.1*	<u>—</u>
5.6	<u>—</u>
5.9	<u>—</u>

- ☐ Gasoline Criteria Met
☒ Gasoline Criteria Not Met
☐ Unknown Compound present

Reported By K. St. Date Reported 8/20/85

cc: T. Plesnarski, Spill Response Section, Rm. 326 (cover letter only)

STATE
OF
NEW YORK

STANDARD VOUCHER

1633
55306

Originating Agency

NYS Dept. Enviro Conservation

Orig. Agency Code

0900

P-Contract

Payment Date (MM) (DD) (YY)

10/10/86

OSC Use Only

Liability Date (MM) (DD) (YY)

08/01/86

3 Payee ID

14-1464023

Additional

Zip Code

Route

Payee Amount

105.00

4 Payee Name (Limit to 30 spaces)

Culligan Dutchess-Putnam

1099 Code

5

Payee Name (Limit to 30 spaces)

Water Conditioning Inc.

Statistic Type

Statistic

09/10/86

Address (Limit to 30 spaces)

39 Friendly Lane

6 Ref/Inv. No. (Limit to 20 spaces)

Address (Limit to 30 spaces)

Ref/Inv. Date (MM) (DD) (YY)

08/25/86

City (Limit to 20 spaces)

(Limit to 2 spaces)

State

Zip Code

Poughkeepsie

NY

12603

7 Purchase
Order No.
and Date

Description of Material/Service
If items are too numerous to be incorporated into the block below,
use form AC 93 and carry total forward.

Quantity

Unit

Price

Amount

2 Guy-Patterson- ~~SECRET~~

August-Oct rental of 2 M oil tanks 035.00

105 00

RECEIVED

SEP 10 1986

RECEIVED

SEP 8 1986

NYSDEC

WHITE PLAINS

8 Payee Certification:

I certify that the above bill is just, true and correct; that no part thereof has been paid except as stated and that the balance is actually due and owing, and that taxes from which the State is exempt are excluded.

Total

105 00

Discount

%

Net

105.00

Payee's Signature in Ink

0-4-86

Date

Name of Company

FOR AGENCY USE ONLY

STATE COMPTROLLER'S PRE-AUDIT

Merchandise Received

I certify that this voucher is correct and just, and payment is approved.

Certified For Payment
of
Net Amount

Date

Verified

Audited

Special Approval
(as required)

By

Page No.

By

Date

Title

Expenditure

Liquidation

Dept.

Cost Center

Var

Yr

Object

Accum

Amount

Orig Agency

PO/Contract

Line

F/F

90163379 - 46 55950

105 00

☐ Check if Continuation
form is attached.

OSC

RECEIVED

DEC 19 1986

RECEIVED
DUTCHESS COUNTY
HEALTH DEPT

'85 SEP 11 AM 11:44

BUREAU OF HAZARDOUS SITE CONTROL
DIVISION OF SOLID AND
HAZARDOUS WASTE

September 9, 1985

Marios Pizza
Route 22
Pawling, NY 12564

Re: Spill No. 311920, PIR SP 1633.701
Pawling, Dutchess County

Dear Sir:

Attached find the chemical analysis (Gasoline Components in Water) of one water sample taken before a previously installed charcoal filter at your location on August 13, 1985.

The analysis indicates that your well water is free of gasoline contamination at this time. For questions regarding the interpretation of this report, contact the Dutchess County Health Department for assistance.

Based on the laboratory results for the last several months, this office will cease any further active involvement in this portion of the project.

The charcoal filters are scheduled to be removed at the end of September, 1985. If you choose to maintain the filters yourself, contact Culligan Water Conditioning at (914) 454-4010 to make the necessary arrangements.

Should you have any questions concerning this matter, contact this office at (914) 431-5771.

Very truly yours,

James D. Bailey
Regional Oil Spill Engineer

by:

John Schaff
John Schaff
Assistant Oil Spill Engineer

JDB/JS/ls
Attachment

cc: M. Clarke, Oil Spill Bureau, Albany, 5/216
C. Manfredi, NYSDEC--Region 3, White Plains
E. Marx, Dutchess County Health Department

COUNTY OF WESTCHESTER
DEPARTMENT OF LABORATORIES AND RESEARCH
VALHALLA, NEW YORK 10595

RESULTS OF ANALYSES - GASOLINE COMPONENTS (DOH 310-19)

Lab No. 3438
Date Rec'd 8/14/85

Bottle No. _____
Date Coll'd 8/13/85
Time: 1-40 Pm

Agency Coll'd for NYS DCT coll'd by M. Wetzel
Collected From: Name Marrio's Pizza
(Last) (First)

Address Pawling, NY. Dutch.
(St. Rd.) (Town Village City) (Zip Code) (County)

Sampling Point _____ Identification of Source Sp. U # 311902
PIN: SP1633701

Gasoline Criteria according to New York State Department of
Transportation. Test Procedure for Gasoline Components in
Water (Purgeable Aromatics) (DOH Procedures 310-19):

1. The following compounds must be present:

Compounds	ug/L
Benzene	<u><1</u>
Toluene	<u><1</u>
Ethylbenzene	<u><1</u>
m-xylene	<u><1</u>
p-xylene	<u><1</u>
o-xylene	<u><1</u>

2. The xylene isomers must be approximately the same concentration
(within a factor of 2).
3. Presence of additional peaks in the chromatogram with the
following retention times (Benzene = 1.0 minutes)
*Major peaks - must be present.

Method R. T.'s (min.)	Actual R. T.'s (min.)
3.9	<u> </u>
4.25*	<u> </u>
4.5*	<u> </u>
4.7*	<u> </u>
5.1*	<u> </u>
5.6	<u> </u>
5.9	<u> </u>

- ☐ Gasoline Criteria Met _____
- ☒ Gasoline Criteria Not Met _____
- ☐ Unknown Compound present

RECEIVED
DUTCHESS COUNTY
HEALTH DEPT

85 SEP 11 AM 11:44

September 9, 1985

Mr. and Mrs. Kent Johnson
Heinchon Dairy
Box 327
Pawling, NY 12564

Re: Spill No. 811920, PIN SP 1633.701
Pawling, Dutchess County

Dear Mr. and Mrs. Johnson:

Attached find the chemical analysis (Gasoline Components in Water) of one water sample taken before a previously installed charcoal filter at your location on August 13, 1985.

The analysis indicates that your well water is free of gasoline contamination at this time. For questions regarding the interpretation of this report, contact the Dutchess County Health Department for assistance.


Based on the laboratory results for the last several months, this office will cease any further active involvement in this portion of the project.

Should you have any questions concerning this matter, contact this office at (914) 431-5771.

Very truly yours,

James D. Bailey
Regional Oil Spill Engineer

by:



John Schaff
Assistant Oil Spill Engineer

JDB/JS/ljs

Attachment

cc: M. Clarke, Oil Spill Bureau—Albany, 5/216
C. Manfredi, NYSDEC—Region 3, White Plains
E. Marx, Dutchess County Health Department

COUNTY OF WESTCHESTER
DEPARTMENT OF LABORATORIES AND RESEARCH
VALHALLA, NEW YORK 10595

RESULTS OF ANALYSES - GASOLINE COMPONENTS (DOH 310-19)

Lab No. 3440

Date Rec'd 8/14/85

Bottle No. _____

Date Coll'd 8/13/85

Time: 1-25 pm

Agency Coll'd for NYS DOT Coll'd By M. Wetzel

Collected From: Name HEINCHON Dairy
(Last) (First)

Address Pawling, N.Y. Dutch.
(St. Rd.) (Town Village City) (Zip Code) (County)

Sampling Point _____ Identification of Source spill # 811902
PIN: SPI633-70

Gasoline Criteria according to New York State Department of Transportation. Test Procedure for Gasoline Components in Water (Purgeable Aromatics) (DOH Procedures 310-19):

1. The following compounds must be present:

Compounds	ug/L
Benzene	<u>23</u>
Toluene	<u><1</u>
Ethylbenzene	<u><1</u>
m-xylene	<u><1</u>
p-xylene	<u><1</u>
o-xylene	<u><1</u>

2. The xylene isomers must be approximately the same concentration (within a factor of 2).

3. Presence of additional peaks in the chromatogram with the following retention times (Benzene = 1.0 minutes)

*Major peaks - must be present.

Method R. T.'s (min.)	Actual R. T.'s (min.)
3.9	<u>—</u>
4.25*	<u>—</u>
4.5*	<u>—</u>
4.7*	<u>—</u>
5.1*	<u>—</u>
5.6	<u>—</u>
5.9	<u>—</u>

☐ Gasoline Criteria Met _____

☒ Gasoline Criteria Not Met _____

☐ Unknown Compound present

Reported By K. Jz

Date Reported 8/20/85

NYS DOT Spill Site
#314060.

		22 NOV 1983	29 FEB 1984	26 APRIL 1984	6 JULY 1984	23 JAN 1985	13 AUG 1985
MAXWELL	Benzene	1500	1100	830	440		160
	Toluene	2900	1600	870	130		83
	Xylene P	380	550	390	146		85.8
	m	710	1500	290	024		
	o	380	510	170	015		
	Eth. Benzene	390	500	350	145		77
	Gasoline	NO	NO	YES	NO		ASu
VENZIA	Benzene						1
	Toluene						
	Xylene						
	TTCE			2	5		1.1
	Gasoline	NO	NO	NO	NO		NO
JOHNSON	Benzene	110	93	092		023	74
	Toluene	13	06	005			20
	Xylene P	21		2		1	1
	m	01		1			
	o	05		1			
	Eth. Benzene		11	10			5.4
	Gasoline	NO	NO	NO	NO	NO	NC
CARPENTER	Benzene	400	3			3.2	1.5
	Toluene	420	10				
	Xylene P	083					
	m	110					
	o	053					
	Gasoline	YES	NO	NO	NO	NO	NO
MARIO PIZZA	Benzene	072			35		6.9
	Toluene	025			3		
	Xylene P	04			3		
	m	05			1		
	o	07			1		
	TCE	031					14
	TTCE		39	33	09		14
	Gasoline	NO	NO	NO	NO	NO	NO

NEW YORK STATE REGISTRY FORM

HAZARDOUS WASTE DISPOSAL SITES REPORT
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

47-15-11(2/80)

Code: 2a

Site Code: 314060

Name of Site: NYSDOT Spill No. 811902

Region: 3

County: Dutchess

Town/City Pawling

Street Address Route 22

Status of Site Narrative:

Commercial area along Route 22, north of Brady Brook and south of Akindale Road, just north of town line of Patterson in Putnam County.

The following parcels, whose wells were tested, indicate gasoline present in well:

- 1) Maxwell Engine Rebuilders
- 2) Inex Venezia, guest house
- 3) Corral Ford
- 4) Heinchon Dairy
- 5) Mario's Pizza

Type of Site: Open Dump ☐
Landfill ☐
Structure ☐

Treatment Pond(s) ☐
Lagoon(s) ☐

Number of Ponds
Number of Lagoons

Estimated Size 20 Acres

Hazardous Wastes Disposed? Confirmed ☒ Suspected ☐

*Type and Quantity of Hazardous Wastes:

TYPE	QUANTITY (Pounds, drums, tons, gallons)
<u>Benzene</u>	<u> </u>
<u>Toluene</u>	<u> </u>
<u>M-xylene</u>	<u> </u>
<u>O-xylene</u>	<u> </u>
<u>Ethyl benzene</u>	<u> </u>

* Use additional sheets if more space is needed.

